

March 1990

# YAKIMA/KLICKITAT PRODUCTION PROJECT PRELIMINARY DESIGN REPORT

## APPENDIX C: YAKIMA AND KLICKITAT PRELIMINARY ENGINEERING REPORTS



DOE/BP-00245-4



This report was funded by the Bonneville Power Administration (BPA), U.S. Department of Energy, as part of BPA's program to protect, mitigate, and enhance fish and wildlife affected by the development and operation of hydroelectric facilities on the Columbia River and its tributaries. The views of this report are the author's and do not necessarily represent the views of BPA.

This document should be cited as follows:

*Yakima River Basin, Salmon and Steelhead Facilities, Preliminary Design Report, CH2M Hill, Klickitat Salmon and Steelhead Hatchery, Preliminary Design Report, R. W. Beck and Associates, Tom Clune, COTR, Bonneville Power Administration, Division of Fish and Wildlife, 318 electronic pages (BPA Report DOE/BP-00245-4)*

This report and other BPA Fish and Wildlife Publications are available on the Internet at:

**<http://www.efw.bpa.gov/cgi-bin/efw/FW/publications.cgi>**

For other information on electronic documents or other printed media, contact or write to:

Bonneville Power Administration  
Environment, Fish and Wildlife Division  
P.O. Box 3621  
905 N.E. 11th Avenue  
Portland, OR 97208-3621

Please include title, author, and DOE/BP number in the request.

**YAKIMA/KLICKITAT PRODUCTION PROJECT PRELIMINARY DESIGN REPORT**

**APPENDIX C:**

**YAKIMA AND KLICKITAT PRELIMINARY ENGINEERING REPORTS**

**Yakima River Basin  
Salmon and Steelhead Facilities  
Preliminary Design Report**

BY  
CH2M Hill

**Klickitat Salmon and Steethead Hatchery  
Preliminary Design Report**

By  
R. W. Beck and Associates

Prepared for:

Tom Clune, COTR  
Bonneville Power Administration  
Division of Fish and Wildlife  
P. O. B o x 3621  
Portland, Oregon 97208-3621

March 1990

**YAKIMA RIVER BASIN**  
**SALMON AND STEELHEAD FACILITIES**  
**PRELIMINARY DESIGN REPORT**

**Prepared for**  
**BONNEVILLE POWER ADMINISTRATION**

**by**  
**CH2M HILL**  
**February 1990**

## CONTENTS

		<u>Page</u>
1	Introduction	1-1
	Authorization	1-1
	Purpose	1-1
	Acknowledgments	1-3
2	Fish Culture Requirements	
	Introduction	2-1
	Program Goals	2-2
	Fish Cultural Criteria	2-4
	Fish Programming	2-7
	Fish Culture Support	2-13
3	Cle Elum Facility Design	3-1
	General Site Description	3-1
	Site Development	3-4
	Water Supply	3-8
	Water Treatment	3-10
	Facility Buildings	3-12
4	Oak Flats Facility Design	4-1
	General Site Description	4-1
	Site Development	4-3
	Water Supply	4-7
	Water Treatment	4-9
	Facility Buildings	4-11
5	Nelson Springs Facility Design	5-1
	General Site Description	5-1
	Site Development	5-3
	Water Supply	5-7
	Water Treatment	5-9
	Facility Buildings	5-11
6	Wapato Facility Design	6-1
	General Site Description	6-1
	Site Development	6-3
	Water Supply	6-7
	Water Treatment	6-8
	Facility Buildings	6-9

	<u>Page</u>	
7	Prosser Facility Design	7-1
	General Site Description	7-1
	Site Development	7-3
	Water Supply	7-7
	Water Treatment	7-9
	Hatchery Building	7-11
8	Acclimation Sites	8-1
	Upper Yakima Spring Chinook	8-1
	Naches Spring Chinook	8-2
	Summer Steelhead	8-2
	Acclimation Site Design	8-3
9	Adult and Juvenile Trapping Facilities	9-1
10	Schedule and Cost	10-1
	Schedule	10-1
	costs	10-1

Appendix A

sea7112/071.50

# **Chapter 1**

## **INTRODUCTION**

### **AUTHORIZATION**

This preliminary design report was prepared by CH2M HILL Northwest, Inc. for the Bonneville Power Administration (BPA) under contract DE-AC79-89BP96455 dated December 1988. The broad scope of the contract was to provide engineering services for studies and preliminary designs for salmon and steelhead facilities in the Yakima River Basin in South Central Washington.

### **PURPOSE**

The purpose of the predesign was to finalize the nature and location of various fish-production facilities in the Yakima Basin in a coordinated fashion that is consistent with the Yakima and Klickitat Rivers Central Outplanting Facility Master Plan (FMC, 1987) and the Report on Refined Project Goals and Management Plan for the Yakima/Klickitat Production Project (May 1989). In essence, this predesign report is intended to form a bridge between the extensive study and

planning done on the project prior to 1989 and the final detailed design, which is planned to start in mid-1990.

The majority of this report is devoted to the production component of the Yakima Basin program. Fish culture programming and vessel requirements are followed by detailed descriptions of individual fish culture facilities. The production goals and rearing vessel size were developed with specific input from the Experimental Design Work Group (EDWG), which deals exclusively with the experimental requirements of the program.

This report will be periodically updated and expanded during the final design process. At this point, there are still several water supply-related issues which remain unresolved. None of these, however, will result in a change in location of the selected sites or the production goals. As these and other unresolved issues, such as flood plain boundaries at some sites, are resolved during final design, they will be incorporated into this document, which will then take the form of the project design memorandum.

## ACKNOWLEDGMENTS

We would like to acknowledge the assistance of the BPA project team, staff of the Yakima Indian Nation, members of the Hatchery Technical Work **Group**, EDWG, and the Bureau of Reclamation (USBR). We also acknowledge the invaluable contribution of our consultant, Mr. Harry Senn, of Fish Management Consultants (FMC) for his development of the fish culture program and the hatchery management plan for the Yakima Basin.

sea71 12/042.50

## **Chapter 2**

# **FISH CULTURE REQUIREMENTS**

## **INTRODUCTION**

This chapter describes the biological and physical fish culture requirements of the hatchery system from which the concepts for the design are formulated. It includes a discussion of the program goals for fish production in the Yakima Basin followed by a brief summary of selected sites. The biological criteria are presented for the water system, adult holding, incubation, rearing, and finally transportation and release. The biological criteria address the water and space requirements, the number and type of vessels, and the related support requirements. To be assured that the components of the system meet all program demands, each life phase from adult capture to the juvenile or smolt transfer into the acclimation sites is analyzed.

## PROGRAM GOALS

### PRODUCTION GOALS

The goal of the Yakima Basin production program is to produce high quality smolts in the required number and at the required locations to meet the objectives of supplementation within the guidelines of the experimental design. The agreed-to production goals by species, subbasin, and numbers of experimental groups are as shown in Table 2-1.

---

**Table 2-1**  
**YAKIMA RIVER BASIN**  
**PRODUCTION GOALS**

<u>Species</u>	<u>Number</u>	<u>Size</u>	<u>Pounds of Production</u>	<u>Number of Experimental Groups</u>
Upper Yakima Spring Chinook	1,150,000	15lb	76,667	15
Naches Spring Chinook	450,000	15/lb	30,000	6
Naches Summer Chinook	200,000	15/lb	13,333	N/A
Naches Summer Steelhead	400,000	7/lb	57,143	12
Fall Chinook	3,600,000	65flb	55,385	18
Lower Yakima Coho	1,550,000	15flb	103,333	3
Naches Coho	<u>450,000</u>	15nb	<u>30,000</u>	6
Total	7,800,000		365,861	

---



The data presented in Table 2-1 are slightly different than shown in previous reports but are generally consistent with the Master Plan and reflect EDWG's most recent requirements for production and experimental design. These production goals are equivalent to what was referred to in the Master Plan as Year 10 goals. EDWG is preparing a separate report that will explain the rate at which the program will develop to meet these ultimate Year 10 goals. For the purposes of this report, facilities will be designed and constructed to accommodate smolt production at the Year 10 levels shown in Table 2-1.

## **FACILITY SITING**

The Draft Environmental Assessment (EA) prepared by BPA in 1989 explains all of the facilities and alternative sites considered in the Yakima Basin. This report will concentrate on those sites finally selected for use in the Yakima Basin program. Table 2-2 lists the various facilities required for the program.

The adult and juvenile trapping facilities are the subject of a separate predesign report being prepared by the Yakima Basin Passage Work Group. Figure 2-1 was taken from the EA and modified to show the locations of the above-listed facilities. At this time, the specific locations of the acclimation sites have not been finalized but the locations shown on Figure 2-1 represent EDWG's most recent plan for the respective stream reaches for acclimation and release.

---

**Table 2-2  
YAKIMA RIVER BASIN  
FISH FACILITIES**

**Central Hatcheries**

Oak Flats  
Cle Elum  
Nelson Springs

**Satellite Facilities**

Wapato  
Prosser

**Acclimation Sites**

12-Summer Steelhead  
15-Upper Yakima Spring Chinook  
6-Naches Spring Chinook

**Adult Trapping Sites**

Roza Dam  
Cowiche Diversion  
Prosser Dam

**Juvenile Trapping Sites**

Roza Dam  
Oak Flats Division  
Prosser Dam

---

**FISH CULTURAL CRITERIA**

**WATER QUALITY AND QUANTITY**

The most important criteria for the fish culture program are water quality and quantity. A brief discussion of water quality and quantity is presented below. A

companion document prepared by the USBR contains detailed information on the suitability of the selected sites to meet these criteria.

### **Water Quality**

The general water quality guidelines for fish culture facilities is taken from the Alaska Department of Fish and Game (1983). The USBR water supply report will compare the recorded water quality at each site with the Alaska criteria. Several criteria have been agreed upon in the hatchery design that relate to disease control. These include:

- The initial incubation of all eggs will be on disease-free water, e.g., spring or well water. Isolation in bucket incubators is suggested initially for steelhead and may be expanded for further use for chinook at a later time.
  
- Rearing will be conducted only with first pass water with the exception of coho and only in the event that site water supply constraints require it.
  
- Second or third pass water can be used for holding adults if site specific water supply constraints require it.

- To reduce stress and potential disease outbreaks, dissolved oxygen gas in the water shall remain 7.0 mg/l or above. Thus, inflowing water or second pass water should be returned to near saturation.
- The rearing of steelhead in raceways or troughs shall be physically isolated from chinook to reduce the chance of disease-bearing water from being easily transferred, e.g., raceways should not have common walls between steelhead and chinook.

Water temperature is a critical parameter for the programming of fish culture. If the desired water temperature cannot be reached from existing sources, water chilling may be required. The water temperature which was assumed to be available at each site is documented in the computer output in Appendix A. These data were taken from existing records and in some cases specific onsite measurements by the USBR. The USBR water supply report presents all available temperature data.

### **Water Quantity**

Based on available temperature data and the program goals at each site, the desired maximum flow rate for fish culture at each site was calculated and is shown

in Table 2-3. Appendix A shows calculated flow and space requirements by species and the desired practical flow rates for normal hatchery operations. These desired flow rates will be compared with the actual available flow rates in the USBR water supply report.

---

**Table 2-3**  
**YAKIMA RIVER BASIN**  
**FISH CULTURE FACILITIES**  
**DESIRED FLOW RATES**

<u>Site</u>	<u>Flow (in CFS)</u>		<u>Total</u>
	<u>Surface</u> <u>Water</u>	<u>Well</u> <u>Water</u>	
Central Hatcheries			
Oak Flats	44	5	49
Cle Elum	17	7	24
Nelson Springs	10	1	11
Satellite Facilities			
Wapato	60	0	60
Prosser	14	1	15
Acclimation Sites			
Each Pond	1.2	0	1.2

---


## **FISH PROGRAMMING**

The programming of each fish species by subbasin and facility in the Yakima River Basin was accomplished by FMC using a computer program which they specifically developed for this purpose. The computer program yields space, **flow**, and food requirements, as well as estimated pollution levels generated by fish culture activities. The detailed computer output is contained in Appendix A. This section deals with the schedule of fish by species, subbasin, and site.


### **SCHEDULES**

Figure 2-2 shows the schedule of fish production by species for a single generation of fish. For clarity, the second generation was not shown. Figure 2-3 shows the same information presented in Figure 2-2 but rearranged by site. Again, no attempt was made to show the second generation of fish. Study of Figures 2-1, 2-2, and 2-3 should make it very clear that this is a complex fish culture program requiring a substantial amount of central control and management, and a significant amount of fish-transfer logistics. This will be discussed later in this chapter.


**UPPER YAKIMA SPRING CHINOOK**  
1,150,000 Fish at Release, 15/lb



**NACHES SPRING CHINOOK**  
450,000 Fish at Release, 15/lb




**FALL CHINOOK**  
3,600,000 Fish at Release, 65/lb




**FIGURE 2-2**  
Yakima Basin  
Fish Culture Schedule  
by Species


**NACHES SUMMER CHINOOK**  
**200,000 Fish at Release, 15/lb**



**COHO**  
**2,000,000 Fish at Release, 15/lb**



**SUMMER STEELHEAD**  
**400,000 Fish at Release, 7/lb**



**FIGURE 2-2 (Continued)**  
 Yakima Basin  
 Fish Culture Schedule  
 by Species

**CLEELUM**

	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M
<b>Life Stage</b>																									
Adult Holding																									
incubation																									
Rearing																									
Final Incubation																									
Rearing																									
<b>Species</b>																									
Upper Yakima Spring Chinook																									
Upper Yakima Spring Chinook																									
Upper Yakima Spring Chinook																									
Naches Spring Chinook																									
Naches Spring Chinook																									
Naches Spring Chinook (to Oak Flats)																									

**NELSON SPRINGS**

	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M
<b>Life Stage</b>																									
Incubation																									
Rearing																									
Adult Holding																									
Incubation																									
Early Rearing (Inside)																									
Rearing																									
<b>Species</b>																									
Fall Chinook																									
Fall Chinook																									
Summer Steelhead																									
Summer Steelhead																									
Summer Steelhead																									
Summer Steelhead (to Oak Flats)																									
Summer Steelhead																									

**OAK FLATS**

	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M
<b>Life Stage</b>																									
Adult Holding																									
incubate to Eyed Eggs																									
Rearing																									
Adult Holding																									
Incubation																									
Rearing/Aclimation																									
Incubation																									
Rearing																									
Acclimation																									
Rearing																									
<b>Species</b>																									
Naches Spring Chinook																									
Naches Spring Chinook																									
Naches Spring Chinook																									
Naches Summer Chinook																									
Naches Summer Chinook																									
Naches Summer Chinook																									
Coho																									
Coho																									
Coho (450,000 Fish)																									
Summer Steelhead																									

**FIGURE 2-3**  
Yakima Basin  
Fish Culture Schedule  
by Site




## **VESSELS**

The programming was based on a discrete number of experimental groups within each stock of fish. Standardized vessels are used throughout the Yakima Basin to allow for the handling of these discrete experimental groups. The details of these vessel requirements and vessel design are presented later in this chapter. As an overview of the programming, however, we have prepared Figures 2-4 through 2-11 to show the vessel and flow usage for both rearing and incubation by station. These schedules include the second generation fish because of the potential for overlapping space and flow requirements.


Figures 2-2 through 2-11 summarize the essence of programming for the Yakima Basin and have received careful review by all concerned parties. The remainder of this chapter is devoted to the details which lead to the development of these figures.

## **LIFE-STAGE CRITERIA**


The programming of the fish from adult capture to smolt release is presented in this section, Table 2-4 presents a summary of the numbers of fish at each life stage for the Yakima River Basin program. Additional details on adult holding and spawning, incubation and rearing are presented in the following sections.



**FIGURE 2-4**  
 Cle Elum Central Hatchery  
 Upper Yakima and Naches Spring Chinook  
 Rearing




**FIGURE 2-5**  
 Cle Elum Central Hatchery  
 Upper Yakima and Naches Spring Chinook  
 Incubation




**FIGURE 2-6**  
 Oak Flats Central Hatchery  
 Naches Spring and Summer Chinook  
 Coho and Summer Steelhead  
 Rearing

	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
<b>FLOW (CFS)</b>													
well water	0	0	0	0	0	5	5	5	5	0	0	0	Well Water
River water	38	40	36	15	15	19	19	23	31	44	38	38	River Water
Returned to River	38	40	36	0	0	0	0	0	0	0	38	38	Returned to River
Returned to Canal	0	0	0	15	15	24	24	28	36	44	0	0	Returned to Canal
Naches-Selah I.D.	0	0	0	130	132	134	136	136	115	108	0	0	Naches-Selah I.D.
River Diversion	38	40	36	130	132	129	131	131	110	108	38	38	River Diversion


**FIGURE 2-6 (Continued)**  
Oak Flats Flow Summary




**FIGURE 2-7**  
 Oak Flats Central Hatchery  
 Naches Spring and Summer Chinook and Coho  
 Incubation




**FIGURE 2-8**  
Nelson Springs Central Hatchery  
Fall Chinook and Steelhead  
Rearing



**FIGURE 2-9**  
 Nelson Springs Central Hatchery  
 Fall Chinook and Steelhead  
 Incubation



**FIGURE 2-10**  
 Wapato Satellite Site  
 Fall Chinook and Coho  
 Acclimation



**FIGURE 2-11**  
 Prosser Satellite Site  
 Fall Chinook Adult Holding and Acclimation  
 Coho Adult Holding

**Table 2-4  
YAKIMA RIVER BASIN  
LIFE-STAGE SUMMARY**

<u>Life Stage</u>	<u>Upper Yakima Spring Chinook</u>	<u>Naches Spring Chinook</u>	<u>Naches Summer Chinook</u>	<u>Fall Chinook</u>	<u>Coho</u>	<u>Summer Steelhead</u>
Adults trapped	1,289	508	243	2,815	2,648	306
Females spawned	412	162	77	1,013	1,191	137
Eggs taken	1,769,000	693,000	308,000	4,557,000	2,857,000	615,000
<b>Eyed eggs</b>	<b>1,627,000</b>	638,000	283,000	<b>3,965,000</b>	2,486,000	566,000
<b>(%)</b>	<b>(92)</b>	<b>(92)</b>	(92)	(87)	<b>(87)</b>	(92)
Survive to first feeding	1,592,000	623,000	<b>277,000</b>	3,737,000	2,343,000	<b>554,000</b>
<b>(%)</b>	<b>(90)</b>	<b>(90)</b>	<b>(90)</b>	(82)	<b>(82)</b>	<b>(90)</b>
Survive to release	1,150,000	450,000	200,000	<b>3,600,000</b>	<b>2,000,000</b>	400,000
<b>(%)</b>	<b>(65)</b>	(65)	(65)	(79)	<b>(70)</b>	<b>(65)</b>

sea7114/013.50

## **Adult Criteria**

Adult brood stock will be trapped at the Prosser, Cowiche and Roza trapping sites. Only short-term holding (one or two days) will be available at these sites. Long-term adult holding and spawning will occur at the central hatcheries and the Prosser satellite facility. The flow criteria for holding adults is 1 gpm/fish for chinook and ½ gpm/fish for coho and 2 gpm/fish for steelhead. The volume criteria is 8 **foot<sup>3</sup>/fish** for chinook, 4 **foot<sup>3</sup>/fish** for coho and 2.5 **foot<sup>3</sup>/fish** for steelhead.

Table 2-5 shows the adult holding criteria for the Yakima Basin. All adult holding vessels will also be used for juvenile rearing with the exception of the fall chinook holding pond at Prosser which will serve as a settling pond.

## **Incubation Criteria**

The general strategy for incubation is to use deep trough incubators (Senn, et al, 1984, pp. 89-93) for all salmon and Isoflow buckets for steelhead. Deep troughs will also be used for steelhead early rearing. The incubation strategy will be to extend with the development rate of all salmon that are to be reared for 12 months or more to a period in time when their first feeding matches closely

**Table 2-5  
YAKIMA RIVER BASIN  
ADULT HOLDING CRITERIA**

	<u>Upper Yakima Spring Chinook</u>	<u>Naches Spring Chinook</u>	<u>Naches Summer Chinook</u>	<u>Fall Chinook</u>	<u>Coho</u>	<u>Summer Steelhead</u>
Eggs required	1,769,000	693,000	308,000	4,557,000	2,857,000	615,000
Eggs per female	4,300	4,300	4,000	4,500	2,400	3,000
Females required	412	162	77	1,013	1,191	205
Pre-spawn mortality (%)	20	20	20	10	10	10
Females taken	515	203	97	1,126	1,324	228
Male to female ratio	1.5:1	1.5:1	1.5:1	1.5:1	1:1	1:1
Adults taken	1,289	508	243	2,815	2,648	456
Adults held at one time	1,289	508	243	2,252	2,119	456
Volume required (ft <sup>3</sup> )	10,312	4,064	1,944	18,016	8,476	1,139
Flow required (gpm)	1,289	508	243	2,250	1,059	912
Raceway	2		1		2	1
Ponds		1		1		

the emergence of fry from the naturally spawning population. Fall chinook and summer steelhead will be incubated on spring water at Neson Springs.

All salmon incubation will include substrate as determined by the hatchery manager. Table 2-6 provides a summary of criteria to be used in the design for incubation. The recommended number of incubation units for each facility is as follows is shown as well as the required flow rate.

### **Rearing Criteria**

The application of the following rearing criteria to the available water supply at each site is detailed in Appendix A. The following density indexes were used for the three types of rearing vessels.

- Raceways                      0.175 lbs/ft<sup>3</sup>/inch
- Ponds                              0.150 lbs/ft<sup>3</sup>/inch
- Acclimation Ponds 0.110 lbs/ft<sup>3</sup>/inch

Flow loading rates were designed according to the following formula for raceway and pond loadings.

$$\text{gpm/lb} = \frac{(\% \text{ food fed})}{(4)(\text{available oxygen, ppm})}$$

**Table 2-6**  
**YAKMA RIVER BASIN**  
**INCUBATION REQUIREMENTS**

	<u>Upper Yakima Spring Chinook</u>	<u>Naches Spring Chinook</u>	<u>Naches Summer Chinook</u>	<u>Fall Chinook</u>	<u>Coho</u>	<u>Summer Steelhead</u>
Eggs spawned	1,769,000	693,000	308,000	<b>4,557,000</b>	2,857,000	615,000
Troughs for <b>eyeing</b>	2	1	1	4	3	82 (buckets)
Flow required ( <b>gpm</b> )	14	7	7	28	21	27
Eggs after <b>eyeing</b>	1,627,000	638,000	283,000	<b>3,965,000</b>	2,486,000	566,000
Density after <b>eyeing</b>	180,000	180,000	180,000	152,000	180,000	180,000
Troughs for hatching	9	4	2	26	14	3
Flow <b>required</b> ( <b>gpm</b> )	90	40	20	260	140	30
Early rearing	--		--	--	--	450,000
Troughs for rearing	--	--	--	--	--	32
Flow required ( <b>gpm</b> )	--		--	--	--	320

Where the available oxygen equals the influent concentration minus effluent concentration. As an example, with available oxygen equal to 4.0 ppm and percentage food fed equal to 2.0, the flow loading rate used for rearing is 0.13 gpm/lb of fish or 8 lbs/gpm. The actual flow rates needed by the fish at each stage of rearing are shown in the computer output in Appendix A.

Based on these criteria and the need for individual experimental groups, it was decided that standard **5,000-ft<sup>3</sup>** concrete raceways of a design similar to that currently used by WDF would be used for rearing. These would be 10 feet wide and 100 feet long (wall to screen) and average 5 feet deep with no kettel.

Rearing ponds will be standardized at 20,000 **ft<sup>3</sup>** and will be designed in keeping with current WDF criteria. The three **45,000-ft<sup>3</sup>** ponds at Wapato are the **only** exception to this standardization of vessels. These ponds for final acclimation of coho will be similar to those used for spring chinook at Chelan PUDs Chiwawa acclimation site. The required rearing vessels for the Yakima Basin are shown in Table 2-7.

**Table 2-7**  
**YAKIMA RIVER BASIN**  
**REARING VESSELS**

	Number of Vessels		
	5,000-ft <sup>3</sup> <u>Raceways</u>	20,000-ft <sup>3</sup> <u>Ponds</u>	45,000-ft <sup>3</sup> <u>Ponds</u>
Cle Elum	18	0	0
Oak Flats	22	5	0
Nelson Springs	7	0	0
Wapato	6	0	3
Prosser	6	1	0

## FISH CULTURE SUPPORT

### FOOD CONSUMPTION

Food consumption was calculated for each station and each stock is documented in Appendix A. Table 2-8 shows a summary of food requirements by station by month. The food requirements shown for Oak Flats, Cle Elum, and Nelson Springs include the food which would be needed at the associated acclimation sites for spring chinook and steelhead. Three 70,000-lb capacity freezer buildings of a type similar to WDF's Klickitat freezer will be provided for the Yakima Basin. One of these buildings will be provided at Oak Flats, Cle Elum, and Wapato. In final design a semitrailer will be considered for the Wapato site to

reduce cost. All required food will be delivered by commercial suppliers to these three main freezer buildings. Hatchery staff will move the required food to walk-in freezers at Nelson Springs, and Prosser Food for acclimation sites will be transported each day to the sites by the fish culturist responsible for these facilities. Two feedings per day are anticipated at the acclimation sites.

---

**Table 2-8**  
**YAKIMA RIVER BASIN**  
**MONTHLY FOOD REQUIREMENTS**  
**BY STATION**

<u>Month</u>	<u>Upper Yakima Basin</u>		<u>Naches Basin</u>		<u>Lower Yakima Basin</u>		<u>Total</u>
	<u>Cle Elum</u>	<u>Elum</u>	<u>Oak Flats</u>	<u>Nelson Springs</u>	<u>Wapato</u>	<u>Prosser</u>	
January	6,139		7,945	9,568			23,652
February	10,852		30,109	17,609			58,570
March	20,362		28,969	4,630	34,755	1,675	90,391
April	2,638		17,729	675	70,536	10,294	101,872
<b>May</b>	5,619		4,535	1,475	12,736	6,203	30,568
June	8,711		9,427	2,969			21,107
July	12,620		15,514	4,944			33,078
August	28,106		32,939	11,814			72,859
September	18,586		31,919	10,184			60,689
October	11,323		29,660	4,727			45,710
November	7,344		8,129	5,610			21,083
December	<u>3,940</u>		<u>7,108</u>	<u>7,169</u>			<u>18,217</u>
<b>Total</b>	<b>136,240</b>		<b>223,983</b>	<b>81,374</b>	<b>118,207</b>	<b>18,172</b>	<b>577,796</b>

---

## **TRANSPORTATION OF FISH**

As explained earlier in this chapter, there will be a substantial movement of fish at various life stages between the facilities in the Yakima Basin. To ensure success of the overall program, these logistical efforts must be carefully designed and managed. There will be two 2,000-gallon tanker trucks, and two 300-gallon tanker trailers to be pulled by 3/4-ton pickups. Eggs will be transported in standard hatchery pickup trucks with canopies. Table 2-9 shows the truck trips and estimated miles per trip required for and estimated miles per trip required for transporting fish in the Yakima program. A total of 321 truck days (one truck day = 8 hours) are estimated for the Yakima Basin program.

## **STAFFING REQUIREMENTS**

An estimate of the staffing requirements for the Yakima Basin was prepared by FMC based on current WDF practice. Table 2-10 shows the estimated staff requirements. This estimate does not include staff required for marking fish and other experimental data collection needs as required by EDWG.

**Table 2-9**  
**YAKIMA RIVER BASIN**  
**FISH TRANSPORTATION REQUIREMENTS**

<u>Stock/ Life Stage</u>	<u>From</u>	<u>To</u>	<u>Start</u>	<u>Finish</u>	<u>Total Number To be Moved</u>	<u>Vehicle</u>	<u>Total Number of Trips</u>	<u>Round Trip Mileage</u>	<u>Total Miles</u>
Upper <b>Yakima</b> Spring Chinook/ Adults	Roza Dam	Cle Elum	5/20	9/30	1,030	Tanker	45	96	4,320
Upper <b>Yakima</b> Spring Chinook/ Adults	Roza Dam	Cle Elum	5/20	9/30	258	Trailer	40	%	3,840
Upper <b>Yakima</b> Spring <b>Chinook/ Presmolts</b>	Cle Elum	Acclimation	2/15	3/15	1,200,000	Tanker	45	40	1,800
<b>Naches</b> Spring and summer Chinook/Adults	Cowiche Diversion	Oak Flats	5/20	9/30	751	Trailer	140	30	4,200
<b>Naches</b> Spring <b>Chinook/Eyed</b> Eggs	Oak Flats	Cle Elum	11/15	11/30	638,000	Pickup	3	150	450
<b>Naches</b> Spring Chinook/Fry	Cle Elum	Oak Flats	9/10	9/18	500,000	Tanker	18	150	2,700
<b>Naches</b> Spring Chinook! Presmolts	Oak Flats	Acclimation	3/1	3/15	460,000	Tanker	18	50	900
Fall Chinook/ Adults	Prosser Dam	Prosser	9/1	12/15	2,252	Tanker	26	2	52
Fall Chinook! Adults	Prosser Dam	Prosser	9/1	12/15	563	Trailer	60	2	120
Fall <b>Chinook/ Green</b> Eggs	Prosser	Nelson Springs	2/1	3/15	4,557,000	Pickup	20	110	2,220
Fall Chinook/ Fry	Nelson Springs	<b>Wapato</b>	3/20	3/30	1,250,000	Tanker	12	24	288

**Table 2-9  
(Continued)**

<u>Stock/ Life Stage</u>	<u>From*</u>	<u>To</u>	<u>Start</u>	<u>Finish</u>	<u>Total Number To be Moved</u>	<u>Vehicle</u>	<u>Total Number of Trips</u>	<u>Round Trip Mileage</u>	<u>Total Miles</u>
Fall Chinook/ Fry	Nelson Springs	<b>Wapato</b>	5/15	5/20	1,250,000	Tanker	18	24	432
Fall Chinook! Fry	Nelson <b>Springs</b>	<b>Prosser</b>	3/15	5/20	1,300,000	Tanker	12	110	1,320
<b>Coho/Adults</b>	<b>Prosser Dam</b>	<b>Prosser</b>	<b>9/20</b>	<b>11/30</b>	2,118	Tanker	16	2	32
<b>Coho/Adults</b>	<b>Prosser Dam</b>	<b>Prosser</b>	<b>9/20</b>	<b>11/30</b>	530	Trailer	16	2	32
<b>Coho/ Green Eggs</b>	<b>Prosser</b>	<b>Oak Flats</b>	<b>9/1</b>	<b>9/30</b>	2,857,000	Pickup	20	140	2,800
<b>Coho/Presmolts</b>	Oak Flats	<b>Wapato</b>	<b>2/28</b>	3/10	1,600,000	Tanker	30	56	1,680
Summer <b>Steelhead/ Adults</b>	<b>Cowiche Diversion</b>	Nelson Springs	<b>9/1</b>	<b>3/15</b>	306	Trailer	40	2	80
Summer <b>Steelhead/ Presmolts</b>	Nelson Springs	Acclimation	<b>2/14</b>	<b>2/16</b>	210,000	Tanker	18	60	1,080
Summer <b>Steelhead/ Fry</b>	Nelson Springs	Oak Flats	<b>11/1</b>	<b>11/4</b>	220,000	Tanker	18	30	540
Summer <b>Steelhead/ Presmolts</b>	Oak Flats	Acclimation	<b>2/20</b>	<b>2/28</b>	210,000	Tanker	18	50	900

**Table 2-10**  
**YAKIMA RIVER BASIN**  
**ESTIMATED STAFF REQUIREMENTS**  
**(person months)**

	<u>Manager</u>	<u>Assistant Manager</u>	<u>Culturist</u>	<u>Temp.</u>	<u>Security</u>	<u>Truck Driver</u>	<u>Pathologist</u>	<u>Maintenance</u>
<b>Cle Elum</b>	12	2	4	6	6	--		--
Oak Flats	12	12	36	10	6	12	12	12
Nelson Springs	12	12	--	6	3	--	--	--
<b>Wapato</b>	--	--	--	8	--	--		--
<b>Prosser</b>	--	--	10	3	3	--		
<b>Upper Yakima Acclimation</b>		--		30				
<b>Naches Acclimation</b>	--	--		36	--	--	--	
<b>Total</b>	<b>36</b>	<b>36</b>	<b>70</b>	<b>99</b>	<b>18</b>	<b>12</b>	<b>12</b>	<b>12</b>

## Chapter 3

# CLE ELUM FACILITY DESIGN

### GENERAL SITE DESCRIPTION

The **Cle Elum** site was chosen as the central hatchery facility for Upper **Yakima** Spring Chinook. In addition, **Naches** Spring Chinook will be incubated and reared at this site prior to their return to the **Naches** basin central hatchery at Oak Flats. The **Cle Elum** site is located **0.9** mile west of the bridge between **Cle Elum** and South **Cle Elum**.


The **5-acre** site is situated near the bank of the old **Yakima** River channel in an undeveloped **140-acre** site. The construction of the Northern Pacific Railroad forced the realignment of the **Yakima** River channel and left the old river channel as a series of ox bow lakes. The railroad embankment acts as a levee to protect the site from floods. The site is approximately at River Mile **184.0** on the **Yakima** River. An aerial photo of the **Cle Elum** site is shown on Figure 3-1.

## **ALTERNATIVE SITES**


Two sites near the town of Thorp were investigated as alternatives to Cle Elum. The Thorp site was at the existing City of Ellensburg water supply facility near the Town Diversion Dam. The Newman site was located across the river from the Thorp site on a 250-acre parcel of land. It was understood that the City of Ellensburg would be willing to sell their facilities including an infiltration pond and a large productive well field. When this option did not develop, the nearby Newman site was investigated. Groundwater which was important to the development of either site did not materialize after geophysical studies and drilling at test wells on the Newman property. As a result, the Thorp and Newman sites were dropped from further consideration and Cle Elum was selected as the site for the Upper Yakima Basin central hatchery.

## **FACILITY SIZE**

Relative to the available space on the site, the hatchery is very small. Ample room is available for the required 18 raceways as well as support facilities. The hatchery site proper will encompass 5 acres. Smaller offsite parcels will be required for a river pump station and well heads (see Figure 3-2). Easements will be required for the short powerline and the 0.5 mile access road. An easement will also be required for the river pump station and its access road.



**FIGURE 3-1**  
 Cle Elum Central Hatchery  
 General Site Plan



C.M.

DSGN					
DR					
CHK					
APVD					
	NO.	DATE	REVISION	BY	APVD

**REUSE OF DOCUMENTS**  
 THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.  
 ©CH2M HILL

BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

YAKIMA RIVER BASIN  
 SALMON AND STEELHEAD FACILITIES  
 PRELIMINARY DESIGN REPORT

**FIGURE 3-2**  
**CLE ELUM CENTRAL HATCHERY**  
**SITE PLAN**

SHEET	
NO.	
DATE	FEB 1990
PROJ	2EAS7133.A0

PRELIMINARY

There exists the potential for wetlands enhancement and joint development of the property east of the site. This would be done in conjunction with the towns of Cle Elum and South Cle Elum.

## **PRODUCTION GOALS REVIEW**

As presented in Chapter 2, the production goals for this facility include adult holding of Upper Yakima Spring Chinook and incubation and rearing of Upper Yakima and Naches Spring Chinook. No fish are planned to be released from this facility. The 1.15 million Upper Yakima Spring Chinook will be outplanted to 15 acclimation ponds and the 450,000 Naches Spring Chinook would be returned to Oak Flats for final rearing prior to outplanting to 6 Naches basin acclimation sites.

As explained in Chapter 2, the Cle Elum central hatchery will have eighteen 5,000-cubic-foot raceways for rearing Upper Yakima and Naches Spring Chinook. Two of these raceways will be specially modified to hold adult Upper Yakima Spring Chinook. The raceways will be supplied with water from the lake pump station. The adult holding raceways will also be supplied by first pass well water.

## **CURRENT LAND USE AND OWNERSHIP**

Currently, the site is undeveloped. There is a Puget Power transmission line running just east of the hatchery facility, and as mentioned earlier the railroad runs the length of the site along the Yakima river. Parts of the site are used as undeveloped camp grounds and some trash dumping has occurred.

All of the proposed facilities are located in unincorporated Kittitas County, although, part of incorporated South Cle Elum lies just east of the site. The lands are currently owned by either the Plum Creek Timber Company or Burlington Northern.

## **SITE DEVELOPMENT**

The following is a discussion of the items of work required to improve the Cle Elum site for use as the central hatchery for the Upper Yakima Basin.

### **ACCESS ROADS**

There are existing access roads throughout the site but they are in need of clearing and resurfacing with gravel before they can serve as adequate access for

the central hatchery. Roads to be improved are shown on Figure 3-1. Onsite roads will be gravel surfaced.

## **DRAINAGE AND SNOW REMOVALS**

Site grading will be designed to ensure adequate drainage. Drainage provisions at this site will be minimal due to the proximity of the ox bow lakes. Snow removal from the access road will be contracted to Kittitas County or the City of Cle Elum. Onsite snow removal will be accomplished by the hatchery staff with use of a plow mounted on a 4-wheel-drive pickup.

## **CONSTRUCTION CLEARING AND GRUBBING**

Clearing and grubbing will be required for the entire hatchery site. The site was selected to retain the buffer of trees between the hatchery and the ox bow lake. Some trees will need to be cleared as part of the upgrading of the existing access roads. Most of the river pump station will be constructed on the existing rip rap dike. If one or more of the acclimation ponds called for in the Cle Elum area are put next to the river pump station, further clearing may be needed. At this point, the 12.5KV transmission line to the river pump station is assumed to follow the access road or the Burlington Northern Railroad right-of-way. Clearing for the transmission line should be minimal.

## **SITE WORK AND SLOPE PROTECTION**

At this point, it is assumed that an earthwork balance is obtainable on the site. Only select backfill material and gravel surfacing material will be imported. Final design flood levels will confirm this assumption. If calculated flood levels require that the structure be elevated higher than those assumed imported material will be acquired at gravel pits on site. Fill slopes will be 3:1 and protected with hydroseeding, and top soil will be imported for the yard area around the residences.

## **WETLANDS**

The hatchery site was selected to avoid existing wetlands on site. Only water related structures such as the access road across the ox bow lake and the pump stations will encroach on the wetlands. An increased flow will pass through the wetlands due to the operation of the hatchery. Currently 5 to 10 cfs flows through the ox bow lakes. This flow may be increased to 20 cfs during peak hatchery operations.

## **FLOOD ANALYSIS**

The Burlington Northern Railroad tracks and the associated riprapped embankment protect the site from direct flooding from the Yakima River. A Federal Emergency Management Agency (FEMA) study (May 1981) shows the hatchery area as within the 100 year flood plain but not at all in the floodway. The only direct hydraulic connection between the site and the river is by way of the culvert under the railroad track about 2,000 feet east of the site. The 100 year flood level at that point is at elevation 1920.0. Unless there is substantial leakage through the railroad embankment, the 100 year flood level at the hatchery site should then be 1920.0. A detailed review of this study and its findings is recommended for final design.

## **POWER SUPPLY**

Electrical power for the Cle Elum central hatchery will be provided by Puget Power Company. The estimated electrical loads for the Cle Elum site are shown in Table 3-1. Their 12.5KV 3 phase power lines run within 200 feet of the hatchery site. A diesel generator backup will be provided to serve power to one-half of the pumping load and other essential services in case of a power outage. It is anticipated that the river pump station will be treated as a separate load by the power company. However, we recommend that serving that load from the main hatchery be investigated in final design.

---

**Table 3-1**  
**ESTIMATED ELECTRICAL LOADS**

<u>Description</u>	<u>Quantity</u>	<u>Horsepower (ea)</u>	<u>KVA t a l )</u>
River Pumps	3	20	60
Lake Pumps	4	30	120
Well Pumps	4	10	40
Hatchery Building	1	--	50
Incubation Building	1	--	110
Freezer Building	1	--	20
Electrical Control Building	1	--	20
Residences	3	--	60
Pole Barn	1	--	20
Cleaning Waste Aerators	2	10	20
Educator Pumps	4	7.5	30
Spray Pumps	2	10	20
Site Lighting	--	--	<u>2</u>
			<b>572</b>

---

## WATER SUPPLY

As presented in Chapter 2, the Cle Elum central hatchery will have need for well water (3 cfs), river water (17 cfs), and infiltration gallery water (4 cfs) at various times during the year. This section presents the design concepts for each water source.

## **WELL WATER**

The **USBR** water supply report has complete details on the **hydrogeologic** study done to date on the site. A production well and an observation well have been drilled into an artisan aquifer. It is assumed that four production wells may be required to provide the needed 4 **cfs**.

## **RIVER WATER**

As shown on Figure **3-1**, the river pump station is located about **0.8** mile southwest of the hatchery site. River water pumped at that site will be discharged into the ox bow lake system which is basically the old **Yakima** River channel. From there, the water will flow to the pump station which is adjacent to the hatchery site. During final design, alternatives to this pump station will be considered. For example, it may be possible to use a gravity diversion through the railroad embankment at that same point and avoid the expense of pumps. It also may be possible to use an infiltration gallery approach at a site on the north side of the railroad embankment opposite the proposed pump station to obtain the required flow rate through the old river channel gravels.

## **INFILTRATION GALLERY**

The existing ox bow lake flow is made up primarily of shallow groundwater which continues to infiltrate onto the site through the railroad embankment along the old river channel. As much as 4 cfs of that flow currently may be available for use in the hatchery. A slurry trench cutoff wall will be investigated during final design to see how much water is available from this source. The pump station sited on the shore of the ox bow lake would pump this flow and any supplemental river water to the hatchery site.

## **MISCELLANEOUS WATER SUPPLY**

Domestic water supply will be taken from one of the hatchery wells. Fire protection will be provided by a fire alarm system and chemical fire extinguishers. No water-based fire fighting system is planned. A tanker fill system will be provided on station.

## **WATER TREATMENT**

Water used at the Cle Elum central hatchery will become contaminated with byproducts of fish culture. These include fish waste, unused food, disease-control

chemicals, and river sediment settled out in rearing vessels. The following is a discussion of proposed facilities to deal with water treatment.

### **HATCHERY EFFLUENT**

Water which has passed through adult holding and rearing vessels will be discharged directly to the **Yakima** River by way of the existing ox bow lake system. The existing culvert under the railroad embankment will have to be improved to allow for a controlled release of the hatchery flow. Provisions will be made to preclude the returning adults from entering the ox bow lakes.

### **CLEANING WASTE**

A vacuum cleaning waste system in keeping with current **WDF** design practice will be installed for the **18** raceways. The proposed system includes concrete holding pond is capable of holding **5,000** cubic feet in the top 3 feet of depth. This system is similar to that provided at the **Eastbank** Hatchery. It would be **30** feet by **56** feet in plan, and depending on final site grades, may require an **influent** booster pump to lift the cleaning waste into the cleaning wastepond. One standard **WDF** educator pump will be provided for each of the raceway groups. Two

10 horsepower aerators are anticipated for the cleaning waste pond. Adult fish held on site will be treated with **formalin** however at this time there is no plan for specific treatment of water during these operations.

## **SEWAGE TREATMENT**

Domestic sewage from the hatchery building and residences will be treated **onsite** in a septic tank and drainfield. A sewage lift station may be required to deliver flow to the drainfield if it is located at a higher elevation than the buildings. Local health department requirements will guide the design.

## **FACILITY BUILDINGS**

The following is a description of the buildings to be provided at the **Cle Elum** central hatchery.

### **HATCHERY BUILDING**

This **40-foot** by **60-foot** frame building will include the following rooms.

<u>Description</u>	<u>Size (feet)</u>
Visitor Center	20 x 30
Visitor Restrooms	2@ 10 x 10
Office	14 x 15
Lunch Room	15 x 20
Locker Room	12 x 17
Restroom	8 x 7
Mechanical Room	12 x 14
Storage	11 x 14

### **INCUBATION BUILDING**

This 45-foot by 60-foot prefabricated metal building will contain 20 deep trough incubators in a 40-foot by 45-foot room. In addition, there will be a 10-foot by 20-foot egg picking room, a 10-foot by 20-foot lab, and a 9-foot by 20-foot mechanical room.

### **FREEZER BUILDING**

This 25-foot by 60-foot prefabricated metal building will be designed to be similar to the **WDF Klickitat** freezer building. It will have a frozen fish food capacity of 70,000 lbs and will serve as the central freezer for the Upper **Yakima Basin**.

## **ELECTRICAL CONTROL BUILDING**

This **25-foot** by **30-foot** building will contain the electrical equipment for the hatchery as well as a **150 KW** diesel generator. Power will be distributed to the various buildings on the hatchery site from this building.

## **POLE BARN**

A **40-foot** by **48-foot** pole barn will be provided for storage and a shop. The tanker truck assigned to this station will be stored in this structure.

## **RESIDENCES**

These **1,600** square foot single family residences will be provided on this station. They will have two car garages and will be of a style selected during final design.

## Chapter 4

# OAK FLATS FACILITY DESIGN

## GENERAL SITE DESCRIPTION

The Oak Flats site was chosen as the central hatchery facility for the **Naches** spring and summer chinook and **coho**. Some steelhead rearing also will occur on this site. The site is on the left bank of the **Naches** River just downstream of the abandoned City of **Yakima** water supply intake. The site lies between State Route **410** (Chinook Pass highway) and the **Naches** River, **5.7** miles west of the town of **Naches**, at River Mile **19.3**.

## FACILITY SIZE

As shown on Figure **4-1**, the **6.7** acre facility fits nicely on the site between the highway and the existing ponds. Although a detailed flood plain study will not be completed until final design, the site will probably be out of the **100** year flood plain and will definitely be outside the floodway. The hatchery facility will share the site with the proposed relocated diversion and intake for the **Naches--Selah** Irrigation District. River water supply for the hatchery will be pumped from the


canal downstream of the new fish screens. The hatchery site and both the existing and proposed diversion facilities for the **Naches Selah** I.D. can be seen on **Figure 4- 1**.

As with the **Cle Elum** site, there exists at Oak Flats the potential for wetlands enhancement and preservation of wildlife habitat. There is also potential for nature trails and an interpretive center.

## **PRODUCTION GOALS REVIEW**

The production goals for the Oak Flats facility are spelled out in Chapter **2**. In summary, they include adult holding of **Naches** spring and summer chinook, incubation of **Naches** spring and summer chinook and **coho**, and rearing of the above species plus some steelhead rearing. As a central hatchery, there are no plans for release of fish directly from Oak Flats to the **Naches** River. Two million **coho**, **200,000 Naches** summer chinook, **450,000 Naches** spring chinook, and **200,000** steelhead are programmed for this site.

As explained in Chapter **2**, the Oak Flats central hatchery will have twenty-two **5,000-cubic-foot** raceways for rearing. One of these raceways will be specially modified to hold adult **Naches** summer chinook. The raceways will be supplied with river water from the canal pump station. The adult holding raceway will also



Approximate Scale 1" = 400'

FIGURE 4-1  
Oak Flats Central Hatchery  
General Site Plan

be supplied by first pass well water. The Oak Flats site also will have five 20,000 cubic foot ponds for rearing coho and summer chinook. One of these ponds will be specifically modified to accommodate adult Naches spring chinook.

## **CURRENT LAND USE AND OWNERSHIP**

The site is currently vacant land owned by the City of Yakima. Preliminary discussions with the City indicate a willingness to lease the site on a long-term basis. The site is in unincorporated Yakima County.

## **SITE DEVELOPMENT**

The following is a discussion of the items of work required to improve the Oak Flats site for use as a central hatchery.

### **ACCESS ROADS**

Two short access roads will connect the site with Highway 410. One of these is an existing rough access road for the Old City of Yakima intake. This will have to be reconstructed to meet state and county road standards. The second access point will be a new one connecting the residences with Highway 410 for the

exclusive use of the hatchery staff and their families. These access points can be seen on Figure 4-2.

#### **DRAINAGE AND SNOW REMOVAL**



Site grading will be designed to ensure adequate drainage. Drainage provisions at this site will be minimal because of the proximity of the existing ponds. Snow removal from the access roads and onsite roads will be accomplished by the hatchery staff with the use of a plow mounted on a 4-wheel-drive pickup.

#### **CONSTRUCTION CLEARING AND GRUBBING**

Clearing and grubbing will be required for the entire hatchery site. However, this effort will be substantially less than at the Cle Elum site because the Oak Flats site is generally open with very few trees.

#### **SITE WORK AND SLOPE PROTECTION**

At this point, it is assumed that an earthwork balance is obtainable on the site. Only select backfill material and gravel surfacing material will be imported. Final design flood levels will be needed to confirm this assumption. Fill slopes will be



	DESIGN				<b>REUSE OF DOCUMENTS</b> THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF C&M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF C&M HILL.	BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	YAKIMA RIVER BASIN SALMON AND STEELHEAD FACILITIES PRELIMINARY DESIGN REPORT	<b>FIGURE 4-2</b> <b>OAK FLATS CENTRAL HATCHERY</b> <b>SITE PLAN</b>	SHEET NO.
	DR								DATE FEB 1990
	CHK								PROJECT NO. 87133.AG
	APVD	NO.	DATE	REVISION					BY

PRELIMINARY

3:1 and protected with **hydroseeding**, and top soil will be imported for the yard area around the residences.

## **WETLANDS**

The hatchery site was selected to avoid existing wetlands on site. An increased flow will pass through the existing ponds in the nonirrigation season because of the operation of the hatchery. An improved outlet channel from the ponds to the Naches River will be required.

## **FLOOD ANALYSIS**

A **FEMA** study (June 1985) shows the hatchery area is within the 100 year flood plain. This area was only studied by approximate methods and as a result, no detailed floor profiles or floodway determination exists for the site. A detailed floor study will be conducted as part of the final design to aid in the final hatchery siting as well as the design of the new **Naches--Selah** ID diversion dam.

## POWER SUPPLY

Electrical power for the Oak Flats central hatchery will be provided by Pacific Power and Light Company. Currently, their 12.5KV 3-phase power lines run near the hatchery site. This line may have to be relocated to the north along the highway. A diesel generator backup will be provided to serve power to one-half of the pumping load and other essential services in case of a power outage. It is anticipated that the residences will be treated as a separate load by the power company. The estimated electrical loads for the Oak Flats site are presented in Table 4-1.

---

**Table 4-1**  
**ESTIMATED ELECTRICAL LOADS**

<u>Description</u>	<u>Quantity</u>	<u>Horsepower (ca)</u>	<u>KVA (total)</u>
Canal Pump	4	45	180
Well Pump	4	10	40
Hatchery Building	1	--	50
Research Center			75
Incubation Building	1	--	110
Freezer Building	1		20
Electrical Control Building	1	--	20
Residences	4	--	75
Pole Barn	1	--	20
Cleaning Waste Aerators	2	10	20
Educator Pump	4	7.5	30
Spray Pump	3	10	20
Site Lighting	--		<u>2</u>
			662

---

## **WATER SUPPLY**

As presented in Chapter 2, the Oak Flats central hatchery will have need for well water (5 cfs) and river water (44 cfs) at various times during the year. This section presents the design concepts for each water source.

### **WELL WATER**

The USBR water supply report has complete details on the hydrogeologic study done to date on the site. Two production wells and an observation wells have been drilled on the site. It is hoped that four production wells could provide the needed 5 cfs. However, preliminary results from the pump test indicated that it will be difficult to produce that much flow. If sufficient ground water is not found on site mechanical chillers may be needed to provide water cool enough for adult holding in the summer. It may be more economical to move the adult holding to another site.

## **RIVER WATER**

The **Naches--Selah** I.D. intake is just downstream of the proposed hatchery site. Preliminary discussions between the district and **BPA** have identified the potential for moving the point of diversion for the district's intake and fish screens to the site of the Old City of **Yakima** intake.

The design details of this new diversion dam, intake, fish screens, and large diameter irrigation pipe are the subject of a preliminary design study being conducted by the **Yakima** Basin Passage Group. A schematic representation of these facilities is shown on Figures **4-1** and **4-2**.

The water supply arrangement of the hatchery site would include nonconsumptive use of irrigation water during the irrigation season. Effluent from the hatchery would be returned to the district for use in irrigation. In the nonirrigation season, hatchery effluent would be discharged first to the existing **onsite** ponds and then to the **Naches** River. Figure **2-6** shows the relative quantities of flow for the different uses on site. A pump station is required to provide river water to the raceways and ponds.

## **INFILTRATION GALLERY**

Provisions for a river bed infiltration gallery is shown in Figure 4-2. This system may be required to provide for winter time hatchery operations when the fish screens and canal are down because of the icing or maintenance.

## **MISCELLANEOUS WATER SUPPLY**

Domestic water supply will be taken from one of the hatchery wells. Fire protection will be provided by a fire alarm system and chemical fire extinguishes. **NO** water-based fire fighting system is planned. A tanker fill system will be provided at a point next to the pump station.

## **WATER TREATMENT**

Water used at the Oak Flats central hatchery will become contaminated with by-products of fish culture. These include fish waste, unused food, disease-control chemicals, and river sediment settled out in rearing vessels. The following is a discussion of proposed facilities to deal with water treatment.

## **HATCHERY EFFLUENT**

Water which has passed through adult holding and rearing vessels will be discharged either to the **Naches--Selah** I.D. or to the **Naches** River by way of the existing **onsite** ponds. Depending on final site grades hatchery effluent will flow by gravity to both discharge points.

## **CLEANING WASTE**

A vacuum cleaning waste system in keeping with current **WDF** design practice will be installed for the **22** raceways. The proposed system includes concrete holding pond is capable of holding **5,000** cubic feet in the top 3 feet of depth. This system is similar to that provided at the **Eastbank** Hatchery. It would be **30** feet by **56** feet in plan, and depending on final site grades, may require an cleaning waste booster pump to deliver the cleaning waste to the cleaning waste pond. One standard **WDF** educator pump will be provided for each of the raceway groups. Two **10** horsepower aerators are anticipated for the cleaning waste pond. Adult fish held on site will be treated with formalin: however, at this time there is no plan for specific treatment of water during these operations.

## SEWAGE TREATMENT

Domestic sewage from the hatchery building, research center and the residences will be treated onsite in a septic tank and drain field. A sewage lift station may be required to deliver flow to the drain field if it is located at a higher elevation than the buildings. Local health department requirements will guide the design.

## FACILITY BUILDINGS

The following is a description of the buildings to be provided at the Oak Flats central hatchery.

### HATCHERY BUILDING

This 40-foot by 60-foot frame building will include the following rooms.

<u>Description</u>	<u>Size (feet)</u>
Visitor Center	20 x 30
Visitor Restrooms	2@ 10 x 10
Office	14 x 15
Lunch Room	15 x 20
Locker Room	12 x 17
Restroom	8 x 7
Mechanical Room	12 x 14
Storage	11 x 14

## **INCUBATION BUILDING**

This 45-foot by 60-foot prefabricated metal building will contain 20 deep trough incubators in a 40-foot by 45-foot room. In addition, there will be a 19-foot by 20-foot egg picking room, a 10-foot by 20-foot lab, and a 9-foot by 20-foot mechanical room.

## **FREEZER BUILDING**

This 25-foot by 60-foot prefabricated metal building will be designed to be similar to the **WDF Kittitas** freezer building. It will have a frozen fish food capacity of 70,000 lbs.

## **ELECTRICAL CONTROL BUILDING**

This 25-foot by 30-foot building will contain the electrical equipment for the hatchery as well as a 150 KW diesel generator. Power will be distributed to the various buildings on the hatchery site from this building.

## **POLE BARN**

A 40-foot by 48-foot pole barn will be provided for storage and a shop. The tanker truck assigned to this station will be stored in this structure.

## **RESIDENCES**

Three 1,600 square foot single family residences will be provided on this station. They will have two car garages and will be of a style selected during final design.

## Chapter 5

### NELSON SPRINGS FACILITY DESIGN

#### GENERAL SITE DESCRIPTION

The Nelson Springs central hatchery is located at the confluence of Buckskin Creek and a creek fed by many springs in the **Gleed** Valley called **Nelson** Springs. This site was selected as the central hatchery for fall chinook and summer **steelhead**. The Nelson Springs site is adjacent to River Mile **3.4** on the **Naches** River just **northwest** of the City of **Yakima**. The site was selected because of a good spring water supply which in recent years has been used by the Northwest Steelheaders in conjunction with Washington Department of Wildlife to rear steelhead.

#### FACILITY SIZE


Nelson Springs is a small site relative to the various project components that are required. As shown on Figure **5-1**, the seven raceways will fit on the vacant farm land between the two creeks. The existing house and some of the old buildings

on the site will be adapted for hatchery use. A new house will be built southwest of the existing home. Existing flood plain maps of the site are suspect and until a detailed flood study is completed during final design! it is not clear where the floodway for the **Naches** River is. The results of that study may provide more land which can safely be developed on the site.

## **PRODUCTION GOALS REVIEW**

As presented in Chapter 2, the Nelson Springs site will provide for adult holding, incubation, and rearing of **Naches** summer steelhead. In addition, fall chinook will be incubated and reared at this station. Four hundred thousand steelhead and 3.6 million fall chinook will be hatched and reared at **Nelson Springs**. One-half of the steelhead will be transferred to the Oak Flats site in late October with the remainder staying at Nelson Springs until late January. before they are transferred to acclimation sites. The fall chinook are reared at Nelson Springs until mid-March when one-third are transferred to **Prosser** and one-third are transferred to **Wapato** for final acclimation. The remaining one-third are transferred at a later time to **Wapato** for final acclimation.

Seven 5,000 cubic feet concrete raceways will be provided with one of those modified to hold and spawn steelhead. The raceways, as shown in Figure 5-1, are located on vacant farm land between **Nelson Springs** and **Buckskin Creek**. Two



DESIGN					
OR					
CHK					
APVD					
	NO.	DATE	REVISION	BY	APVD

**REUSE OF DOCUMENTS**  
 THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

SCALE: ONE INCH ON ORIGINAL DRAWING.  
 IF NO ONE INCH ON THIS SHEET, ADJUST SCALE ACCORDINGLY.

**YAKIMA RIVER BASIN  
 SALMON AND STEELHEAD FACILITIES  
 PRELIMINARY DESIGN REPORT**

**FIGURE 5-1  
 NELSON SPRINGS CENTRAL HATCHERY  
 SITE PLAN**

SHEET	
NO.	
DATE	FEB 1980
PROJECT NO.	81A2/138.20

PRELIMINARY

raceways are kept separate from the others to allow the local sportsmen's group to continue to participate in the feeding of steelhead.

## SITE DEVELOPMENT

The following is a discussion of the items of work required to improve the Nelson Springs site for use as the central hatchery for fall chinook and summer steelhead.

### **ACCESS ROADS**

Since the site has been used in the past as a steelhead, rearing station adequate access roads already exist at the site. To improve access to the site and reduce dust, the access road will be paved with **asphaltic** concrete for an approximate distance of **800** feet to connect with the existing paved road. **Onsite** roads will be gravel surfaced. The adequacy of existing bridges and culverts will need to be verified during final design. Figure **5-1** shows the **onsite** roads and part of the access road.

## **DRAINAGE AND SNOW REMOVAL**

Site grading will be designed to ensure adequate drainage. Drainage provisions at this site will be minimal since Buckskin Creek and Nelson Springs run directly through the site. Snow removal from the access road will be contracted to Yakima County. Onsite snow removal will be accomplished by the hatchery staff with use of a plow mounted on a 4-wheel-drive pickup.

## **CONSTRUCTION CLEARING AND GRUBBING**

Clearing of existing large trees on the site will be minimized. There will be some trees removed to improve access to site facilities, such as raceways and the incubation building. Much of the area to be occupied by the raceways and new building is vacant farmland which has already been cleared. Grubbing will be required in areas where structures are to be placed.

## **SITE WORK AND SLOPE PROTECTION**

Finished grade at the site will be approximately elevation 1,164.5, which is the average elevation around the existing raceway and the existing home. This elevation may have to be adjusted during final design pending the outcome of a detailed flood plain study. This grade will result in up to 2,000 cubic yards of

excess material being generated during the construction of the raceways. Some of this excess material will be used to fill in the old raceway and some will be used to raise the grade of the access road and the general site. Disturbed areas such as fill slopes will be **hydroseeded** after construction.

At this time, no special flood proofing is planned. The **100** year flood level reported in the June **1985 FEMA** flood insurance study is very suspect. As a result, a detailed flood plain and flood way determination of the **Naches** River will be required for final design. There have been no reports of flooding from Buckskin Creek of Nelson Springs.

## **WETLANDS**

With the exception of Buckskin Creek and Nelson Springs, there are no other wetlands on the site. As a result, no net loss of wetlands is anticipated.

## **FLOOD ANALYSIS**

As mentioned earlier, the Nelson Springs site was covered in a detailed **FEMA** study. That report shows a **100** year flood elevation of **1,174** on the site. The general ground elevation on the site is **1,164**. A **10-foot** depth of flooding at the site is **very** suspect and as a result, it is recommended that a detailed flood study

be conducted at the site. It is possible that some part of the site is in the 100 year flood plain; however, no structures will be placed in the floodway.

## POWER SUPPLY

Electrical power for the Nelson Springs site will be provided by Pacific Power and Light Company. Their 12.5 kV, 3 phase power line is near the site. A diesel generator backup will be provided to serve one-half of the pumping load. The estimated load at the site is shown in Table 5-1.

---

**Table 5-1**  
**ESTIMATED ELECTRICAL LOADS**

<u>Description</u>	<u>Quantity</u>	<u>Horsepower (ea)</u>	<u>KVA (total)</u>
Pumps	3	15	45
Hatchery Building	1	--	50
Incubation Building	1	--	80
Cleaning Waste Aerator	1	10	10
Educator Pumps	2	7.5	15
Spray Pumps	2	5	10
Electrical Building	1	--	2
Pump Building	1	--	2
Pole Barn	1	--	10
Site Lighting	1	--	1
			<b>224</b>

---

## **WATER SUPPLY**

As presented in Chapter 2, the Nelson Springs site will have the need for **Naches** River water (5 cfs), **Buckskin Creek** water (8 cfs), **Nelson Springs** water (8 cfs), and well water (1 cfs). This section presents the design concepts for each water source.

### **NACHES RIVER WATER**

Up to 5 cfs of water from the **Naches** River to provide a redundant water supply and needed temperature control for steelhead adult holding and juvenile **presmolt** acclimation. A screened intake for this water will be designed as an integral part of the new attraction water supply system for the **Cowiche Dam fishway** and adult trapping facility. It is assumed that this water supply from the **Naches** River will flow by gravity to a central pumping station on site as shown in Figure 5-1.

Preliminary design considerations included using the existing spring creek and highway and railway culverts to route the flow to the **Buckskin Creek** pump station. However, for this preliminary design a 1,900-foot-long, 24-inch-diameter pipeline from **Cowiche Dam** to **Nelson Springs** will be used. Although more costly, the pipe alternative will ensure that a truly redundant supply is provided for the hatchery.

## **BUCKSKIN AND NELSON SPRINGS CREEK WATER**

Up to eight cfs from both Buckskin Creek and Nelson Springs will be pumped to the raceways. This will require four 10 horsepower pumps. Flow control will be incorporated into the pump station to provide a constant level in the respective creeks so that there will always be 1 cfs of flow over the control weir. Depending on the results of the **USBR** water supply report water from the two creeks may be blended first before pumping. This will affect the design of the control weirs.

## **WELL WATER**

The well drilled in the center of the site did not produce sufficient flow for incubation (see **USBR** water supply report). In final design, two additional wells will be drilled in the northwest corner of the site which will hopefully yield 1 cfs. If well water cannot be obtained on the site, spring water will be used for incubation.

**Diversion Weirs.** Two diversion weirs will be constructed at the confluence of Nelson Springs and Buckskin Creek. These weirs are required to provide enough depth for the fish screens and the pump intakes. The weirs will be as low as possible to minimize the barrier to **coho** which reportedly use the creeks. A

series of low weirs downstream from these diversion weirs and the confluence may be required to facilitate upstream passage. All weirs may be part of a single concrete structure which also will serve as the outflow point for hatchery effluent. This outflow will be screened for adults. As mentioned above, if the results of the **USBR** water supply report indicate that the two creeks provide basically the same quality water, there may be a single diversion weir which would mix the flow before pumping.

#### MISCELLANEOUS WATER SUPPLY

Domestic water for the existing residence will be supplied by wells, one of which already exists. A tanker fill station will be provided with a booster pump if needed. Fire Protection will be provided by the fire alarm system and chemical fire extinguishers. No water-based fire fighting system is planned.

### **WATER TREATMENT**

#### HATCHERY EFFLUENT

Water passing through the raceways will be discharged directly to the creek below the control weirs. **As** mentioned earlier, this outfall will be screened to prevent

returning adults from entering. At certain times the hatchery effluent will makeup **90** percent of the flow of the creek. No special treatment is planned for general hatchery effluent.

**Cleaning Waste.** A vacuum cleaning waste system in keeping with current **WDF** design practice will be installed for the seven raceways. The proposed system includes concrete holding pond capable of holding **1,700** cubic feet in the top **3-feet** of depth. This system is similar to that provided at the **Eastbank** Hatchery. It would be **20** feet by **28** feet in plan, and depending on final site grades, may require an effluent booster pump to return the effluent to the main site drain. One standard **WDF** educator pump will be provided for each group of raceways. A **10** horsepower aerator is anticipated for the cleaning waste pond.

Adult steelhead to be held **onsite** may be treated with formalin; however, at this time there is no plan for specific treatment of water during these operations is planned.

## **DOMESTIC SEWAGE**

Domestic sewage from the hatchery building will be treated **onsite** in a septic tank and drainfield. A sewage lift station may be required to deliver flow to the **drain-**

field if it is located at a higher elevation than the hatchery building. **Local** health department requirements will guide the design.

## **FACILITY BUILDINGS**

The following is a description of buildings to be provided at the Nelson Springs central hatchery.

### **HATCHERY BUILDING**

This 40-foot by 40-foot frame building will include the following rooms.

<u>Description</u>	<u>Size (feet)</u>
Office	15 by 15
Restroom	8 by 10
Lunchroom	15 by 20
Locker Room	16 by 20
Mechanical Room	15 by 14
Laboratory	15 by 12

This will be an energy-efficient building with air conditioning and electric heat.

The building will have concrete floors.

## **INCUBATION BUILDING**

This 45-foot by 80-foot building will include the following rooms.

<u>Description</u>	<u>Size (feet)</u>
Steelhead Incubation Room	16 by 45
Egg Picking Room	18 by 19
Laboratory	18 by 19
Salmon Incubation Room	46 by 45

The steelhead incubation room will be designed to accommodate 80 isoflow buckets in eight deep troughs, early rearing of some of the steelhead will also be accomplished in these troughs. Additional troughs in the salmon incubation room will be used by the steelhead for early rearing, but the fall chinook are programmed to be out of the incubation building by that time. If fall chinook remain in the building during the steelhead early rearing period a curtain will be used to separate the two.

## **RESIDENCES**

**One** existing residence on site will be remodeled and a new 1600-foot<sup>2</sup> residence will be built. The new residence will have a two car garage and will be of a style determined during final design.

## **PUMP BUILDING**

The 20-foot by 40-foot pump building will house the pumps and motor controls for the hatchery. Three 15 horsepower pumps will be available to pump from either creek or the Naches River.

## **POLE BARN**

The 30-foot by 48-foot pole barn will provide room for a walk-in freezer, a shop, and covered storage for hatchery vehicles.

## **ELECTRICAL CONTROL BUILDING**

This 20-foot by 30-foot building will house the diesel generator, auto transfer-switches, and associated electrical equipment.

## Chapter 6

### WAPATO FACILITY DESIGN

#### GENERAL SITE DESCRIPTION

The **Wapato** satellite facility is located between the **Wapato** Canal, and the Union Pacific Railroad, and U.S. Route **97** approximately **1.2** miles northwest of the town of Parker and **0.4** miles downstream of **Wapato** Dam. The site is at River Mile **106.2** on the right bank of the **Yakima** River on government property adjacent to the recently constructed **Wapato** Canal fish screens.

#### ALTERNATIVE SITES

A site near Sunnyside Dam was considered during earlier planning but was eliminated because of flood plain constraints. The **Wapato** site was originally proposed to be fed by gravity on a site east of the canal. The selected site west of the canal will require pumping, but is more protected from floods by the Burlington Northern Railroad and the canal embankment.

In final design, a gravity-supply site east of the Burlington Northern tracks will be investigated. Land is limited at that site and is privately held; however, the potential for gravity supply makes the site potentially desirable. This will require a detailed flood plain and floodway analysis during final design.


## FACILITY SIZE

As shown on Figure 6-1, the proposed facility will take up most of the remaining unused land in government ownership. This is approximately 4.0 acres. With the exception of a small meteorological station on the site, the land is currently vacant. In final design near by orchard land may be acquired to provide additional room for construction staging and room for disposal of canal sediments.

## PRODUCTION GOALS REVIEW

The **Wapato** satellite facility will be used for final rearing and acclimation of **coho** and fall chinook. The facility will be operated from March 1 through the end of May. **Coho smolt** releases are planned for 1.55 million fish at 15 fish per pound, and fall chinook releases are planned for 2.4 million fish at 65 fish per pound.

The **Wapato** satellite site will have three 45,000 cubic feet ponds for **coho** and 12 raceways for fall chinook.



CHM

NO.	DATE	REVISION	BY	APPROVED

**REUSE OF DOCUMENTS**  
 THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

YAKIMA RIVER BASIN  
 SALMON AND TROUT FACILITIES  
 PRELIMINARY DESIGN REPORT

**FIGURE 6-1**  
**WAPATO SATELLITE FACILITY**  
**SITE PLAN**

DESIGNER	
DATE	FEB 1990

PRELIMINARY

## CURRENT LAND USE AND OWNERSHIP

As mentioned earlier, the site of the proposed facility is currently vacant land adjacent to the new fish screens on the **Wapato** Canal. The site is on the **Yakima** Indian Nation reservation in unincorporated **Yakima** County. All proposed facility lands are currently owned by the government.

## SITE DEVELOPMENT

The following is a discussion of items of work required to improve the selected site for use as a fish culture station.

### ACCESS ROADS

Since the **Wapato** site is currently developed and actively maintained for the fish screen structure, no new access roads are required. Because of the expected increase in traffic from large fish transfer and fish food trucks, access arrangements need to be carefully reviewed with **WSDOT** and the affected railroads. To ensure that the ponds and raceways will drain completely dry to the canal they will be elevated on fill, resulting in the site roads, and parking areas being **2** to

3 feet higher than the existing roads. As shown in Figure **6-1**, these grade differences will be accommodated with ramps up to the rearing areas. All roads and parking areas will be gravel surfaced. Site plans will be coordinated with the **USBR** and **WIP** to ensure that there are no access problems with the joint use of the site.

#### DRAINAGE AND SNOW REMOVAL

Site grading will be designed to ensure adequate drainage. Drainage provisions at this site will be minimal. Snow removal will be required in some years to provide access to the site prior to the March 1 startup date. This snow removal will be by local contract forces. Adequate room for snow storage will be provided within the fenced area on the fill slopes.

#### **CONSTRUCTION** CLEARING AND GRUBBING

The **Wapato** site was previously used for constructing staging for the new fish screens on the **Wapato** Canal. As a result, minimal clearing and grubbing is anticipated.

## SITE WORK AND SLOPE **PROTECTION**

As much as **10,000** cubic yards of fill will be brought to the site in order to construct the ponds and raceways high enough to allow for gravity drainage to the **Wapato** Canal. This material will be imported from an **offsite** location, which will be at the contractor's option. The fill **slopes** at the site will be at a slope of **3:1** where possible, some low retaining wall may be required to maintain existing access. All disturbed areas and fill slopes will be **hydroseeded** after construction.

No flood protection is required for this site as currently proposed. If an alternate site on the river side of the Burlington Northern tracks is selected in final design, there will need to be substantial flood proofing. Cost of flood proofing for a gravity supply site will have to be compared with the cost of pumping at the primary site.

## **WETLANDS**

No wetlands have been identified at the site, and there is little opportunity for wetland enhancement.

## FLOOD ANALYSIS

The **Wapato** site was included in a June **1985** flood insurance study by **FEMA**. The site is shown as being in the **100-year** flood plain. A detailed flood study was not done by **FEMA** and as a result, no floodway was delineated. As part of the final design, a detailed flood plain and floodway analysis will be done to refine local flood elevations and evaluate the potential for reducing construction and operations cost by a gravity-supply system.

## POWER SUPPLY

Electrical power for the **Wapato** site will be provided by the Pacific Power and Light Company. They already serve the **Wapato** fish screen site with **12.5 kV**, 3 phase power. A diesel generator backup will be provided to serve two of the canal pumps if there is a power outage. The estimated electrical load at the **Wapato** site is shown in Table **6-1**.

---

Table **6-1**  
ESTIMATED **ELECTRICAL** LOADS

<u>Description</u>	<u>Quantity</u>	<u>Horsepower (ca)</u>	<u>KVA (total)</u>
Canal Pumps	4	75	300
Domestic Well	1	5	5
Hatchery Building	1	--	20
Site Lighting	1	--	1
			<b>326</b>

---

## WATER SUPPLY

As presented in Chapter 2, the **Wapato** site will need **60 cfs** pumped from the **Wapato** Canal. In addition, a domestic well will be required. This section presents the design concepts for the water supply system.

### CANAL WATER

A pump station will be constructed just downstream of the access ramp to the new fish screens on **Wapato** Canal. The site is on the right bank of the canal directly opposite the downstream end of the fish screen structure. The **WIP** has agreed to provide at least **500 cfs** of flow on March 1 of each year. This should provide sufficient depth of flow in the canal for the pump station to operate. In

final design, an evaluation of the tailwater conditions and the effectiveness of the new screens at that low flow will be evaluated. A check structure may be required in the canal to provide sufficient tailwater.

Return flow from the ponds and raceways will be discharged upstream of the existing fish screens which will result in some reuse of water. The reuse of less than **10** percent is not considered detrimental to the fish.

### **DOMESTIC SUPPLY**

A domestic water supply well will be constructed on the site. No preliminary investigations into that system have been done, but all homes nearby have wells, so it should not be a problem.

## **WATER TREATMENT**

Since the return flow enters the **Wapato** Canal, no special treatment of hatchery effluent is planned at the **Wapato** site. After the fish have left the station, the ponds and raceways will be drained to allow the accumulated material to dry out for mechanical removal.

## **SEWAGE TREATMENT**

Domestic sewage from the hatchery building will be treated **onsite** in a septic tank and drain field. Local health department requirements will guide the design of this system.

## **FACILITY BUILDINGS**

The following is a description of the buildings to be provided at the **Wapato** site.

### **HATCHERY BUILDING**

The **20-foot** by **20-foot** hatchery building will include the following rooms.

<u>Description</u>	<u>size (feet)</u>
office	<b>10</b> by <b>12</b>
Restroom	8 by <b>10</b>
Storage	<b>10</b> by <b>20</b>

This will be an energy-efficient frame constructed building with electric heat and no air conditioning. The hatchery building will have concrete floors.

## **FREEZER BUILDING**

The freezer building will be a prefabricated metal building similar to the **WDF** standard **Kittitas** freezer. The capacity of this **25-foot** by **60-foot** building will be **70,000** pounds.

## Chapter 7

### **PROSSER FACILITY DESIGN**

#### **GENERAL SITE DESCRIPTION**

The **Prosser** site is located between the Chandler Canal and the **Yakima** River just northeast of the town of **Prosser**. The site is at River Mile **46.3** on the **Yakima** River on government property adjacent to the recently constructed fish screens and juvenile trapping facility on the Chandler Canal.

#### ALTERNATIVE SITES

TWO alternative sites were considered prior to selecting the new juvenile trap site. The first was proposed for a flood plain area just downstream of the adult trapping facilities on the right bank of the river below the **Prosser** Dam. This site was rejected because it was subsequently developed as a city park, it had potential flood plain problems and it was reported to have archaeological significance to the **Yakima** Indian Nation. The second site was at the old juvenile trap just downstream of the selected site. It was determined that the selected site was


preferable because it consolidates fisheries-related activities in one secure location on existing government land.

## FACILITY SIZE

The proposed facilities will occupy approximately **4.5** acres of land. The site plan for the facility is presented in Figure 7-1. Part of the facility will be in the vacant land between the fish screens and the juvenile trapping building. The six concrete raceways will be located in the **100** year flood plain but outside the floodway on the low land adjacent to the access road for the juvenile trapping facility. This site for the raceways may need to be moved in final design to accommodate **USBR** plans for a new trash and ice **wasteway** or to avoid conflict with springs in the vicinity.

## **PRODUCTION GOALS** REVIEW

The **Prosser** satellite facility will be used for holding adult **coho** and fall chinook in the late summer and fall. These adults are to be trapped **0.9** mile away at **Prosser** Dam. In addition, the facility will be used for final rearing and acclimation of **1.2** million fall chinook in March, April, and May. The facility will have one **20,000-cubic-foot** pond for holding adult fall chinook and six **5,000-cubic-foot**



**INDEX OF DOCUMENTS**  
 THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

THIS IS ONE SIGN ON ORIGINAL SUBMITTAL. IF NOT ONE SIGN ON THIS SHEET, PLEASE REPORT APPROPRIATELY.

YAKIMA RIVER BASS SALMON AND BULLHEAD TOPIAS PRELIMINARY DESIGN REGION

**FIGURE 7-1 PROSSER SATELLITE FACILITY SITE PLAN**

NO.	DATE	REVISION	BY	APPROVED

SHEET	
DATE	FEB 2000
DESIGNED BY	
CHECKED BY	

PRELIMINARY

raceways for holding adult **coho** and for final rearing and acclimation of fall chinook.

## **CURRENT LAND USE AND OWNERSHIP**

As mentioned earlier, the site of the proposed facility is currently vacant land adjacent to existing fish screens and is in unincorporated **Benton** County. **All** lands required for the facility are currently owned by the government.

## **SITE DEVELOPMENT**

The following is a discussion of items of work required to improve the selected site for use as a fish culture station.

### **ACCESS ROADS**

Since this site is currently developed and actively maintained for the fish screen structure and juvenile trapping facility, no new access roads are required. The existing gravel surfaced access roads will be extended to the upper pond, the lower raceways, and the river pump station, as shown on Figure 7-1.

## **DRAINAGE AND SNOW REMOVAL**

Site grading will be designed to ensure adequate drainage. Drainage provisions at this site will be minimal. Some snow may accumulate in the latter part of the adult holding period (November and December). Snow may also still be on the site in mid-March during some years. Snow removal will be accomplished by local contract forces. Adequate room for snow storage will be provided within the fence at the pond and raceway sites.

## **CONSTRUCTION CLEARING AND GRUBBING**

The **Prosser** site will require very little clearing and grubbing. Some low brush at the site of the proposed raceways will be removed, but the few larger trees near the river will not be disturbed. The area around the pond and hatchery building was previously disturbed during the construction of the fish screens and juvenile trap.

## **SITE WORK AND SLOPE PROTECTION**

The adult holding pond will be located at a point which requires approximately 1,500 cubic yards of cut. The excess material from this cut will be used to fill the

existing depression north of the access road to the juvenile trapping facility. Some of this material may also be used around the raceways. Excess material which is not used in final structures will be disposed of onsite as is currently being done with excess material from the **Prosser** left bank ladder construction.

At this time, no special flood proofing is planned. The 50 year flood in the area may be as high as elevation 615.3 feet, which would encroach on the raceway fill slopes. This elevation and the final elevation of the raceway embankments will be verified during final design. Cut and fill slope area will be 3:1 and will be hydro-seeded after construction.

## **WETLANDS**

Although the pump station and raceways are in the 100 year flood plain and within 200 feet of the bank of the river, no wetlands have been identified and as such, no loss of wetlands is anticipated.

## **FLOOD ANALYSIS**

The **Prosser** site was studied by the **FEMA** as part of its **Benton County** flood insurance study. A detailed flood study, including a floodway determination, was completed in July 1982. This study will form the basis of the final design of the

site. The current plan is to have the raceways and their associated fill outside the flood way, but partially in the 100 year flood plain. This configuration should not encroach on the flood plain any more than the existing juvenile trapping facility and its access roads. The adult holding pond, hatchery building, and pump control building will be well above the 100 year flood level.

## **POWER SUPPLY**

Electrical power for the **Prosser** site will be provided by **Benton County PUD**. Their 12.5 kV, 3 phase power line already serves the needs of the fish screen and the juvenile trapping facility **onsite**. A diesel generator backup will be provided to serve power to one of the river pumps and the well pump, if there is a power outage. The estimated electrical load at the **Prosser** site is shown in Table 7-1.

---

**Table 7-1**  
**ESTIMATED ELECTRICAL LOADS**

<u>Description</u>	<u>Quantity</u>	<u>Horsepower (ea)</u>	<u>KVA ( total)</u>
River pumps	2	20	40
Well pump	2	10	20
Hatchery Building	1	--	20
Educator Pump	2	7.5	15
Spray pumps	4	10	40
Site Lighting	1	--	1
			<b>135</b>

---

## **WATER SUPPLY**

As presented in Chapter 2, the **Prosser** site will have the need for well water (1 cfs), river water (6 cfs), and canal water (14 cfs) at various times during the year. This section presents the design concepts for each water source.

### **WELL WATER**

The **USBR** water supply report has complete details on the well field. The plan is to pump 1 cfs from the well(s) during the late summer and early fall, when adults are being held. The anticipated 58°F water will be used to temper the warmer canal water.

The well water will be pumped to a **degassification** tower and will then be delivered to the adult holding pond where it will be mixed with either canal water or river water, depending on the time of year.

## **RIVER WATER**

Six cfs will be pumped directly from the **Yakima** River during the late fall period when the Chandler Canal is shut down for maintenance. Two 20-horsepower line-shaft pumps will be used to produce a total flow of 6 cfs. Since it is unlikely that a large flood would occur at the site in late fall, the pump station will only be protected up to the 10 year flood level. Pumps and intake screens would be removed during the nonpumping season. Since the river is very shallow at the site of the pump station, minor dredging of sediment may be required each fall to put the pump station in service.

## **CANAL WATER**

A gravity diversion from the Chandler Canal will be the primary water source for the **Prosser** site. Up to 14 cfs will be diverted from the canal. Two alternative intake points are shown on Figure 7-1. The exact point of diversion will be resolved in final design after discussion with the **USBR** on the impact of the proposed intake site. The coordination with the **USBR** also will include discussions on their proposed new ice/trash **wasteway** for the trash rack structure on the Chandler Canal. For rearing of fall chinook, canal water will be settled first in the large adult holding pond.

## MISCELLANEOUS WATER SUPPLY

Although it was originally planned to provide incubation at **Prosser** through the eyed egg stage for **coho** and fall chinook, it is recommended that the eggs be shipped green to Nelson Springs and Oak Flats for incubation. As a result, there will be no incubation at **Prosser**. Since only green eggs are programmed to leave the station, so no tanker fill system will be provided. The **6-inch** observation well used during the groundwater investigation will be used for domestic water supply. Fire protection will be provided by a fire alarm system and chemical fire extinguishers. No water-based fire fighting system is planned.

## WATER TREATMENT

Water used at the **Prosser** facility will become contaminated with byproducts of fish culture. These include fish waste, unused food, disease-control chemicals, and river sediment settled out in rearing vessels. The following is a discussion of proposed facilities to deal with water treatment.

## **HATCHERY EFFLUENT**

Water which has passed through adult holding and rearing vessels will be discharged directly to the **Yakima** River by way of the existing fish bypass piping. If in final design it is determined that this pipe cannot be used, a similar structure will be constructed. Adult holding of fall chinook at the same station as that is used for final acclimation, always presents the risk of false attraction of returning adults. This factor will have to be examined in the final design.

## **CLEANING WASTE**

A vacuum cleaning waste system in keeping with current **WDF** design practice will be installed for the six raceways. The proposed system includes a large earthen drying bed to receive the cleaning waste. Adult fish held on station may be treated with formalin; however, at this time there is no plan for specific treatment of water during these operations.

## **SEWAGE TREATMENT**

Domestic sewage from the hatchery building will be treated **onsite** in a septic tank and drainfield. A sewage lift station may be required to deliver flow to the **drain-**field if it is located at a higher elevation than the hatchery building. Local health

department requirements will guide the design. Direct discharge of domestic sewage to the near by sewage treatment plan will also be investigated during final design.

## HATCHERY BUILDING

The hatchery building will be a 20-foot by 40-foot frame building and will include the following rooms:

<u>Description</u>	<u>Size (feet)</u>
Office	10 by 12
Restroom	8 by 10
Storage	10 by 20
Pump Controls and Mechanical	10 by 10
Lunch/Bunk Room	10 by 20
Freezer	10 by 10

This will be an energy-efficient building with electric heat and air conditioning.

The building will have concrete floors.

## Chapter 8

### ACCLIMATION SITES

The acclimation sites for spring chinook and for summer steelhead are very important to the concept of supplementation. Acclimation sites will be provided to allow different experimental groups of fish to imprint and thus return to different areas on the main stem of the upper **Yakima** River and other tributaries throughout the basin.

#### UPPER YAKIMA SPRING CHINOOK

The plan developed by **EDWG** for siting the 15 acclimation ponds required for Upper **Yakima** spring chinook involves putting three ponds in clusters at five areas in the upper basin. Each pond in a cluster would be within a mile or so of each other. The location of these sites can be seen in Figure 2-1. The clusters on the **Teanaway** River and **Yakima** River above **Lake Easton** are referred to as tributary clusters. The three clusters at **Easton**, **Cle Elum**, and **Thorp** are considered main stem clusters. Management and operations of these sites will be coordinated by the hatchery manager at the **Cle Elum** central hatchery. Food will be distributed on a daily basis by hatchery staff in hatchery pickup trucks. Peak

food consumption at each pond is approximately one **50-pound** bag per day. **Two** feedings per day are planned.

### **NACHES SPRING CHINOOK**

The plan for acclimation of the **Naches** spring chinook was also developed by **EDWG** and includes three clusters of two ponds each to accommodate the six experimental groups. As shown in Figure 2-1, there is one cluster on the Little **Naches** River, one cluster on the Bumping River, and one cluster on Rattlesnake Creek. The Rattlesnake Creek sites have single acclimation ponds. The Little **Naches** and Bumping sites are proposed to have two ponds per site. One pond for the spring chinook and one pond for steelhead.

As with the Upper **Yakima** acclimation sites the **Naches** spring chinook acclimation sites will be managed by the manager of the nearby central hatchery at Oak Flats. Staff from Oak Flats will feed the fish and maintain the acclimation sites.

### **SUMMER STEELHEAD**

The plan developed by **EDWG** for summer steelhead includes six clusters of two ponds each on tributaries of the **Naches** and Lower **Yakima** Rivers (see Figure 2-1). As mentioned earlier, the Little **Naches** and Bumping River steel-

head sites will be dual pond sites with chinook in one pond and steelhead in the other. The steelhead acclimation will be managed and serviced by the Oak Flats central hatchery, however, it may be more practical to manage the **Toppenish** Creek sites from the **Wapato** satellite site.

## **ACCLIMATION SITE DESIGN**

The acclimation sites described above and their associated design criteria were developed by a joint reconnaissance effort by members of **EDWG** and Mr. **Senn** of **FMC**. Design concepts come from recent work completed by Mr. **Senn** and Mr. **Mack** of **FMC** for very similar acclimation sites for the **Nez Perce** tribe.



A standardized acclimation pond was designed to accommodate the various experimental groups in the program. The groups are made up of either **33,000** summer steelhead at 7 per pound or **75,000** spring chinook at 15 per pound. A density factor of **1.1**, which is one-half of that used in the raceways, resulted in the required pond volume of **9,000** cubic feet. Using an average depth of 5 feet and the current **WDF** recommended top width to length ratio, the **9,000** cubic feet pond has a top width of **33** feet and a length of **87.8** feet from the **8-inch** inlet riser to the outlet screens. The earthen ponds will be lined with river rock to help simulate natural rearing conditions. Simple culvert riser drain structures will be used to minimize cost. The flow rate pond will be **1.2 cfs** or

9.28 pounds per gpm for the 5,000 pounds of fish. The outlet will be designed for volitional release with provisions for a counter.

Figure 8-1 shows a typical site plan for an acclimation site. This figure shows general design considerations modeled after the FMC experience with the Nez Perce project. The preferred alternative at any site is a gravity supply of surface water. This is shown on the left side of the figure as being positioned adjacent to a hypothetical existing bridge. This approach would work well on streams with gradients steeper than 50 feet per mile.

On flatter gradient streams such as the Yakima River pump stations will be required. Pump stations allow for shorter transmission piping but of course require electrical power and diesel generator backups.

The pond(s) must be positioned such that they are outside of the floodway and high enough to drain by gravity. Depending on the site, one or two ponds will be constructed. Security fencing, alarm systems, and predator protection devices are not shown on the figure but are required at all sites. There are no current plans for a buildings at the acclimation sites.



DESIGN					
DR					
CHK					
NO.	DATE	REVISION	BY	APVD	

**ABUSE OF DOCUMENTS**  
 THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

YAKIMA RIVER BASIN  
 SALMON AND STEELHEAD FACILITIES  
 PRELIMINARY DESIGN REPORT

**FIGURE 8-1**  
 TYPICAL ACCLIMATION POND  
 SITE PLAN

SHEET	
NO.	
DATE	FEB 1990
PROJ	WAS/RS/AD
NO.	

PRELIMINARY

## Chapter 9

### ADULT AND JUVENILE TRAPPING FACILITIES

Adult and juvenile trapping facilities are required for the **Yakima** Basin program. **EDWG** in coordination with the passage Workgroup has identified the sites which will be initially required to collect adult brood stock and to evaluate **smolt** out migration. The passage work group has started to draft a plan for preliminary design of the required facilities. In developing this plan design concepts have been identified for both new sites and modifications to existing facilities.

At **Prosser** minor modifications to the existing adult trap and the addition of a short term holding tank is planned. No modifications are currently planned for the juvenile trap at **Prosser**. At the **Cowiche** Dam an adult trap has to be added to the existing left bank **fishway**. In addition, a **10 cfs** gravity intake to supply the Nelson Springs central hatchery will be included. A new juvenile trap will be required at the new diversion dam at Oak Flats. At **Raza** Dam a new adult trap will be added to the existing left bank ladder and the existing juvenile will be modified.

A more complete description of the proposed adult and juvenile trapping facilities including **EDWG's** fish collection design criteria **will** be the first product of the upcoming **pre-design** by the passage Workgroup.

## Chapter 10

### SCHEDULE AND COST

#### SCHEDULE

Construction of the **Yakima** River Basin facilities is planned to occur over a five year period from **1992** through **1996**. The schedule for individual facilities is shown in Figure 10-1. This schedule is designed to meet the program goals for fish culture as well as to phase in construction to meet funding limitations. The schedule for construction is driven by the goal of taking adult brood stock. Upper **Yakima** spring chinook will be taken in **1993**. **Naches** spring and summer chinook and coho will be taken in **1944** although the coho brood stock may initially need to come from outside the basin. Fall chinook and **Naches** summer steelhead will be taken in **1995**.



## COSTS

### CAPITAL COST

An estimate of the capital cost of each of the **Yakima** Basin facilities has been made. Due to the varying level of site specific data and engineering design three sources of estimates were used. For the three central hatcheries and the two satellite facilities most of the costs were based on the recently constructed **Chelan** County **PUD** Rock Island central hatchery and satellite sites. For the acclimation sites the estimate was based on recent experience with similar facilities on the **Nez Perce** acclimation site at Meadow Creek. this estimate was prepared by Mr. John **Mack** of **FMC**. The estimate for the adult and juvenile trapping facilities was prepared by the **USBR** passage group based on previous projects and knowledge of the proposed sites. All of the capital cost estimates presented in this report are based on similar facilities, either constructed or planned for other basins.

The estimates represent the best judgement of the respective estimators as to the bids which would be received in January 1990 for the facilities as currently designed for construction in 1990. No escalation to or during construction or construction financing cost is included. Local sales taxes are also excluded since

they will not likely be required. These estimates have been prepared for guidance in project evaluation and implementation from the information available at the time of the estimate. The final costs of the project will depend on actual labor and material costs, actual site conditions, productivity, competitive market conditions, final project scope, final project schedule, and other variable factors. As a result, the final product costs will vary from the estimates presented herein. Because of these factors, funding needs must be carefully reviewed prior to establishing final project budgets.

Table 10-1 shows a summary of the estimated construction costs for the various **Yakima** River Basin facilities. An estimated 25% for engineering, legal, and administrative cost is also included in Table 10-1. Also shown in Table 10-1, is the **BPA** Realty-Acquisition Section estimate that the cost to acquire the sites for the three central hatcheries and the two satellite sites are **\$500,000**. No land acquisition cost is available for the acclimation sites or the adult and juvenile trapping facilities.

Tables 10-2 through 10-6 show a more detailed breakdown of estimated costs for the three central hatcheries and the two satellite sites.

---

**Table 10-1**  
**YAKIMA RIVER BASIN**  
**SALMON AND STEELHEAD FACILITIES**  
**CAPITAL COST SUMMARY**  
**(JANUARY 1990 \$)**

Central Hatcheries	
<b>Cle Elum</b>	<b>\$5,160,000</b>
Oak Flats	6,216,000
Nelson Springs	2,647,000
Satellite Facilities	
<b>Wapato</b>	<b>2,154,000</b>
<b>Prosser</b>	<b>1,390,000</b>
Acclimation Sites	
Spring Chinook (17 sites)	3,060,000
Steelhead (8 sites)	1,440,000
Chinook/Steelhead (4 sites)	1,000,000
Adult Trapping Facilities	
<b>Raza</b>	<b>875,000</b>
<b>Cowiche</b>	<b>625,000</b>
<b>Prosser</b>	<b>80,000</b>
Juvenile Trapping Facilities	
Oak Flats	390,000
<b>Raza</b>	<b>110,000</b>
<b>Prosser</b>	<b>-0-</b>
	Subtotal
	<b>25,147,000</b>
Engineering Legal and Administrative Costs (25%)	6,287,000
Land Acquisition Costs	500,000
	Total
	<b><u>\$31,934,000</u></b>

---

Table 10-2 through 10-6 show a more detailed breakdown of estimated costs for the three central hatcheries and the two satellite sites.

Table 10-2 **Cle Elum** Central Hatchery Cost Estimate 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Site Development</b>				
General Requirements	1	LS	\$339,800.00	\$339,800
Clearing & Grubbing	5	AC	\$2,288.00	\$10,982
Access Roadway	11,400	LF	\$10.01	\$114,114
Misc Surfaced* Areas	9,680	SY	\$2.97	\$28,792
Drainage & Culverts	1	LS	\$3,000.00	\$3,000
Site Grading	5	AC	\$1,258.40	\$6,040
Fencing	1,450	LF	\$13.73	\$19,906
Subtotal				\$522,635
<b>Water Supply System</b>				
Water Supply Well	4	EA	\$50,000.00	\$200,000
River Pump Station:				
Care And Diversion Of Water	1	LS	\$80,000.00	\$80,000
Civil Works	1	LS	\$145,000.00	\$145,000
Electrical/Mechanical	1	LS	\$225,000.00	\$225,000
Pumps	3	EA	\$18,000.00	\$54,000
Diesel Generator	1	LS	\$32,000.00	\$32,000
Lake Pump Station:				
Cut-Off Trench	1	LS	\$150,000.00	\$150,000
Care And Diversion Of Water	1	LS	\$20,000.00	\$20,000
Civil Works	1	LS	\$80,000.00	\$80,000
Electrical/Mechanical	1	LS	\$225,000.00	\$225,000
Pumps	4	EA	\$13,000.00	\$52,000
Site Piping:				
Discharge 30"	480	LF	\$123.55	\$59,305
Drain 36"	640	LF	\$83.51	\$53,448
well 12"	1200	LF	\$68.64	\$82,368
Minor Piping (>12")	0.9	AC	\$19,136.83	\$17,223
Degasification Tower	1	LS	\$85,800.00	\$85,800
Modify Outfall Structure	1	LS	\$40,000.00	\$40,000
Subtotal				\$1,601,144
<b>Fish Production Facilities</b>				
Raceway	16	EA	\$51,000.00	\$816,000
Adult Raceway	2	EA	\$90,000.00	\$180,000
Subtotal				\$996,000

Table 10-2 (cont'd) Cle Elum Central Hatchery Cost Est. 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Buildings</b>				
Hatchery Building	2,400	SF	\$110.00	\$264,000
Incubation Building:	2,700	SF	\$85.00	\$229,500
Troughs	20	EA	\$2,667.00	\$53,340
Pole Barn	1,920	SF	\$15.00	\$28,800
Electrical Control Building	1,500	SF	\$50.00	\$75,000
Residences	3	EA	\$120,000.00	\$360,000
Freezer Building	1	LS	\$180,000.00	\$180,000
Covered Parking	1500	SF	\$5.00	\$7,500
Subtotal				\$1,198,140
<b>Waste Treatment</b>				
Septic Tank/Drain Field	1	LS	\$40,000.00	\$40,000
Cleaning Waste Pond	1	LS	\$125,000.00	\$125,000
Subtotal				\$165,000
<b>Electrical System</b>				
Standby Generator	1	EA	\$60,000.00	\$60,000
Site Electrical	1	LS	\$120,000.00	\$120,000
Electrical Service				
Main	1	LS	\$20,000.00	\$20,000
River Pump Station	1	LS	\$55,000.00	\$55,000
Instrumentation and Controls	1	LS	\$120,000.00	\$120,000
Subtotal				\$375,000
<b>Hatchery Equipment</b>				
General Equipment	1	LS	\$100,000.00	\$100,000
3/4 Ton 4x4 Pickup	1	EA	\$18,000.00	\$18,000
Snow Plow Attachment	1	EA	\$1,500.00	\$1,500
1/2 Ton 4x4 Pickup	2	EA	\$12,000.00	\$24,000
Fork Lift	1	EA	\$25,000.00	\$25,000
2000 Gal Tanker	1	EA	\$120,000.00	\$120,000
300 Gal Trailer	1	EA	\$15,000.00	\$15,000
Subtotal				\$303,500

Estimated Construction Cost (Cle Elum) = \$5,161,418

Table 10-3 Oak Flats Central Hatchery Cost Estimate 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Site Development</b>				
General Requirements	1	LS	\$297,600.00	\$297,600
Clearing & Grubbing	5	AC	\$1,000.00	\$4,800
Access Roadway	630	LF	\$10.01	\$6,306
Misc Surfaced Areas	17,000	SF	\$2.97	\$50,565
Drainage & Culverts	1	LS	\$2,500.00	\$2,500
Site Grading	5	AC	\$1,258.40	\$6,292
Fencing	2,430	LF	\$13.73	\$33,359
Subtotal				\$401,422
<b>Water Supply System</b>				
Water Supply Wells	4	EA	\$45,000.00	\$180,000
Diversion Dam	1	LS	\$500,000.00	\$500,000
River Pump Station:				
Civil Works	1	LS	\$140,000.00	\$140,000
Electrical/Mechanical	1	LS	\$120,000.00	\$120,000
Pumps	4	EA	\$19,000.00	\$76,000
Share Of Fish Screens	1	LS	\$68,000.00	\$68,000
Infiltration System				
Infiltration Drain (18")	600	LF	\$35.00	\$21,000
Transmission Pipe (30")	150	LF	\$125.00	\$18,750
Mechanical	1	LS	\$28,000.00	\$28,000
Site Piping:				
Process Water 42"	530	LF	\$167.02	\$88,523
Process Water 30"	310	LF	\$123.55	\$38,301
Drain Water 48"	900	LF	\$98.38	\$88,546
Drain 36"	260	LF	\$83.51	\$21,713
Well 6"	4000	LF	\$45.76	\$183,040
Minor Piping (<12")	1.6	AC	\$19,136.83	\$30,619
Degasification Tower	1	Is	\$24,000.00	\$24,000
Subtotal				\$1,626,491
<b>Fish Production Facilities</b>				
Raceways	21	EA	\$51,000.00	\$1,071,000
Adult Raceways	1	EA	\$90,000.00	\$90,000
Rearing Ponds	4	EA	\$50,000.00	\$200,000
Adult Ponds	1	EA	\$90,000.00	\$90,000
Subtotal				\$1,451,000

Table 10-3(cont'd) Oak Flats Central Hatchery Cost Est. 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Buildings</b>				
Hatchery Building	2,400	SF	\$110.00	\$264,000
Incubation Building:	2,700	SF	\$85.00	\$229,500
Troughs	20	EA	\$2,667.00	\$53,340
Pole Barn	1,920	SF	\$15.00	\$28,800
Electrical Control Building	1,500	SF	\$50.00	\$75,000
Residences	4	EA	\$120,000.00	\$480,000
Freezer Building	1	LS	\$180,000.00	\$180,000
Covered Parking	1500	SF	\$5.00	\$7,500
Research Center	6000	SF	\$80.00	\$480,000
Subtotal				\$1,798,140
<b>Waste Treatment</b>				
Septic Tank/Drain Field	1	LS	\$40,000.00	\$40,000
Cleaning Waste Pond	1	LS	\$125,000.00	\$125,000
Subtotal				\$165,000
<b>Electrical System</b>				
Standby Generator	1	EA	\$60,000.00	\$60,000
Site Electrical	1	LS	\$210,000.00	\$210,000
Electrical Service	1	LS	\$40,000.00	\$40,000
Instrumentation and Control	1	LS	\$120,000.00	\$120,000
Subtotal				\$430,000
<b>Hatchery Equipment</b>				
General Equipment	1	LS	\$120,000.00	\$120,000
3/4 Ton 4x4 Pickup	1	EA	\$18,000.00	\$18,000
Snow Plow Attachment	1	EA	\$1,500.00	\$1,500
1/2 Ton 4x4 Pickup	3	EA	\$12,000.00	\$36,000
Pathologist Car	1	EA	\$10,000.00	\$10,000
Fork Lift	1	EA	\$25,000.00	\$25,000
2000 Gal Tanker	1	EA	\$120,000.00	\$120,000
300 Gal Trailer	1	EA	\$15,000.00	\$15,000
Subtotal				\$345,500

Estimated Construction Cost (Oak Flats) = \$6,217,554

Fable 10-4 Nelson Springs Central Hatchery Cost Estimate 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Site Development</b>				
General Requirements	1	LS	\$175,000.00	\$175,000
Clearing & Grubbing	2	AC	\$1,000.00	\$1,600
Access Roadway (Paved)	800	LF	\$16.00	\$12,800
Misc Surfaced Areas	5,808	SF	\$3.00	\$17,424
Drainage & Culverts	1	LS	\$3,800.00	\$3,800
Site Grading	2	AC	\$1,300.00	\$2,080
New Creek Culverts	1	LS	\$22,000.00	\$22,000
Fencing	1,800	LF	\$13.73	\$24,710
Fill/Demo Exist Pond	1	LS	\$6,000.00	\$6,000
Subtotal				\$265,414
<b>Water Supply System</b>				
Water Supply Well	2	EA	\$45,000.00	\$90,000
Domestic Well	1	EA	\$5,000.00	\$5,000
Nelson Springs Intake	1	LS	\$15,000.00	\$15,000
Buckskin Creek Intake	1	LS	\$15,000.00	\$15,000
Drain Outfall and Weirs	1	LS	\$56,000.00	\$56,000
Pump Building				
Care And Diversion Of Water	1	LS	\$10,000.00	\$10,000
Civil Works	1	LS	\$40,000.00	\$40,000
Pumps	3	Ea	\$11,000.00	\$33,000
Electrical: Mechanical	1	LS	\$180,000.00	\$180,000
Site Piping:				
Suction RCP 18"	90	LF	\$54.91	\$4,942
Coviche RCP 24"	1550	LF	\$65.21	\$101,072
Added Cost To Cross Highway	1	LS	\$50,000.00	\$50,000
Coviche Intake	1	LS	\$30,000.00	\$30,000
Discharge 20" CCP	230	LF	\$101.82	\$23,418
Discharge 6" CCP	390	LF	\$45.76	\$17,846
Drain 30"	160	LF	\$74.36	\$11,898
Minor Piping (<12")	0.4	AC	\$19,136.83	\$7,655
Degasification Tower	1	LS	\$22,000.00	\$22,000
Subtotal				\$712,831

Table 10-4(cont'd) Nelson Springs Central Hatchery Cost Est. 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Fish Production Facilities</b>				
Raceway	6	EA	\$51,000.00	\$306,000
Adult Raceway	1	EA	\$90,000.00	\$90,000
Subtotal				\$396,000
<b>Buildings</b>				
Hatchery Building & Visitor Bu	1,600	SF	\$110.00	\$176,000
Incubation Building:	3,600	SF	\$85.00	\$306,000
Troughs	34	EA	\$2,667.00	\$90,678
Pole Barn	1,920	SF	\$15.00	\$28,800
Electrical Control Building	1,500	SF	\$50.00	\$75,000
New Residence	1	EA	\$120,000.00	\$120,000
Pump Building	800	SF	\$50.00	\$40,000
Subtotal				\$836,478
<b>Waste Treatment</b>				
Septic Tank/Drain Field		LS	\$12,000.00	\$12,000
Cleaning Waste Pond	1	LS	\$62,000.00	\$62,000
Subtotal				\$74,000
<b>Electrical System</b>				
Standby Generator		EA	\$40,000.00	\$40,000
Electrical		LS	\$120,000.00	\$120,000
Electrical Service		LS	\$40,000.00	\$40,000
Instrumentation and Control		LS	\$60,000.00	\$60,000
Subtotal				\$260,000
<b>General Equipment</b>				
General Equipment		LS	\$70,000.00	\$70,000
3/4 Ton 4x4 Pickup		EA	\$18,000.00	\$18,000
Special Plov Attachment		EA	\$1,500.00	\$1,500
Small Loader		EA	\$15,000.00	\$15,000
Subtotal				\$104,500

Estimated Construction Cost (Nelson Springs) = \$2,649,223

Table 10-5 Wapato Satellite Facility Cost Estimate

13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Site Development</b>				
General Requirements	1	LS	\$143,249.13	\$143,249
Clearing & Grubbing	2	AC	\$1,000.00	\$2,100
Railroad Crossing	1	LS	\$100,000.00	\$100,000
Misc Surfaced Areas	6,800	SY	\$2.97	\$20,226
Drainage & Culverts	1	LS	\$800.00	\$800
Site Grading	2	AC	\$1,258.40	\$2,643
Fencing	1,320	LF	\$13.73	\$18,121
Subtotal				\$287,139
<b>Water Supply System</b>				
Domestic Well	1	EA	\$5,000.00	\$5,000
Pump Station:				
Care And Diversion Of Water	1	LS	\$10,000.00	\$10,000
Civil Works	1	LS	\$190,000.00	\$190,000
Pumps	4	EA	\$30,500.00	\$122,000
Electrical/Mechanical	1	LS	\$198,000.00	\$198,000
Site Piping:				
Process Water 42"	170	LF	\$167.02	\$28,394
Process Water 30"	180	LF	\$123.55	\$22,239
Drain 48"	165	LF	\$98.38	\$16,233
Drain 42"	195	LF	\$91.52	\$17,846
Minor Piping (<12")	0.7	AC	\$19,136.83	\$13,396
Subtotal				\$623,109
<b>Fish Production Facilities</b>				
Raceway	6	EA	\$51,000.00	\$306,000
Coho Ponds	3	EA	\$162,000.00	\$486,000
Subtotal				\$792,000

Table 10-5 (cont'd) Wapato Satellite Facility Cost Est. 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Buildings</b>				
Hatchery Building	400	SF	\$50.00	\$20,000
Freezer Building	1	LS	\$180,000.00	\$180,000
R&R Weather Sta.	1	LS	\$2,000.00	\$2,000
Subtotal				\$202,000
<b>Waste Treatment</b>				
Septic Tank: Drain Field	1	LS	\$6,000.00	\$6,000
Subtotal				\$6,000
<b>Electrical System</b>				
Standby Generator (200 KW)	1	EA	\$75,000.00	\$75,000
Site Electrical	1	LS	\$40,000.00	\$40,000
Electrical Service	1	EA	\$12,000.00	\$12,000
Instrumentation & Control	1	LS	\$45,000.00	\$45,000
Subtotal				\$172,000
<b>Hatchery Equipment</b>				
General Equipment	1	LS	\$30,000.00	\$30,000
3/4 Ton 4x4 Pickup	1	LS	\$18,000.00	\$18,000
Snow Plow Attachment	1	LS	\$1,500.00	\$1,500
Fork Lift	1	LS	\$25,000.00	\$25,000
Subtotal				\$74,500
Estimated Construction Cost (Wapato)=				\$2,156,748

Table 10-6 Prosser Satellite Facility Cost Estimate 13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Site Development</b>				
General Requirements	1	LS	\$93,300.00	\$93,300
Clearing & Grubbing	1	AC	\$1,000.00	\$1,250
Access Roadway	270	LF	\$10.01	\$2,703
Misc Surfaced Areas	4,452	SF	\$2.97	\$13,242
Drainage & Culverts	1	LS	\$800.00	\$800
Site Grading	1	AC	\$1,258.40	\$1,573
Fencing	930	LF	\$13.73	\$12,767
Subtotal				\$125,635
<b>Water Supply System</b>				
Water Supply Well	2	EA	\$45,000.00	\$90,000
Domestic Well	1	LS	\$5,000.00	\$5,000
Canal Intake	1	EA	\$12,000.00	\$12,000
Pump Station:			?	
Care And Diversion Of Water	1		\$20,000.00	\$20,000
Civil/Mechanical	1		\$106,000.00	\$106,000
Pumps	2		\$12,000.00	\$24,000
Compressor	1		\$6,000.00	\$6,000
Diesel Generator ?	0		\$0.00	so
Site Piping:				
Process Water 16"	570	LF	\$82.37	\$46,950
Process Water 24"	1090	LF	\$114.40	\$124,696
Process Water 6"	340	LF	\$45.76	\$15,558
Drain 30"	290	LF	\$74.36	\$21,564
Drain 16"	310	LF	\$51.48	\$15,959
Minor Piping (<12")	0.33	AC	\$19,136.83	\$6,315
Manholes 4' Dia 8'H	2	EA	\$2,478.00	\$4,956
Connect to Exist Pipe	1	EA	\$2,000.00	\$2,000
Degasification Tower	1	LS	\$18,000.00	\$18,000
Subtotal				\$518,999
<b>Fish Production Facilities</b>				
Raceways	3	EA	\$51,000.00	\$153,000
Adult Raceways	3	EA	\$90,000.00	\$270,000
20,000 CF Pond	1	EA	\$90,000.00	\$90,000
Subtotal				\$513,000

Fable 10-6(cont'd)    **Prosser** Satellite Facility Cost Est.    13-Feb-90

Description	Quantity	Unit	Unit Cost	Total
<b>Buildings</b>				
Hatchery Building	800	SF	\$65.00	\$52,000
Subtotal				\$52,000
<b>Waste Treatment</b>				
Septic Tank/Drain Field	1	LS	\$6,000.00	\$6,000
Cleaning Waste Pond	1	LS	\$12,000.00	\$12,000
Subtotal				\$18,000
<b>Electrical System</b>				
Standby Generator	1	LS	\$40,000.00	\$40,000
Site Electrical	1	LS	\$40,000.00	\$40,000
Electrical Service	1	LS	\$10,000.00	\$10,000
Instrumentation & Controls	1	LS	\$45,000.00	\$45,000
Subtotal				\$135,000
<b>Hatchery Equipment</b>				
General Equipment	1	LS	\$30,000.00	\$30,000
Subtotal				\$30,000
Estimated Construction Cost ( <b>Prosser</b> )=				\$1,392,633

## **OPERATIONS AND MAINTENANCE COSTS**

An O&M estimate for the **Yakima** River Basin facilities was prepared by Mr. **Senn** of **FMC**. The estimate, in January 1990 dollars, was based on the food, staffing and transportation estimates provided in Chapter 2.

The annual food cost was estimated to be \$226,000 based on 46¢/lb for **OMP#2** and an annual consumption of 578,000 lbs. Transportation costs were estimated at \$35,000 per year based on 24¢ per mile for cars, 40¢ per mile for pickups, and \$1.00 per mile for tanker trucks. This includes \$1500 per year per diem. Labor costs are based on the average of current **WDF** pay scales for the various positions itemized in Table 2-10. The total estimated labor budget is \$410,000 per year. This estimate does not include staff for operations of the traps staff for fish marking. No cost for **general** management or payroll administration are included. A power cost was prepared based on comparisons with similar facilities. The estimated annual power cost is \$165,000. With a 5 percent allowance for the annual cost for miscellaneous supplies, this brings the total annual O&M estimate to \$920,000.

**APPENDIX A**

**FLOW , SPACE, FOOD  
SUMMARY**

**F O R YAKIMA B A S I N H A T C H E R I E S**

**Wapato  
Prosser  
Cle Elum  
Oak Flat  
Nelson Springs**

**By Fish Management Consultants  
Olympia, WA**

**December 1989**

**F L O W , S P A C E I F O O D**

**S U M M A R Y**

**For  
WAPATO**

**By Fish Management Consultants  
Olympia, WA**

**February 2, 1990**

WAPATO - FALL CHINOOK

Growth - Food

RUN NAME: HYWP1A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	% MORT.	AVE. TEMP. (F)	STU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY %	
										FEED REQ. (LBS.)	FOOD FED /DAY
43	03/19/91	1,225,353				57.7	288.1	4,253			
57	04/02/91	1,215,860	0.74	45.0	29.0	63.0	221.9	5,478	1.13	1,390	2.2
71	04/16/91	1,209,404	0.50	47.0	29.0	69.0	168.5	7,176	1.16	1,962	2.4
85	04/30/91	1,205,014	0.34	50.0	29.0	76.3	124.8	9,653	1.18	2,915	2.7
99	05/14/91	1,202,029	0.23	52.0	29.0	84.3	92.3	13,019	1.20	4,035	2.8
113	05/28/91	1,200,000	0.16	57.0	29.0	94.4	65.8	14,239	1.22	6,368	3.2

BIOMASS PRODUCED (LBS.) = 13,985

TOTAL FOOD FED (LBS.) = 16,670

AVERAGE CONVERSION = 1.19

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 5,850 GPM (13 cfs)

RACEWAY SPACE = 30,000 CU.FT.

HYWPIAR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----				
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	FLOW	ACTUAL	ACTUAL	ALLOW-	TOTAL	
ENDING	ENDING	BIOMASS	WATER	LBS./	LBS./	REQ'D	RACEWAY	LBS./	LBS./	CU.FT.	
DAY	DATE	(LBS.)	USED	GPM	GPM	(GPM)	USED	CU.FT.	CU.FT.	REQ'D	
1	03/19/91	4,253	3,150	1.35	7.68	553	30,000	0.14	0.43	9,806	
15	04/02/91	7,178	3,150	1.74	7.68	713	30,000	0.18	0.43	12,630	
29	04/16/91	7,176	3,150	2.28	6.37	1,127	30,000	0.24	0.48	15,094	
43	04/30/91	9,653	3,150	3.06	5.06	1,907	30,000	0.32	0.53	18,370	
57	05/14/91	13,019	3,150	4.13	4.49	2,901	30,000	0.43	0.58	22,406	
71	05/28/91	16,239	5,850	3.12	3.12	5,837	30,000	0.61	0.65	28,037	

WAPATO - COHO

Growth - Food

RUN NAME: HYWP3A

PERIOD ENDING DAY	PERIOD ENDING DATE	SC. FISH	MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	% FOOD FED /DAY
365	02/28/92	1,558,006				119.8	25.5	61,089			
379	03/13/92	1,556,432	0.08	43.0	44.0	122.7	23.7	65,606	2.01	9,064	1.0
393	03/27/92	1,554,858	0.08	45.0	44.0	126.2	21.8	71,234	2.05	11,510	1.2
407	04/10/92	1,553,284	0.08	47.0	44.0	130.2	19.9	78,124	2.08	14,358	1.4
421	04/24/92	1,551,710	0.08	50.0	44.0	135.0	17.8	86,973	2.12	18,782	1.7
435	05/08/92	1,550,137	0.08	52.0	44.0	140.3	15.9	97,564	2.16	22,891	1.8
449	05/22/92	1,548,563	0.08	53.0	44.0	145.9	14.1	109,572	2.20	26,417	1.9

BIOMASS PRODUCED (LBS.) = 48,483

TOTAL FOOD FED (LBS.) = 103,022 AVERAGE CONVERSION = 2.12

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 17,550 GPM (39 cfs)

POND SPACE = 135,000 CU.FT.

HYWP3AR		-----WATER FLOW REQMT'S-----					-----POND REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	ACTUAL	ACTUAL	ALLOW-	TOTAL	
ENDING	ENDING	BIOMASS	WATER	LBS./	ABLE	FLOW	POND	LBS./	ABLE	REQ'D
DAY	DATE	(LBS.)	USED	GPM	GPM	(GPM) U	SPACE	CU.FT.	CU.FT.	REQ'D
15	02/23/92	65,606	17,550	3.74	17.68	3,456	135,000	0.49	0.68	90,310
29	03/27/92	71,234	17,550	4.06	13.69	5,204	135,000	0.53	0.70	102,424
43	04/10/92	79,124	17,550	4.45	10.81	7,229	135,000	0.58	0.72	108,890
57	04/24/92	86,973	17,550	4.96	8.14	10,687	135,000	0.64	0.74	116,925
71	05/08/92	97,564	17,550	5.56	6.79	14,367	135,000	0.72	0.77	126,191
85	05/22/92	109,572	17,550	6.24	6.39	17,147	135,000	0.81	0.80	136,298

FOOD REQUIREMENTS A T WAPATO

HYWP1AF

PERIOD ENDING DATE	*****LBS. FOOD REQUIRE;; BY SPECIES *****		TOTAL LBS. FOOD REQUIRED
	FALL CHINOOK	COHO	
01/29/91			
02/28/91			
03/30/91	1,390	20,574	21,964
04/30/91	4,877	33,140	38,018
05/30/91	10,403	49,308	59,710
06/30/91			
07/30/91			
08/29/91			
09/29/91			
10/29/91			
11/29/91			
12/29/91			
01/29/92			

**WATER FLOW REQUIREMENTS  
AT WAPATO**

HYWPIAZ

PERIOD ENDING DAY	PERIOD ENDING DATE	----- ACTUAL -----		-- MIN. REQ'D --	
		GPM WATER	CFS WATER	GPM WATER	CFS WATER
1	01/01/91				
15	01/15/91				
29	01/29/91				
43	02/12/91				
57	02/26/91	17,550	39.0	3,456	7.7
71	03/12/91	17,550	39.0	3,711	8.2
85	03/26/91	20,700	46.0	5,757	12.8
99	04/09/91	20,700	46.0	7,942	17.6
113	04/23/91	20,700	46.0	11,814	26.3
127	05/07/91	20,700	46.0	16,274	36.2
141	05/21/91	20,700	46.0	20,048	44.6
155	06/04/91	5,850	13.0	5,837	13.0
169	06/18/91				
183	07/02/91				
197	07/16/91				
211	07/30/91				
225	08/13/91				
239	08/27/91				
253	09/10/91				
267	09/24/91				
281	10/08/91				
295	10/22/91				
309	11/05/91				
323	11/19/91				
337	12/03/91				
351	12/17/91				
365	12/31/91				
379	01/14/92				
393	01/28/92				

**WAPATO**

**Pollutants**

Estimated PPM of Pollutants Generated Daily for  
all Species Programed at Wapato

HYWPIAP

PERIOD ENDING DAY	PERIOD ENDING DATE	FOOD FED ALL SPECIES (LBS.)	GPM WATER ACTUAL	POLLUTANTS GENERATED IN PPM **						RECEIVING WATER B.C.D. (C'S)
				TOTAL AMMONIA	NH3	NITRATE	PHOSPHATE	SETTLABLE; SOLIDS		
1	02/26/91		17,550							
15	03/12/91	647	17,550	0.10	0.0001	0.27	0.02	0.92	1.04	
19	03/26/91	822	20,700	0.11	0.0002	0.29	0.02	0.99	1.12	
43	04/09/91	1,125	20,700	0.15	0.0002	0.39	0.02	1.36	1.54	
57	04/23/91	1,482	20,700	0.19	0.0003	0.52	0.03	1.79	2.03	
71	05/07/91	1,843	20,700	0.24	0.0003	0.65	0.04	2.23	2.52	
85	05/21/91	2,175	20,700	0.28	0.0004	0.76	0.04	2.63	2.97	
99	06/04/91	455	5,850	0.21	0.0003	0.56	0.03	1.94	2.20	

\*\* The ppm of pollutants in the discharge water is illustrated in the table. Vacuum cleaning will significantly reduce the level of settleable solids and B.O.D.

**FLOW, SPACE, FOOD**

**S U M M A R Y**

**For**

**PROSSER**

**By Fish Management Consultants  
Olympia, WA**

**December 1989**

**PROSSER - FALL CHINOOK**

**Growth - Food**

RUN NAME: HYPRI1A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO.	% FISH MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	% FOOD FED /DAY
43	03/19/91	1,225,353				57.7	288.1	4,253			
57	04/02/91	1,215,860	0.74	50.0	34.0	63.9	212.2	5,730	1.13	1,675	2.6
71	04/16/91	1,209,404	0.50	52.0	34.0	70.8	156.1	7,746	1.16	2,330	2.7
85	04/30/91	1,205,014	0.34	55.0	34.0	78.7	113.6	10,606	1.18	3,367	2.9
99	05/14/91	1,202,029	0.23	57.0	34.0	87.3	83.2	14,441	1.20	4,597	2.9
113	05/28/91	1,200,000	0.16	59.0	34.0	96.6	61.5	19,526	1.22	6,203	2.8

BIOMASS PRODUCED (LBS.) = 15,273

TOTAL FOOD FED (LBS.) = 18,172      AVERAGE CONVERSION = 1.19

**PROSSER - FALL CHINOOK**

**Flow - Space**

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 6,300 GPM (14 cfs)

RACEWAY SPACE = 30,000 CU.FT.

HYPRIRAR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----				
PERIOD	PERIOD	TOTAL	ACTUAL	ALLOW-		ACTUAL	ALLOW-	TOTAL			
ENDING	ENDING	BIOMASS	WATER	ABLE	FLOW	RACEWAY	ABLE	CU.FT.	CU.FT.	REQ'D	
DAY	DATE	LBS./	USED	LBS./	(GPM)	USED	CU.FT.	CU.FT.	REQ'D		
			GPM	GPM							
1	03/19/91	4,253	6,300	0.68	5.22	814	30,000	0.14	0.44	9,660	
15	04/02/91	5,730	6,300	0.91	5.22	1,097	30,000	0.19	0.44	13,014	
29	04/16/91	7,746	6,300	1.23	4.62	1,678	30,000	0.26	0.49	15,882	
43	04/30/91	10,606	6,300	1.68	3.91	2,710	30,000	0.35	0.54	19,560	
57	05/14/91	14,441	6,300	2.29	3.50	4,127	30,000	0.48	0.60	24,010	
71	05/28/91	19,526	6,300	3.10	3.10	6,296	30,000	0.65	0.67	29,341	

FOOD REQUIREMENTS AT PROSSER

HYPR1AF

PERIOD ENDING DATE	***** LBS . FOOD REQUIRED BY SPECIES ***** FALL CHINOOK	TOTAL LBS . FOOD REQUIRED
01/29/91		
02/28/91		
03/30/91	1,675	1,675
04/30/91	10,294	10,294
05/30/91	6,203	6,203
06/30/91		
07/30/91		
08/29/91		
09/29/91		
10/29/91		
11/29/91		
12/29/91		
01/29/92		

WATER FLOW REQUIREMENTS  
AT PROSSER

HYPR1AZ

PERIOD ENDING DAY	PERIOD ENDING DATE	----- ACTUAL -----		-- MIN. REQ'D --	
		GPM WATER	CFS WATER	GPM WATER	CFS WATER
1	01/01/91				
15	01/15/91				
29	01/29/91				
43	02/12/91				
57	02/26/91				
71	03/12/91				
85	03/26/91	6,300	14.0	814	1.8
99	04/09/91	6,300	14.0	1,097	2.4
113	04/23/91	6,300	14.0	1,678	3.7
127	05/07/91	6,300	14.0	2,710	6.0
141	05/21/91	6,300	14.0	4,127	9.2
155	06/04/91	6,300	14.0	6,296	14.0
169	06/18/91				
183	07/02/91				
197	07/16/91				
211	07/30/91				
225	08/13/91				
239	08/27/91				
253	09/10/91	2,250	5.0	2,250	5.0
267	09/24/91	2,250	5.0	2,250	5.0
281	10/08/91	2,250	5.0	2,250	5.0
295	10/22/91	2,250	5.0	2,250	5.0
309	11/05/91	3,150	7.0	3,150	7.0
323	11/19/91	2,700	6.0	2,700	6.0
337	12/03/91	2,700	6.0	2,700	6.0
351	12/17/91	2,700	6.0	2,700	6.0
365	12/31/91				
379	01/14/92				
393	01/28/92				

**PROSSER**

**Pollutants**

Estimated **PPM** of Pollutants Generated Daily for  
all Species Programed at **Prosser**

**HYPRIAP**

PERIOD ENDING DAY	PERIOD ENDING DATE	FOOD FED ALL SPECIES (LBS.)	GPM WATER ACTUAL	POLLUTANTS GENERATED IN PPM**					RECEIVING WATER (CFS)
				TOTAL AMMONIA	NH3	NITRATE	PHOSPHATE	SETTLED SOLIDS	
1	03/19/91		6,300						
15	04/02/91	120	6,300	0.05	0.0001	0.14	0.01	0.47	0.54
29	04/16/91	166	6,300	0.07	0.0001	0.19	0.01	0.66	0.75
43	04/30/91	240	6,300	0.10	0.0001	0.28	0.02	0.95	1.08
57	05/14/91	328	6,300	0.14	0.0002	0.38	0.02	1.30	1.47
71	05/28/91	443	6,300	0.19	0.0003	0.51	0.03	1.76	1.99

\*\* The ppm of pollutants in the discharge water is illustrated in the table. Vacuum cleaning will significantly reduce the level of settleable solids and B.O.D.

**F L O W , S P A C E , F O O D**

**S U M M A R Y**

**For**  
**CLE ELUM**

**By Fish Management Consultants**  
**Olympia, WA**

**December 1989**

CLE ELUM

UPPER YAKIMA SPRING CHINOOK

Growth - Food

RUN NAME: MYCE3A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	% MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	% FOOD FED /DAY
1	02/28/91	1,586,164				34.1	1,400.0	1,133			
15	03/14/91	1,463,493	7.73	47.0	37.0	38.8	947.0	1,545	1.00	412	2.4
29	03/28/91	1,379,542	5.29	43.0	37.0	42.3	732.1	1,884	1.03	350	1.5
43	04/11/91	1,322,990	3.57	44.0	37.0	46.1	565.8	2,338	1.07	484	1.7
57	04/25/91	1,284,534	2.42	46.0	37.0	50.5	429.7	2,989	1.10	716	2.1
71	05/09/91	1,258,385	1.65	50.0	37.0	56.2	311.9	4,034	1.13	1,184	2.6
85	05/23/91	1,240,603	1.12	53.0	37.0	62.8	223.2	5,559	1.17	1,780	2.9
99	06/06/91	1,228,511	0.76	53.0	37.0	69.5	165.1	7,441	1.20	2,258	2.7
113	06/20/91	1,220,289	0.52	53.0	37.0	76.1	125.6	9,719	1.23	2,809	2.5
127	07/04/91	1,214,632	0.36	53.0	37.0	82.8	97.7	12,432	1.27	3,437	2.4
141	07/18/91	1,210,127	0.28	53.0	37.0	89.4	77.5	15,612	1.30	4,134	2.2
155	08/01/91	1,205,820	0.27	53.0	37.0	96.0	62.5	19,286	1.33	4,899	2.1
169	08/15/91	1,201,630	0.26	53.0	37.0	102.7	51.2	23,487	1.37	5,741	2.0
183	08/29/91	1,197,563	0.26	53.0	37.0	109.3	42.4	28,248	1.40	6,665	1.9
197	09/12/91	1,193,617	0.25	53.0	37.0	116.0	35.5	33,603	1.43	7,675	1.9
211	09/26/91	1,189,802	0.24	52.0	37.0	122.3	30.3	39,279	1.47	8,325	1.7
225	10/10/91	1,186,123	0.23	47.0	37.0	127.0	27.0	43,892	1.50	6,920	1.2
239	10/24/91	1,182,580	0.22	44.0	37.0	130.8	24.7	47,800	1.53	5,993	1.0
253	11/07/91	1,179,173	0.21	42.0	37.0	134.0	23.0	51,202	1.57	5,330	0.8
267	11/21/91	1,175,902	0.21	40.0	37.0	136.5	21.8	54,007	1.60	4,487	0.6
281	12/05/91	1,172,767	0.20	37.0	37.0	138.1	21.0	55,756	1.63	2,857	0.4
295	12/19/91	1,169,768	0.19	36.0	37.0	139.3	20.5	57,155	1.67	2,332	0.3
309	01/02/92	1,166,905	0.18	33.0	37.0	139.7	20.3	57,404	1.70	1,607	0.2
323	01/16/92	1,164,179	0.17	34.0	37.0	140.3	20.1	58,052	1.73	1,625	0.2
337	01/30/92	1,161,588	0.16	35.0	37.0	141.2	19.7	59,105	1.77	1,861	0.2
351	02/13/92	1,159,134	0.15	36.0	37.0	142.5	19.1	60,579	1.80	2,652	0.3
365	02/27/92	1,156,815	0.15	38.0	37.0	144.4	18.4	62,904	1.83	4,263	0.5
379	03/12/92	1,154,565	0.14	40.0	37.0	146.9	17.5	66,138	1.87	6,038	0.7
393	03/26/92	1,152,314	0.14	43.0	37.0	150.4	16.3	70,808	1.90	8,872	0.9
407	04/09/92	1,150,064	0.14	44.0	37.0	154.2	15.1	76,153	1.93	10,334	1.0

BIOMASS PRODUCED (LBS.) = 76,153  
 TOTAL FOOD FED (LBS.) = 116,042      AVERAGE CONVERSION = 1.55

NOTE: average temperature is programed for 53 F during first week after ponding

CLE ELUM - UPPER YAKIMA SPRING CHINOOK

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS (INCL. PREVIOUS AND NEXT BROODS):

WELL WATER = 5,400 GPM (12 cfs; used from June 1st through September 1st)  
 RIVER WATER = 7,200 GPM (1bcfs; used from September 1st through June 1st)  
 RACEWAY SPACE = 75,000 CU.FT.

HYCE3AR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ALLOW-		ACTUAL	ALLOW-			
ENDING	ENDING	BIOMASS	WATER	ACTUAL	ABLE	FLOW	RACEWAY	ACTUAL	ABLE	TOTAL
DAY	DATE	(LBS.)	FLOW	LBS./	LBS./	REQ'D	SPACE	LBS./	LBS./	CU.FT.
			USED	CPM	GPM	(GPM)	USED	CU.FT.	CU.FT.	REQ'D
1	02/28/91	1,133	450	2.52	6.34	179	10,000	0.11	0.27	4,237
15	03/14/91	1,545	450	3.43	6.34	244	10,000	0.15	0.27	5,779
29	03/28/91	1,884	450	4.19	11.96	158	10,000	0.19	0.29	6,467
43	04/11/91	2,338	450	5.20	10.13	231	10,000	0.23	0.32	7,364
57	04/25/91	2,989	450	6.64	7.79	384	45,000	0.07	0.35	8,590
71	05/09/91	4,034	1,350	2.99	5.20	776	45,000	0.09	0.39	10,418
85	05/23/91	5,559	1,350	4.12	4.14	1,343	45,000	0.12	0.43	12,840
99	06/06/91	7,441	2,700	2.76	4.46	1,668	45,000	0.17	0.48	15,544
113	06/20/91	9,719	2,700	3.60	4.77	2,039	45,000	0.22	0.52	18,531
127	07/04/91	12,432	4,950	2.51	5.06	2,456	45,000	0.28	0.57	21,803
141	07/18/91	15,612	4,950	3.15	5.36	2,915	45,000	0.35	0.62	25,347
155	08/01/91	19,286	4,950	3.90	5.65	3,412	45,000	0.43	0.66	29,148
169	08/15/91	23,487	4,950	4.74	5.94	3,957	45,000	0.52	0.71	33,201
183	08/29/91	28,248	5,400	5.23	6.21	4,552	45,000	0.63	0.75	37,506
197	09/12/91	33,603	5,400	6.22	6.46	5,199	45,000	0.75	0.80	42,061
211	09/26/91	39,279	5,400	7.27	7.29	5,387	75,000	0.52	0.84	46,624
225	10/10/91	43,892	7,200	6.10	12.42	3,533	75,000	0.59	0.88	50,155
239	10/24/91	47,800	7,200	6.64	18.44	2,592	75,000	0.64	0.90	53,036
253	11/07/91	51,202	7,200	7.11	24.62	2,132	75,000	0.68	0.92	55,471
267	11/21/91	54,007	7,200	7.50	31.73	1,702	75,000	0.72	0.94	57,425
281	12/05/91	55,756	7,200	7.74	53.36	1,045	75,000	0.74	0.95	58,606
295	12/19/91	57,155	7,200	7.94	67.35	849	75,000	0.76	0.96	59,532
309	01/02/92	57,404	7,200	7.97	99.67	576	75,000	0.77	0.96	59,656
323	01/16/92	58,052	7,200	8.06	99.16	585	75,000	0.77	0.97	60,057
337	01/30/92	59,105	7,200	8.21	87.3	674	75,000	0.79	0.97	60,736
351	02/13/92	60,579	7,200	8.41	62.3	965	75,000	0.81	0.98	61,698
365	02/27/92	62,904	7,200	8.74	40.7	1,566	75,000	0.84	0.99	63,224
379	03/12/92	66,138	7,200	9.19	28.55	2,284	75,000	0.88	1.01	65,331
393	03/26/92	70,808	7,200	9.83	19.14	3,625	75,000	0.94	1.04	68,326

CLE ELUM - NACHES SPRING CHINOOK

Growth - Food

RUN NAME: HYCE4A

PERIOD ENDING DAY	PERIOD ENDING DATE	NC.	% FISH MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB	BIOMASS (LBS.)	CONV RATE	14 DAY FEED REQ. (LBS.)	% FOOD FED /DAY
1	02/28/91	523,077				34.1	1,400.0	445			
15	03/14/91	574,139	7.95	45.5	37.0	38.3	982.6	584	1.00	139	2.1
29	03/28/91	540,649	5.37	43.0	37.0	41.8	757.3	714	1.04	134	1.6
43	04/11/91	518,088	3.62	44.0	37.0	45.6	563.6	888	1.07	167	1.8
57	04/25/91	502,747	2.46	46.0	37.0	50.0	442.0	1370	1.11	277	2.1
71	05/09/91	492,315	1.67	50.0	37.0	55.7	320.0	1,539	1.15	461	2.7
85	05/23/91	485,221	1.14	53.0	37.0	62.4	128.3	2,125	1.19	696	3.0
99	06/06/91	480,398	0.77	53.0	37.0	69.0	168.5	2,851	1.22	886	3.6
113	06/20/91	477,117	0.53	53.0	37.0	75.6	127.9	3,257	1.26	1,107	2.5
127	07/04/91	474,861	0.36	53.0	37.0	82.3	99.4	4,771	1.30	1,455	2.4
141	07/18/91	473,063	0.29	52.0	37.0	88.9	78.8	6,007	1.33	1,639	2.3
155	08/01/91	471,345	0.26	53.0	37.0	95.6	63.5	7,428	1.37	1,948	2.2
169	08/15/91	469,674	0.17	53.0	37.0	102.2	51.9	9,054	1.41	2,288	2.1
183	08/29/91	468,051	0.16	53.0	37.0	108.8	43.0	10,997	1.44	2,563	2.0
197	09/12/91	466,477	0.25	53.0	37.0	115.5	36.0	12,972	1.46	2,870	1.9
211	09/26/91	464,955	0.24	52.0	37.0	121.8	30.6	15,740	1.50	3,341	1.6

BIOMASS PRODUCED (LBS.) = 15,172  
 TOTAL FOOD FED (LBS.) = 20,197 AVERAGE CONVERSION = 1.37

NOTE: average temperature is programmed for 53 F during first week after ponding

CLE ELUM - NACHES SPRING CHINOOK

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

YELL WATER = 1,800GPM (4 cfs; used from June 1st through September 1st)  
 RIVER WATER = 2,250 GPM (5 cfs; used from September 1st through June 1st)  
 RACEWAY SPACE = 20,000 CU.FT.

HYCE4AR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	ACTUAL	ACTUAL	ALLOW-	TOTAL	
ENDING	ENDING	BIOMASS	WATER	LBS./	LBS./	FLOW	RACEWAY	LBS./	LBS./	
DAY	DATE	(LBS.)	FLOW	GPM	GPM	REQ'D	SPACE	CU.FT.	CU.FT.	
			USED			(GPM)	USED		REQ'D	
1	02/28/91	445	225	1.98	8.06	55	5,000	0.09	0.26	1,685
15	03/14/91	584	225	2.60	8.06	72	5,000	0.12	0.26	2,212
29	03/28/91	714	225	3.17	11.79	61	5,000	0.14	0.29	2,478
43	04/11/91	888	225	3.95	9.96	89	5,000	0.18	0.31	2,825
57	04/25/91	1,137	225	5.05	7.64	149	5,000	0.23	0.34	3,299
71	05/09/91	1,539	225	6.84	5.08	303	5,000	0.31	0.38	4,007
85	05/23/91	2,126	450	4.72	4.04	526	20,000	0.11	0.43	4,947
99	06/06/91	2,851	900	3.17	4.35	656	20,000	0.14	0.48	5,996
113	06/20/91	3,729	900	4.14	4.64	804	20,000	0.19	0.52	7,155
127	07/04/91	4,777	900	5.31	4.92	972	20,000	0.24	0.57	8,427
141	07/18/91	6,007	1,800	3.34	5.19	1,157	20,000	0.30	0.61	9,804
155	08/01/91	7,428	1,800	4.13	5.47	1,358	20,000	0.37	0.66	11,281
169	08/15/91	9,054	1,800	5.03	5.74	1,578	20,000	0.45	0.70	12,857
183	08/29/91	10,897	1,800	6.05	5.99	1,820	20,000	0.54	0.75	14,532
197	09/12/91	12,972	2,250	5.77	6.23	2,083	20,000	0.65	0.80	16,304
211	09/26/91	15,172	2,250	6.74	7.02	2,163	20,000	0.76	0.84	18,079

FOOD REQUIREMENTS AT CLE ELUM

HYCE1AF

PERIOD ENDING DATE	***** LBS. YAKIMA SP. CHINOOK	FOOD REWIRED BY SPECIES NACHES SP. CHINOOK	*****	TOTAL LBS. FOOD REWIRED
01/29/91	6,139			6,139
02/28/91	10,713	139		10,852
03/30/91	20,041	321		20,362
04/30/91	1,900	738		2,638
05/30/91	4,037	1,582		5,619
06/30/91	6,246	2,465		8,711
07/30/91	9,033	3,587		12,620
08/29/91	20,081	8,025		28,106
09/29/91	15,245	3,341		18,586
10/29/91	11,323			11,323
11/29/91	7,344			7,344
12/29/91	3,940			3,940
01/29/92	6,139			6,139

WATER FLOW REQUIREMENTS  
AT CLE ELUM

HYCE1AZ

PERIOD ENDING DAY	PERIOD ENDING DATE	----- ACTUAL -----		-- MIN. REQ'D --	
		GPM WATER	CFS WATER	GPM WATER	CFS WATER
1	02/28/91	7,875	17.5	1,800	4.0
15	03/14/91	7,875	17.5	2,600	5.8
29	03/28/91	7,875	17.5	3,844	8.5
43	04/11/91	675	1.5	320	0.7
57	04/25/91	675	1.5	533	1.2
71	05/09/91	1,575	3.5	1,079	2.4
85	05/23/91	1,800	4.0	1,869	4.2
99	06/06/91	3,600	8.0	2,324	5.2
113	06/20/91	3,600	8.0	2,843	6.3
127	07/04/91	5,850	13.0	3,428	7.6
141	07/18/91	6,750	15.0	4,072	9.0
155	08/01/91	6,750	15.0	4,770	10.6
169	08/15/91	6,750	15.0	5,535	12.3
183	08/29/91	7,200	16.0	6,372	14.2
197	09/12/91	7,650	17.0	7,282	16.2
211	09/26/91	7,650	17.0	7,550	16.8
225	10/10/91	7,200	16.0	3,533	7.9
239	10/24/91	7,200	16.0	2,592	5.8
253	11/07/91	7,200	16.0	2,132	4.7
267	11/21/91	7,200	16.0	1,702	3.8
281	12/05/91	7,200	16.0	1,045	2.3
295	12/19/91	7,200	16.0	849	1.9
309	01/02/92	7,200	16.0	576	1.3
323	01/16/92	7,200	16.0	585	1.3
337	01/30/92	7,200	16.0	674	1.5
351	02/13/92	7,200	16.0	965	2.1
365	02/27/92	7,875	17.5	1,800	4.0
379	03/12/92	7,875	17.5	2,600	5.8

50/50  
RIVER &  
WELL

**CLE ELUM**

**Pollutants**

Estimated **PPM** of Pollutants Generated Daily for all Species **Programmed** at **Cle Elum** Facility

**HYCEIAP**

PERIOD ENDING DAY	PERIOD ENDING DATE	FOOD		POLLUTANTS GENERATED IN PPM **						RECEIVING WATER (CFS)
		FED ALL SPECIES (LBS.)	GPM WATER ACTUAL	TOTAL AMMONIA	MH3	NITRATE	PHOSPHATE	SETTLED SOLIDS	B.O.D.	
1	02/28/91	304	7,875	0.10	0.0002	0.28	0.02	0.97	1.09	
15	03/14/91	471	7,875	0.16	0.0002	0.43	0.02	1.49	1.69	
29	03/28/91	668	7,875	0.23	0.0003	0.62	0.04	2.12	2.40	
43	04/11/91	786	675	3.11	0.0046	8.44	0.49	29.11	32.96	
57	04/25/91	71	675	0.28	0.0004	0.76	0.04	2.63	2.98	
71	05/09/91	117	1,575	0.20	0.0003	0.54	0.03	1.86	2.11	
85	05/23/91	177	1,800	0.26	0.0004	0.71	0.04	2.46	2.78	
99	06/06/91	225	3,600	0.17	0.0002	0.45	0.03	1.56	1.77	
113	06/20/91	280	3,600	0.21	0.0003	0.56	0.03	1.94	2.20	
127	07/04/91	343	5,850	0.16	0.0002	0.42	0.02	1.46	1.66	
141	07/18/91	412	6,750	0.16	0.0002	0.44	0.03	1.53	1.73	
155	08/01/91	489	6,750	0.19	0.0003	0.53	0.03	1.81	2.05	
169	08/15/91	574	6,750	0.23	0.0003	0.62	0.04	2.12	2.40	
183	08/29/91	666	7,200	0.25	0.0004	0.67	0.04	2.31	2.62	
197	09/12/91	768	7,650	0.27	0.0004	0.73	0.04	2.51	2.84	
211	09/26/91	833	7,650	0.29	0.0004	0.79	0.05	2.72	3.08	
225	10/10/91	494	7,200	0.18	0.0003	0.50	0.03	1.72	1.94	
239	10/24/91	428	7,200	0.16	0.0002	0.43	0.02	1.49	1.68	
253	11/07/91	381	7,200	0.14	0.0002	0.38	0.02	1.32	1.50	
267	11/21/91	321	7,200	0.12	0.0002	0.32	0.02	1.11	1.26	
281	12/05/91	204	7,200	0.08	0.0001	0.21	0.01	0.71	0.80	
295	12/19/91	167	7,200	0.06	0.0001	0.17	0.01	0.58	0.65	
309	01/02/92	115	7,200	0.04	0.0001	0.12	0.01	0.40	0.45	
323	01/16/92	116	7,200	0.04	0.0001	0.12	0.01	0.40	0.46	
337	01/30/92	133	7,200	0.05	0.0001	0.13	0.01	0.46	0.52	
351	02/13/92	189	7,200	0.07	0.0001	0.19	0.01	0.66	0.74	
365	02/27/92	304	7,875	0.10	0.0002	0.28	0.02	0.97	1.09	
379	03/12/92	471	7,875	0.16	0.0002	0.43	0.02	1.49	1.69	

\*\* The ppm of pollutants in the discharge water is illustrated in the table. Vacuum cleaning will significantly reduce the level of settleable solids and B.O.D.

**F L O W I S P A C E . F O O D**

**SUMMARY**

**For**

**OAK FLAT**

**By Fish Management Consultants  
Olympia, WA**

**December 1989**

OAK FLAT - NACHES SPRING CHINOOK

Growth - Food

RUN NAME: HYOF4A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO.	% FISH MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS)	% FOOD FED /DAY
211	09/26/91	465,771				121.8	30.6	15,197			
225	10/10/91	464,311	0.23	52.0	33.0	128.9	25.9	17,952	1.54	4,230	1.9
239	10/24/91	462,905	0.23	47.0	33.0	134.2	22.3	20,205	1.57	3,541	1.4
253	11/07/91	461,553	0.22	40.0	33.0	137.0	21.5	21,450	1.61	2,001	0.7
267	11/21/91	460,254	0.21	35.0	33.0	138.1	21.0	21,891	1.64	725	0.2
281	12/05/91	459,010	0.20	35.0	33.0	139.2	20.5	22,340	1.68	754	0.2
295	12/19/91	457,820	0.19	32.5	33.0	139.3	20.5	22,368	1.71	626	0.2
309	01/02/92	456,684	0.18	34.0	33.0	140.1	20.2	22,655	1.75	634	0.2
323	01/16/92	455,602	0.17	34.0	33.0	140.8	19.9	22,946	1.79	642	0.2
337	01/30/92	454,574	0.16	34.0	33.0	141.5	19.6	23,242	1.82	651	0.2
351	02/13/92	453,600	0.16	34.0	33.0	142.2	19.3	23,542	1.86	659	0.2
365	02/27/92	452,679	0.15	36.0	33.0	143.6	18.7	24,204	1.89	1,253	0.4
379	03/12/92	451,786	0.14	40.0	33.0	146.4	17.6	25,616	1.93	2,723	0.8
393	03/26/92	450,893	0.14	42.0	33.0	150.0	16.4	27,467	1.96	3,636	1.0
407	04/09/92	450,000	0.14	44.0	33.0	154.2	15.1	29,812	2.00	4,690	1.2

BIOMASS PRODUCED (LBS.) = 14,615

TOTAL FOOD FED (LBS.) = 26,766

AVERAGE CONVERSION = 1.83

OAK FLAT - NACHES SPRING CHINOOK

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 4,050 GPM (9 cfs)

RACEWAY SPACE = 30,000 CU.FT.

HYOF4AR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	FLOW	ACTUAL	ALLOW-	TOTAL	
ENDING	ENDING	BIOMASS	WATER	LBS./	LBS./	REQ'D	RACEWAY	LBS./	CU.FT.	
DAY	DATE	(LBS.)	USED	GPM	GPM	(GPM)	USED	CU.FT.	REQ'D	
1	09/26/91	15,197	3,150	4.82	6.51	2,335	30,000	0.51	0.89	17,113
15	10/10/91	17,952	3,150	5.70	6.51	2,759	30,000	0.60	0.89	20,215
29	10/24/91	20,205	3,150	6.41	11.12	1,817	30,000	0.67	0.92	21,851
43	11/07/91	21,450	3,600	5.96	28.13	763	30,000	0.71	0.94	22,718
57	11/21/91	21,891	3,600	6.08	83.23	263	30,000	0.73	0.95	23,007
71	12/05/91	22,340	3,600	6.21	81.74	273	30,000	0.74	0.96	23,299
85	12/19/91	22,368	3,600	6.21	99.91	224	30,000	0.75	0.96	23,298
99	01/02/92	22,655	3,600	6.29	99.05	229	30,000	0.76	0.96	23,478
113	01/16/92	22,946	3,600	6.37	99.05	232	30,000	0.76	0.97	23,660
127	01/30/92	23,242	3,600	6.46	99.04	235	30,000	0.77	0.97	23,845
141	02/13/92	23,542	3,600	6.54	99.04	238	30,000	0.78	0.98	24,033
155	02/27/92	24,204	3,600	6.72	52.96	457	30,000	0.81	0.99	24,465
169	03/12/92	25,616	4,050	6.32	24.74	1,035	30,000	0.85	1.01	25,390
183	03/26/92	27,467	4,050	6.78	18.87	1,456	30,000	0.92	1.03	26,582
197	04/09/92	29,812	4,050	7.36	14.73	2,023	30,000	0.99	1.06	28,055

OAK FLAT - NACHES SUMMER CHINOOK

Growth - Food

RUN NAME: HYOF5A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	% CR.	AVE. TEMP (°F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV RATE	14 DAY FEED REQ. (LBS.)	% FOOD /DAY
	03/01/91	276,923				34.1	1,400.0	198			
15	03/15/91	255,396	7.77	45.5	36.0	38.5	973.5	262	1.00	65	2.1
29	03/29/91	240,664	5.32	42.0	36.0	41.7	763.3	315	1.03	55	1.4
43	04/12/91	230,740	3.58	44.0	36.0	45.6	583.8	395	1.07	85	1.8
57	04/26/91	223,992	2.44	45.0	36.0	49.8	447.5	500	1.10	116	2.0
71	05/10/91	219,403	1.66	47.0	36.0	54.7	338.3	649	1.14	169	2.1
85	05/24/91	216,283	1.13	47.0	36.0	60.6	249.4	867	1.17	256	2.1
99	06/07/91	214,361	0.77	47.0	36.0	67.4	181.1	1,153	1.21	381	2.4
113	06/21/91	212,719	0.50	47.0	36.0	74.2	135.6	1,569	1.24	480	2.7
127	07/05/91	211,716	0.36	47.0	36.0	81.0	104.1	2,134	1.26	593	7.1
141	07/19/91	210,935	0.29	53.0	36.0	87.8	81.7	2,582	1.31	719	2.4
155	08/02/91	210,179	0.27	53.0	36.0	94.7	65.3	3,220	1.34	858	2.1
169	08/16/91	209,444	0.27	53.0	36.0	101.5	53.0	3,954	1.38	1,012	2.1
183	08/30/91	208,730	0.26	53.0	36.0	108.3	43.6	4,790	1.41	1,162	2.0
197	09/13/91	208,039	0.25	53.0	36.0	114.8	36.6	5,686	1.45	1,298	1.9
211	09/27/91	207,364	0.24	53.0	36.0	121.3	31.0	6,686	1.48	1,432	1.9
225	10/11/91	206,701	0.23	53.0	36.0	127.8	26.5	7,794	1.52	1,682	1.7
239	10/25/91	206,101	0.21	47.0	36.0	132.7	23.7	8,694	1.55	1,896	1.1
253	11/08/91	205,503	0.22	49.0	36.0	139.2	22.4	9,188	1.59	2,084	0.8
267	11/22/91	204,929	0.21	35.0	36.0	136.3	21.9	9,362	1.62	292	0.2
281	12/06/91	204,379	0.20	35.0	36.0	137.2	21.4	9,539	1.66	292	0.2
295	12/20/91	203,853	0.19	32.5	36.0	137.4	21.4	9,548	1.69	267	0.2
309	01/03/92	203,350	0.18	34.0	36.0	138.0	21.1	9,660	1.72	270	0.2
323	01/17/92	202,872	0.17	34.0	36.0	138.7	20.8	9,774	1.76	274	0.2
337	01/31/92	202,417	0.16	34.0	36.0	139.3	20.5	9,890	1.79	277	0.2
351	02/14/92	201,986	0.16	34.0	36.0	140.0	20.2	10,008	1.83	280	0.2
365	02/28/92	201,580	0.15	36.0	36.0	141.3	19.6	10,268	1.86	485	0.2
379	03/13/92	201,185	0.14	40.0	36.0	143.9	18.6	10,824	1.90	1,054	0.2
393	03/27/92	200,790	0.14	42.0	36.0	147.1	17.4	11,552	1.93	1,404	3.9
407	04/10/92	200,395	0.14	44.0	36.0	151.0	16.1	12,470	1.97	1,805	1.1
421	04/24/92	200,000	0.14	45.0	26.0	155.3	14.8	13,519	2.00	2,098	1.2

BIOMASS PRODUCED (LBS) = 13,519  
 TOTAL FOOD FED (LBS.) = 21,402 AVERAGE CONVERSION = 1.61

NOTE: average temperature is programmed for 53 F during first week after ponding

OAK FLAT - NACHES SUMMER CHINOOK

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS ( INCL. PREVIOUS AND NEXT BROODS ):

WELL WATER = 900 GPM ( 2 cfs; used from June 1st through September 2nd )

RIVER WATER = 1,800GPM ( 4 cfs; used from September 2nd through June 1st )

RACEWAY SPACE = 15,000 CU.FT. ( MAX. )

HYOF5AR		WATERFLOWREQMT'S-----					RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	ACTUAL	ACTUAL	ACTUAL	ALLOW-	TOTAL
ENDING	ENDING	BIOMASS	WATER	LBS./	LBS./	FLOW	RACEWAY	LBS./	LBS./	CU.FT.
DAY	DATE	(LBS.)	USED	GPM	GPM	(GPM)	SPACE	CU.FT.	CU.FT.	REQ'D
1	03/01/91	198	900	0.22	7.75	26	15,000	0.01	0.26	746
15	03/15/91	262	900	0.29	7.75	34	15,000	0.02	0.26	990
29	03/29/91	315	900	0.35	13.21	24	15,000	0.02	0.29	1,097
43	04/12/91	395	900	0.44	9.63	41	15,000	0.03	0.31	1,258
57	04/26/91	500	900	0.56	8.51	59	15,000	0.03	0.34	1,458
71	05/10/91	649	900	0.72	6.76	96	15,000	0.04	0.38	1,721
85	05/24/91	867	900	0.96	5.20	167	15,000	0.06	0.42	2,079
99	06/07/91	1,183	900	1.31	4.14	285	15,000	0.08	0.46	2,548
113	06/21/91	1,569	900	1.74	4.46	352	15,000	0.10	0.51	3,070
127	07/05/91	2,034	900	2.26	4.76	428	15,000	0.14	0.56	3,643
141	07/19/91	2,582	900	2.87	5.05	511	15,000	0.17	0.61	4,266
155	08/02/91	3,220	900	3.58	5.35	602	15,000	0.21	0.65	4,937
169	08/16/91	3,954	900	4.39	5.63	702	15,000	0.26	0.70	5,655
183	08/30/91	4,790	900	5.32	5.90	811	15,000	0.32	0.75	6,418
197	09/13/91	5,686	1,350	4.21	6.70	849	15,000	0.38	0.79	7,188
211	09/27/91	6,686	1,350	4.95	6.94	963	15,000	0.45	0.84	7,999
225	10/11/91	7,794	1,350	5.77	7.18	1,086	15,000	0.52	0.88	8,851
239	10/25/91	8,694	1,350	6.44	12.21	712	15,000	0.58	0.91	9,510
253	11/08/91	9,188	1,800	5.10	30.85	298	15,000	0.61	0.93	9,858
267	11/22/91	9,362	1,800	5.20	91.75	102	15,000	0.62	0.94	9,972
281	12/06/91	9,539	1,800	5.30	90.06	106	15,000	0.64	0.95	10,088
295	12/20/91	9,548	1,800	5.30	99.93	96	15,000	0.64	0.95	10,086
309	01/03/92	9,660	1,800	5.37	99.13	97	15,000	0.64	0.95	10,157
323	01/17/92	9,774	1,800	5.43	99.12	99	15,000	0.65	0.96	10,228
337	01/31/92	9,890	1,800	5.49	99.12	100	15,000	0.66	0.96	10,301
351	02/14/92	10,008	1,800	5.56	99.12	101	15,000	0.67	0.96	10,376
365	02/28/92	10,268	1,800	5.70	58.12	177	15,000	0.68	0.97	10,548
379	03/13/92	10,824	1,800	6.01	27.08	400	15,000	0.72	0.99	10,918
393	03/27/92	11,552	1,800	6.42	20.62	560	15,000	0.77	1.01	11,394
407	04/10/92	12,470	1,800	6.93	16.08	776	15,000	0.83	1.04	11,983
421	04/24/92	13,519	1,800	7.51	14.27	948	15,000	0.90	1.07	12,637

OAK FLAT - COHO

Growth - Food

RUN NAME: MYOF1A

PERIOD ENDING DAY	PERIOD ENDING DATE	2 NO. FISH	MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14DAY FEED REQ. (LBS.)	2 FOOD FED /DAY
	03/15/91	2,400,000				29.0	1,800.0	1,333			
15	03/29/91	2,288,061	4.66	42.0	44.0	31.6	1,383.4	1,654	1.00	321	1.6
29	04/12/91	2,211,455	3.19	44.0	44.0	34.8	1,037.1	2,132	1.04	498	2.0
43	04/26/91	2,159,850	2.15	45.0	44.0	38.3	780.9	2,766	1.08	686	2.1
57	05/10/91	2,124,760	1.46	47.0	44.0	42.3	580.1	3,663	1.12	1,008	2.4
71	05/24/91	2,100,898	0.99	50.0	44.0	47.1	420.6	1,995	1.17	1,553	2.8
85	06/07/91	2,084,672	0.68	53.0	44.0	52.6	300.5	6,938	1.22	2,345	3.1
99	06/21/91	2,073,638	0.46	57.0	44.0	59.3	210.3	9,859	1.25	3,546	3.4
113	07/05/91	2,066,135	0.31	57.0	44.0	65.9	152.9	13,510	1.29	4,709	3.1
127	07/19/91	2,060,973	0.22	58.0	44.0	72.9	113.4	18,174	1.33	6,208	3.0
141	08/02/91	2,056,861	0.17	58.0	44.0	79.8	86.4	23,806	1.37	7,729	2.8
155	08/16/91	2,052,931	0.16	59.0	44.0	86.9	66.7	30,769	1.41	9,845	2.8
169	08/30/91	2,049,108	0.16	54.0	44.0	92.8	54.9	37,336	1.45	9,556	2.1
183	09/13/91	2,045,397	0.15	52.0	44.0	98.1	46.4	44,049	1.50	10,046	1.8
197	09/27/91	2,041,796	0.15	52.0	44.0	103.4	39.6	51,515	1.54	11,482	1.8
211	10/11/91	2,038,315	0.15	52.0	44.0	108.7	34.1	59,773	1.58	13,042	1.7
225	10/25/91	2,034,958	0.14	47.0	44.0	112.7	30.6	66,484	1.62	10,875	1.3
239	11/08/91	2,031,725	0.13	40.0	44.0	114.9	28.9	70,206	1.66	6,187	0.7
253	11/22/91	2,028,616	0.13	35.0	44.0	115.7	28.3	71,569	1.70	2,322	0.2
267	12/06/91	2,025,631	0.12	35.0	44.0	116.5	27.8	72,953	1.74	2,414	0.2
281	12/20/91	2,022,770	0.12	32.5	44.0	116.6	27.7	73,099	1.79	2,047	0.2
295	01/03/92	2,020,034	0.11	34.0	44.0	117.1	27.3	74,004	1.83	2,072	0.2
309	01/17/92	2,017,422	0.11	34.0	44.0	117.6	26.9	74,919	1.87	2,098	0.2
323	01/31/92	2,014,934	0.10	34.0	44.0	118.2	26.6	75,846	1.91	2,124	0.2
337	02/14/92	2,012,570	0.10	34.0	44.0	118.7	26.2	76,784	1.95	2,150	0.2
351	02/28/92	452,324	0.09	36.0	44.0	119.8	25.5	78,778	1.99	3,975	0.4
365	03/13/92	451,848	0.09	40.0	30.0	122.9	23.6	19,126	2.03	2,850	1.1
379	03/27/92	451,386	0.09	42.0	30.0	126.8	21.5	20,983	2.08	3,856	1.4
393	04/10/92	450,924	0.09	44.0	30.0	131.5	19.3	23,369	2.12	5,051	1.7
407	04/24/92	450,462	0.09	45.0	30.0	136.5	17.2	26,151	2.16	6,005	1.8
421	05/08/92	450,000	0.09	47.0	30.0	142.4	15.2	29,627	2.20	7,647	2.0

BIOMASS PRODUCED (LBS.)= 90,680  
 TOTAL FOOD FED (LBS.) = 144,346 AVERAGE CONVERSION = 1.62

NOTE: 77.5 percent of fish are moved to ponds on August 2nd;  
 these fish are relocated to Wapato on February 28th.

OAK FLAT - COHO

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS (INCL. PREVIOUS AND NEXT BROODS):

RIVER WATER = 9,900 GPM (22 cfs)  
 RACEWAY SPACE = 50,000 CU.FT. (MAX.) POND SPACE = 100,000 CU.FT. (MAX.)

HYOF1AR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----				-----POND REQMT'S-----				
PERIOD	PERIOD	TOTAL	ACTUAL	AC TUAL	ALLOW-	ACTUAL	ACTUAL	ALLOW-	TOTAL	ACTUAL	ALLOW-	TOTAL	ACTUAL	ALLOW-	TOTAL
ENDING	ENDING	BIOMASS	WATER	LBS./	LBS./	FLOW	RACEWAY	LBS./	LBS./	CU.FT.	POND	CU.FT.	LBS./	LBS./	CU.FT.
DAY	DATE	(LBS.)	USED	GPM	GPM	(GPM)	USED	CU.FT.	CU.FT.	REQ'D	SPACE	USED	CU.FT.	CU.FT.	REQ'D
1	03/15/91	1,333	900	1.48	11.57	115	20,000	0.07	0.22	6,115					
15	03/29/91	1,654	900	1.84	11.57	143	20,000	0.08	0.22	7,585					
29	04/12/91	2,132	900	2.37	8.73	244	20,000	0.11	0.24	8,884					
43	04/26/91	2,766	900	3.07	7.82	354	20,000	0.14	0.26	10,483					
57	05/10/91	3,663	1,350	2.71	6.28	583	20,000	0.18	0.29	12,573					
71	05/24/91	4,995	1,350	3.70	4.87	1,027	50,000	0.10	0.32	15,405					
85	06/07/91	6,938	8,100	0.86	3.90	1,780	50,000	0.14	0.36	19,127					
99	06/21/91	9,859	8,100	1.22	2.92	3,377	50,000	0.20	0.41	24,132					
113	07/05/91	13,510	8,100	1.67	3.18	4,247	50,000	0.27	0.45	29,737					
127	07/19/91	18,174	8,100	2.24	3.16	5,754	50,000	0.36	0.50	36,208					
141	08/02/91	23,806	8,100	2.94	3.39	7,025	50,000	0.48	0.55	43,317					
155	08/16/91	30,769	9,900	3.11	3.18	9,667	50,000	0.14	0.60	11,557	100,000	0.24	0.48	49,761	
169	08/30/91	37,336	9,900	3.77	5.49	6,795	50,000	0.17	0.64	13,140	100,000	0.29	0.51	56,575	
183	09/13/91	44,049	9,900	4.45	6.73	6,545	50,000	0.20	0.68	14,662	100,000	0.34	0.54	63,130	
197	09/27/91	51,515	9,900	5.20	6.93	7,433	30,000	0.39	0.71	16,266	100,000	0.40	0.57	70,034	
211	10/11/91	59,773	9,900	6.04	7.12	8,393	30,000	0.45	0.75	17,951	100,000	0.46	0.60	77,288	
225	10/25/91	66,484	8,100	8.21	12.02	5,533	30,000	0.50	0.78	19,260	100,000	0.52	0.62	82,923	
239	11/08/91	70,206	8,100	8.67	29.89	2,349	30,000	0.53	0.79	19,961	100,000	0.54	0.63	85,945	
253	11/22/91	71,569	8,100	8.84	85.08	841	30,000	0.54	0.80	20,209	100,000	0.55	0.64	87,009	
267	12/06/91	72,953	8,100	9.01	83.42	874	30,000	0.55	0.80	20,458	100,000	0.57	0.64	88,084	
281	12/20/91	73,099	8,100	9.02	99.85	732	30,000	0.55	0.80	20,476	100,000	0.57	0.64	88,160	
295	01/03/92	74,004	8,100	9.14	99.08	747	30,000	0.56	0.81	20,635	100,000	0.57	0.65	88,846	
309	01/17/92	74,919	8,100	9.25	99.08	756	30,000	0.56	0.81	20,796	100,000	0.58	0.65	89,538	
323	01/31/92	75,846	8,100	9.36	99.08	765	30,000	0.57	0.81	20,959	100,000	0.59	0.65	90,230	
337	02/14/92	76,784	8,100	9.48	99.08	775	30,000	0.58	0.82	21,123	100,000	0.60	0.65	90,945	
351	02/28/92	78,778	8,100	9.73	54.44	1,447	30,000	0.59	0.83	21,479	100,000	0.61	0.66	92,479	
365	03/13/92	19,126	4,500	4.25	17.39	1,100	20,000	0.96	0.85	22,588					
379	03/27/92	20,983	4,500	4.66	13.37	1,570	30,000	0.70	0.87	24,020					
393	04/10/92	23,369	4,500	5.19	10.52	2,222	30,000	0.78	0.91	25,799					
407	04/24/92	26,151	4,500	5.81	9.42	2,777	30,000	0.87	0.94	27,798					
421	05/08/92	29,627	4,500	6.58	7.51	3,944	30,000	0.99	0.98	30,199					

**OAK FLAT**

**STEELHEAD**

**Growth - Food**

RUN WANE: HYOF2A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	% MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	% FOOD FED /DAY
211	10/11/91	204,670				158.9	12.0	17,056			
225	10/25/91	204,210	0.18	47.0	28.0	165.1	10.7	19,112	1.51	3,106	1.3
239	11/08/91	203,767	0.17	40.0	28.0	168.5	10.1	20,251	1.55	1,769	0.7
253	11/22/91	203,341	0.17	35.0	28.0	169.7	9.8	20,663	1.59	656	0.2
267	12/06/91	202,932	0.16	35.0	28.0	171.0	9.6	21,082	1.63	684	0.2
281	12/20/91	202,541	0.15	32.5	28.0	171.0	9.6	21,119	1.64	591	0.2
295	01/03/92	202,166	0.15	34.0	28.0	172.0	9.5	21,390	1.71	599	0.2
309	01/17/92	201,808	0.14	34.0	28.0	172.9	9.3	21,664	1.76	607	0.2
323	01/31/92	201,467	0.13	34.0	28.0	173.7	9.2	21,943	1.80	614	0.2
337	02/14/92	201,143	0.13	34.0	28.0	174.5	9.1	22,225	1.84	622	0.2
351	02/28/92	200,836	0.12	36.0	28.0	176.2	8.8	22,835	1.88	1,145	0.4
365	03/13/92	200,547	0.11	40.0	28.0	179.6	8.3	24,124	1.92	2,473	0.8
379	03/27/92	200,265	0.11	42.0	28.0	183.7	7.8	25,811	1.96	3,305	1.0
393	04/10/92	199,984	0.11	44.0	28.0	188.7	7.2	27,943	2.00	4,263	1.2

BIOMASS PRODUCED (LBS.) = 10,887

TOTAL FOOD FED (LBS.) = 20,435

AVERAGE CONVERSION = 1.88

OAK FLAT - STEELHEAD

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 4,050 GPM (9 cfs)  
 RACEWAYSPACE = 30,000 CU.FT.

HYOF2AR		-----WATER FLOW REQMT'S-----					-----RACEWAYREQMT'S-----				
PERIOD	PERIOD	TOTAL	ACTUAL	ALLOW-		ACTUAL	ALLOW-			TOTAL	
ENDING	ENDING	BIOMASS	WATER	ACTUAL	ABLE	FLOW	RACEWAY	ACTUAL	ABLE	CU.FT.	
DAY	DATE	(LBS.)	FLOW	LBS./	LBS./	REQ'D	SPACE	LBS./	LBS./	REQ'D	
			USED	GPM	GPM	(GPM)	USED	CU.FT.	CU.FT.		
1	10/11/91	17,056	3,600	4.74	12.03	1,418	30,000	0.57	1.14	14,990	
15	10/25/91	19,112	3,600	5.31	12.03	1,589	30,000	0.64	1.14	16,797	
29	11/08/91	20,251	3,600	5.63	30.08	673	30,000	0.68	1.16	17,446	
43	11/22/91	20,663	3,600	5.74	86.85	238	30,000	0.69	1.17	17,669	
57	12/06/91	21,082	3,600	5.86	85.05	248	30,000	0.70	1.18	17,895	
71	12/20/91	21,119	3,600	5.87	99.87	211	30,000	0.70	1.18	17,904	
85	01/03/92	21,390	3,600	5.94	99.05	216	30,000	0.71	1.19	18,046	
99	01/17/92	21,664	3,600	6.02	99.05	219	30,000	0.72	1.19	18,189	
113	01/31/92	21,943	3,600	6.10	99.05	222	30,000	0.73	1.20	18,334	
127	02/14/92	22,225	3,600	6.17	99.05	224	30,000	0.74	1.20	18,481	
141	02/28/92	22,835	3,600	6.34	54.74	417	30,000	0.76	1.21	18,808	
155	03/13/92	24,124	4,050	5.96	25.69	939	30,000	0.80	1.24	19,500	
169	03/27/92	25,811	4,050	6.37	19.54	1,321	30,000	0.86	1.27	20,390	
183	04/10/92	27,943	4,050	6.90	15.22	1,836	30,000	0.93	1.30	21,487	

FOOD REQUIREMENTS AT OAK FLAT

HYOF1AF

PERIOD ENDING DATE	***** LBS. FOOD REQUIRED BY SPECIES *****				TOTAL LBS. FOOD REQUIRED
	SPRING CHINOOK	SUMMER CHINOOK	STEELHEAD	COHO	
01/29/91	1,952	551	1,221	4,221	7,945
02/28/91	3,976	1,884	4,240	8,975	19,076
03/30/91	8,326	3,349	7,569	9,726	28,969
04/30/91		2,383		15,346	17,729
05/30/91		637		3,898	4,535
06/30/91		1,072		8,355	9,427
07/30/91		1,577		13,937	15,514
08/29/91		3,492		29,447	32,939
09/29/91	4,230	3,164		24,524	31,919
10/29/91	5,542	2,180	4,875	17,062	29,660
11/29/91	1,479	574	1,340	4,735	8,129
12/29/91	1,261	538	1,190	4,119	7,108
01/29/92	1,952	551	1,221	4,221	7,945

WATER FLOW REQUIREMENTS  
AT OAK FLAT

HYOF1AZ

PERIOD ENDING DAY	PERIOD ENDING DATE	----- ACTUAL -----		-- MIN. GPM WATER	REQ'D -- CFS WATER
		GPM WATER	CFS WATER		
1	01/01/91	17,100	38.0	1,289	2.9
15	01/15/91	17,100	38.0	1,306	2.9
29	01/29/91	17,100	38.0	1,322	2.9
43	02/12/91	17,100	38.0	1,338	3.0
57	02/26/91	18,000	40.0	2,524	5.6
71	03/12/91	16,200	36.0	3,623	8.1
85	03/26/91	16,200	36.0	5,074	11.3
99	04/09/91	16,200	36.0	7,142	15.9
113	04/23/91	8,100	18.0	4,138	9.2
127	05/07/91	6,750	15.0	4,623	10.3
141	05/21/91	2,250	5.0	1,194	2.7
155	06/04/91	9,000	20.0	2,065	4.6
169	06/18/91	9,000	20.0	3,729	8.3
183	07/02/91	9,000	20.0	4,675	10.4
197	07/16/91	9,000	20.0	6,265	13.9
211	07/30/91	9,000	20.0	7,627	16.9
225	08/13/91	10,800	24.0	10,369	23.0
239	08/27/91	10,800	24.0	7,606	16.9
253	09/10/91	11,250	25.0	7,394	16.4
267	09/24/91	14,400	32.0	10,731	23.8
281	10/08/91	18,000	40.0	13,656	30.3
295	10/22/91	16,200	36.0	9,651	21.4
309	11/05/91	17,100	38.0	4,083	9.1
323	11/19/91	17,100	38.0	1,444	3.2
337	12/03/91	17,100	38.0	1,501	3.3
351	12/17/91	17,100	38.0	1,263	2.8
365	12/31/91	17,100	38.0	1,289	2.9
379	01/14/92	17,100	38.0	1,306	2.9
393	01/28/92	17,100	38.0	1,322	2.9

**OAK FLAT**

**Pollutants**

Estimated PPM of Pollutants Generated Daily for  
all Species Programmed at Oak flats

**HYOF1AP**

PERIOD ENDING DAY	PERIOD ENDING DATE	FOOD		POLLUTANTS GENERATED IN PPM **						RECEIVING WATER (CFS)
		FED SPECIES (LBS.)	ALL GPM WATER ACTUAL	TOTAL AMMONIA	NH3	NITRATE	PHOSPHATE	SETTLED SOLIDS	B.O.D.	
1	01/01/91	255	17,100	0.04	0.0001	0.11	0.01	0.37	0.42	
15	01/15/91	259	17,100	0.04	0.0001	0.11	0.01	0.38	0.43	
29	01/29/91	262	17,100	0.04	0.0001	0.11	0.01	0.38	0.43	
43	02/12/91	265	17,100	0.04	0.0001	0.11	0.01	0.39	0.44	
57	02/26/91	490	18,000	0.07	0.0001	0.20	0.01	0.68	0.77	
71	03/12/91	655	16,200	0.11	0.0002	0.29	0.02	1.01	1.14	
85	03/26/91	898	16,200	0.15	0.0002	0.40	0.02	1.39	1.57	
99	04/09/91	1,171	16,200	0.19	0.0003	0.52	0.03	1.81	2.05	
113	04/23/91	636	8,100	0.21	0.0003	0.57	0.03	1.96	2.22	
127	05/07/91	630	6,750	0.25	0.0004	0.68	0.04	2.33	2.64	
141	05/21/91	129	2,250	0.15	0.0002	0.42	0.02	1.44	1.63	
155	06/04/91	195	9,000	0.06	0.0001	0.16	0.01	0.54	0.61	
169	06/18/91	295	9,000	0.09	0.0001	0.24	0.01	0.82	0.93	
183	07/02/91	379	9,000	0.11	0.0002	0.31	0.02	1.05	1.19	
197	07/16/91	495	9,000	0.15	0.0002	0.40	0.02	1.37	1.56	
211	07/30/91	613	9,000	0.18	0.0003	0.49	0.03	1.70	1.93	
225	08/13/91	776	10,800	0.19	0.0003	0.52	0.03	1.80	2.03	
239	08/27/91	767	10,800	0.19	0.0003	0.51	0.03	1.78	2.01	
253	09/10/91	810	11,250	0.19	0.0003	0.52	0.03	1.80	2.04	
267	09/24/91	926	14,400	0.17	0.0003	0.47	0.03	1.61	1.82	
281	10/08/91	1,354	18,000	0.20	0.0003	0.55	0.03	1.88	2.13	
295	10/22/91	1,351	16,200	0.22	0.0003	0.60	0.03	2.09	2.36	
309	11/05/91	767	17,100	0.12	0.0002	0.33	0.02	1.12	1.27	
323	11/19/91	285	17,100	0.04	0.0001	0.12	0.01	0.42	0.47	
337	12/03/91	296	17,100	0.05	0.0001	0.13	0.01	0.43	0.49	
351	12/17/91	252	17,100	0.04	0.0001	0.11	0.01	0.37	0.42	
365	12/31/91	255	17,100	0.04	0.0001	0.11	0.01	0.37	0.42	
379	01/14/92	259	17,100	0.04	0.0001	0.11	0.01	0.38	0.43	
393	01/28/92	262	17,100	0.04	0.0001	0.11	0.01	0.38	0.43	

\*\* The ppm of pollutants in the discharge water is illustrated in the table.  
Vacuum cleaning will significantly reduce the level of settleable solids  
and B.O.D.

**F L O W I S P A C E , F O O D**

**S U M M A R Y**

**For**

**NELSON SPRINGS**

**By Fish Management Consultants  
Olympia, WA**

NELSON SPRINGS - FALL CHINOOK

Growth - Food

RUN NAME: HYBK1A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	2 MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	2 FOOD FED /DAY
i	02/05/91	3,870,967				36.3	1,160.6	3,335			
15	02/19/91	3,780,117	2.35	52.0	30.0	44.1	647.1	5,842	1.00	2,507	4.6
29	03/05/91	3,717,942	1.61	50.0	30.0	51.1	415.4	8,951	1.03	3,207	3.5
43	03/19/91	1,225,353	1.08	50.0	30.0	58.1	282.3	13,022	1.06	4,327	3.1
57	04/02/91	1,215,860	0.74	51.0	33.0	64.8	203.1	5,985	1.09	1,799	2.7
71	04/16/91	1,209,404	0.50	52.0	33.0	71.9	148.8	8,127	1.13	2,412	2.7
85	04/30/91	1,205,015	0.34	53.0	33.0	79.4	110.7	10,881	1.16	3,186	2.6
99	05/14/91	1,202,030	0.23	54.0	33.0	87.2	83.6	16,378	1.19	4,156	2.5
113	05/28/91	1,200,000	0.16	55.0	33.0	95.3	63.9	18,769	1.22	5,357	2.5

BIOMASS PRODUCED (LBS.) = 27,450

TOTAL FOOD FED (LBS.) = 26,951 AVERAGE CONVERSION = 1.12

NOTE: average temperature is programed for 54 F  
 from February 5th through February 12th;  
 67% of fish are relocated to Wapato and Prosser  
 March 19.

NELSON SPRINGS - FALL CHINOOK

Flow - Space

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 4,500 GPM (10 cfs)  
 RACEWAY SPACE = 30,000 CU.FT.

HYBK1AR		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	FLOW	ACTUAL	ACTUAL	ALLOW-	TOTAL
ENDING	ENDING	BIO MASS	WATER	LBS./	LBS./	REQ'D	RACEWAY	LBS./	LBS./	CU.FT.
CAY	DATE	(LBS.)	USED	GPM	GPM	(GPM)	SPACE	CU.FT.	CU.FT.	REQ'D
	02/05/91	3,335	3,150	1.06	2.68	1,243	30,000	0.11	0.30	10,985
15	02/19/91	5,842	3,150	1.85	2.68	2,178	30,000	0.19	0.30	19,240
29	03/05/91	8,951	3,150	2.84	3.88	2,307	30,000	0.30	0.35	25,431
43	03/19/91	13,022	3,150	4.13	4.34	2,997	30,000	0.43	0.40	32,528
57	04/02/91	5,985	3,150	1.90	4.85	1,235	30,000	0.20	0.45	13,397
71	04/16/91	8,127	3,150	2.58	4.66	1,742	30,000	0.27	0.50	16,400
85	04/30/91	10,881	3,150	3.45	4.62	2,355	30,000	0.36	0.55	19,897
99	05/14/91	14,378	4,500	3.20	4.57	3,147	30,000	0.48	0.60	23,939
113	05/28/91	18,769	4,500	4.17	4.51	4,164	30,000	0.63	0.66	28,578

**NELSON SPRINGS - STEELHEAD**

**Growth - Food**

RUN NAME: HYBK2A

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED RED. (LBS.)	2 FOOD FED /CAY
1	03/15/91	553,845				25.8	2,806.1	197			
15	03/29/91	509,122	8.68	51.0	39.0	31.5	1,541.6	330	0.90	120	3.8
29	04/12/91	478,515	5.53	52.0	39.0	37.5	913.6	524	0.95	184	3.5
43	04/26/91	457,896	3.72	53.0	39.0	43.8	573.4	799	1.00	275	3.4
57	05/10/91	443,878	2.53	54.0	39.0	50.4	376.3	1,180	1.05	400	3.2
71	05/24/91	434,344	1.72	55.0	39.0	57.3	256.1	1,696	1.10	568	3.1
85	06/07/91	427,862	1.17	59.0	39.0	65.4	172.2	2,485	1.15	907	3.5
99	06/21/91	423,453	0.80	60.0	39.0	73.8	119.8	3,533	1.20	1,259	3.3
113	07/05/91	420,456	0.54	61.0	39.0	82.5	85.8	4,901	1.25	1,710	3.2
127	07/19/91	418,393	0.37	61.0	39.0	91.2	63.5	6,589	1.30	2,194	3.0
141	08/02/91	416,751	0.30	61.0	39.0	99.9	48.3	8,626	1.35	2,750	2.8
155	08/16/91	415,180	0.28	61.0	39.0	108.6	37.6	11,040	1.40	3,380	2.6
169	08/30/91	413,653	0.28	60.0	39.0	117.0	30.1	13,755	1.45	3,936	2.4
183	09/13/91	412,170	0.27	59.0	39.0	125.1	24.6	16,754	1.50	4,498	2.2
197	09/27/91	410,732	0.26	58.0	39.0	132.9	20.5	20,017	1.55	5,056	2.1
211	10/11/91	204,670	0.25	55.0	39.0	139.8	17.6	23,221	1.60	5,126	1.8
225	10/25/91	204,112	0.20	53.0	28.0	122.2	26.4	7,735	1.59	2,433	2.6
239	11/08/91	203,576	0.19	49.0	28.0	129.3	22.3	9,139	1.63	2,294	2.0
253	11/22/91	203,059	0.19	49.0	28.0	136.4	19.0	10,703	1.68	2,625	2.0
267	12/06/91	202,564	0.18	49.0	28.0	143.5	16.3	12,433	1.73	2,985	1.9
281	12/20/91	202,088	0.17	49.0	28.0	150.6	14.1	14,338	1.77	3,374	1.9
295	01/03/92	201,634	0.16	49.0	28.0	157.7	12.3	16,427	1.82	3,795	1.8
309	01/17/92	201,200	0.16	50.0	28.0	165.2	10.7	18,850	1.86	4,513	1.9
323	01/31/92	200,787	0.15	50.0	28.0	172.7	9.3	21,499	1.91	5,055	1.9
337	02/14/92	200,394	0.14	50.0	28.0	180.2	8.2	24,383	1.95	5,636	1.8
351	02/28/92	200,022	0.13	50.0	28.0	187.8	7.3	27,513	2.00	6,259	1.8

BIOMASS PRODUCED (LBS.) = 39,123

TOTAL FOOD FED (LBS.) = 71,333 AVERAGE CONVERSION = 1.83

50% of brood stock averaging 12/lb are transfered to Oak Flat on 10/11. The 50% remaining at Nelson Springs average 33/lb on 10/11.

**NELSON SPRINGS - STEELHEAD**

**Flow - Space**

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

WATER FLOW = 4,500 GPM (10 cfs)

RACEWAY SPACE = 25,000 CU.FT.

HYBK2AR		----- WATER FLOW REQMT'S-----					----- RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ALLOW-	ACTUAL	ACTUAL	ALLOW-	TOTAL		
ENDING	ENDING	BIOMASS	WATER	ACTUAL	ABLE	FLOW	RACEWAY	ACTUAL	ABLE	TOTAL
DAY	DATE	(LBS.)	FLOW	LBS./	LBS./	REQ'D	SPACE	LBS./	LBS./	CU.FT.
			USED	GPM	GPM	(GPM)	USED	CU.FT.	CU.FT.	REQ'D
1	03/15/91	197	450	0.44	3.50	56	25,000	0.01	0.22	910
15	03/29/91	330	450	0.73	3.50	94	25,000	0.01	0.22	1,522
29	04/12/91	524	450	1.16	3.52	149	25,000	0.02	0.26	2,028
43	04/26/91	799	450	1.77	3.58	223	25,000	0.03	0.30	2,647
57	05/10/91	1,180	450	2.62	3.59	329	25,000	0.05	0.35	3,398
71		1,696	900	1.88	3.58	474	25,000	0.07	0.39	4,298
85	06/07/91	2,485	1,350	1.84	2.55	975	25,000	0.10	0.45	5,516
99	06/21/91	3,533	3,150	1.12	2.54	1,389	25,000	0.14	0.51	6,951
113	07/05/91	4,901	3,150	1.56	2.65	1,852	25,000	0.20	0.57	8,626
127	07/19/91	6,589	3,150	2.09	2.84	2,323	25,000	0.26	0.63	10,489
141	08/02/91	8,626	3,150	2.74	3.02	2,856	25,000	0.35	0.69	12,536
155	08/16/91	11,040	4,050	2.73	3.20	3,452	25,000	0.44	0.75	14,759
169	08/30/91	13,755	4,050	3.40	3.49	3,941	25,000	0.55	0.81	17,068
183	09/13/91	16,754	4,500	3.72	3.96	4,228	25,000	0.67	0.86	19,443
197	09/27/91	20,017	4,500	4.45	4.66	4,297	25,000	0.80	0.92	21,867
211	10/11/91	23,221	4,050	5.73	6.36	3,652	25,000	0.93	0.96	24,115
225	10/25/91	7,735	4,050	1.91	4.53	1,706	25,000	0.31	0.84	9,189
239	11/08/91	9,139	4,050	2.26	7.09	1,289	25,000	0.37	0.89	10,261
253	11/22/91	10,703	4,050	2.64	7.31	1,465	25,000	0.43	0.94	11,390
267	12/06/91	12,433	4,050	3.07	7.51	1,655	25,000	0.50	0.99	12,577
281	12/20/91	14,338	4,050	3.54	7.70	1,861	25,000	0.57	1.04	13,820
295	01/03/92	16,427	4,050	4.06	7.89	2,083	25,000	0.66	1.09	15,120
309	01/17/92	18,850	4,050	4.65	7.18	2,627	25,000	0.75	1.14	16,561
323	01/31/92	21,499	4,050	5.31	7.34	2,928	25,000	0.86	1.19	18,066

FOOD REQUIREMENTS AT NELSON SPRINGS

HYBK1AF

PERIOD ENDING DATE	***** LBS. FOOD REQUIRED BY SPECIES *****		TOTAL LBS. FOOD REQUIRED
	FALL		
	CHINOOK	STEELHEAD	
01/29/91		9,568	9,568
02/28/91	5,714	11,896	17,609
03/30/91	6,126	120	6,246
04/30/91	5,598	459	6,057
05/30/91	9,514	968	10,482
06/30/91		3,875	3,875
07/30/91		4,944	4,944
08/29/91		7,316	7,316
09/29/91		9,557	9,557
10/29/91		7,559	7,559
11/29/91		7,904	7,904
12/29/91		7,169	7,169
01/29/92		9,568	9,568

WATER FLOW REQUIREMENTS  
AT NELSON SPRINGS

HYBK1AZ

PERIOD ENDING GAY	PERIOD ENDING DATE	----- ACTUAL -----		-- MIN. GPM WATER	REQ'D -- CFS WATER
		GPM WATER	CFS WATER		
1	01/01/91	4,050	9.0	2,083	4.6
15	01/15/91	4,050	9.0	2,627	5.8
29	01/29/91	4,050	9.0	2,928	6.5
43	02/12/91	3,150	7.0	1,243	2.8
57	02/26/91	3,150	7.0	2,178	4.8
71	03/12/91	3,600	8.0	2,363	5.3
85	03/26/91	3,600	8.0	3,091	6.9
99	04/09/91	3,600	8.0	1,384	3.1
113	04/23/91	3,600	8.0	1,965	4.4
127	05/07/91	3,600	8.0	2,684	6.0
141	05/21/91	5,400	12.0	3,621	8.0
155	06/04/91	5,850	13.0	5,139	11.4
169	06/18/91	3,150	7.0	1,389	3.1
183	07/02/91	3,150	7.0	1,852	4.1
197	07/16/91	3,150	7.0	2,323	5.2
211	07/30/91	3,150	7.0	2,856	6.3
225	08/13/91	4,050	9.0	3,452	7.7
239	08/27/91	4,050	9.0	3,941	8.8
253	09/10/91	4,500	10.0	4,228	9.4
267	09/24/91	4,500	10.0	4,297	9.5
281	10/08/91	4,050	9.0	3,652	8.1
295	10/22/91	4,050	9.0	1,706	3.8
309	11/05/91	4,050	9.0	1,289	2.9
323	11/19/91	4,050	9.0	1,465	3.3
337	12/03/91	4,050	9.0	1,655	3.7
351	12/17/91	4,050	9.0	1,861	4.1
365	12/31/91	4,050	9.0	2,083	4.6
379	01/14/92	4,050	9.0	2,627	5.8
393	01/28/92	4,050	9.0	2,928	6.5

**NELSON SPRINGS**

**Pollutants**

Estimated **PPM** of Pollutants **Generated** Daily for  
all Species **Programed** at Nelson Springs

HYBK1AP

PERIOD ENDING DAY	PERIOD ENDING DATE	FOOD FED ALL SPECIES (LBS.)	GPM WATER ACTUAL	POLLUTANTS GENERATED IN PPM **						RECEIVING WATER B.O.D. (CFS)
				TOTAL AMMONIA	NH3	NITRATE	PHOSPHATE	SETTLED SOLIOS	B.O.D.	
1	01/01/91	271	4,050	0.18	0.0003	0.49	0.03	1.67	1.89	
15	01/15/91	322	4,050	0.21	0.0003	0.58	0.03	1.99	2.25	
29	01/29/91	361	4,050	0.24	0.0003	0.65	0.04	2.23	2.52	
43	02/12/91	403	3,150	0.34	0.0005	0.93	0.05	3.20	3.62	
57	02/26/91	626	3,150	0.53	0.0008	1.44	0.08	4.97	5.63	
71	03/12/91	229	3,600	0.17	0.0002	0.46	0.03	1.59	1.80	
85	03/26/91	318	3,600	0.24	0.0003	0.64	0.04	2.21	2.50	
99	04/09/91	142	3,600	0.11	0.0002	0.29	0.02	0.98	1.11	
113	04/23/91	192	3,600	0.14	0.0002	0.39	0.02	1.33	1.51	
127	05/07/91	256	3,600	0.19	0.0003	0.52	0.03	1.78	2.01	
141	05/21/91	337	5,400	0.17	0.0002	0.45	0.03	1.56	1.77	
155	06/04/91	447	5,850	0.20	0.0003	0.55	0.03	1.91	2.16	
169	06/18/91	90	3,150	0.08	0.0001	0.21	0.01	0.71	0.81	
183	07/02/91	122	3,150	0.10	0.0002	0.28	0.02	0.97	1.10	
197	07/16/91	157	3,150	0.13	0.0002	0.36	0.02	1.24	1.41	
211	07/30/91	196	3,150	0.17	0.0002	0.45	0.03	1.56	1.77	
225	08/13/91	241	4,050	0.16	0.0002	0.43	0.02	1.49	1.69	
239	08/27/91	281	4,050	0.19	0.0003	0.50	0.03	1.74	1.96	
253	09/10/91	321	4,500	0.19	0.0003	0.52	0.03	1.79	2.02	
267	09/24/91	361	4,500	0.21	0.0003	0.58	0.03	2.01	2.27	
281	10/08/91	366	4,050	0.24	0.0004	0.66	0.04	2.26	2.56	
295	10/22/91	174	4,050	0.11	0.0002	0.31	0.02	1.07	1.21	
309	11/05/91	164	4,050	0.11	0.0002	0.29	0.02	1.01	1.15	
323	11/19/91	187	4,050	0.12	0.0002	0.34	0.02	1.16	1.31	
337	12/03/91	213	4,050	0.14	0.0002	0.38	0.02	1.32	1.49	
351	12/17/91	241	4,050	0.16	0.0002	0.43	0.02	1.49	1.68	
365	12/31/91	271	4,050	0.18	0.0003	0.49	0.03	1.67	1.89	
379	01/14/92	322	4,050	0.21	0.0003	0.58	0.03	1.99	2.25	
393	01/28/92	361	4,050	0.24	0.0003	0.65	0.04	2.23	2.52	

\*\* The ppm of pollutants in the discharge water is illustrated in the table.  
Vacuum cleaning will significantly reduce the level of settleable solids  
and B.O.D.

KLICKITAT SALMON AND STEELHEAD HATCHERY  
PRELIMINARY DESIGN REPORT


**CERTIFICATE OF ENGINEER**

**KLICKITAT SALMON AND STEELHEAD HATCHERY  
PRELIMINARY DESIGN REPORT**

January 1990

The technical material and data contained in this report were prepared under the supervision and direction of the undersigned, whose seal as a professional engineer licensed to practice as such in the State of Washington, is affixed below.



  
\_\_\_\_\_  
Jay S. Kidder  
Civil Engineer

KLICKITAT SALMON AND STEELHEAD HATCHERY  
PRELIMINARY DESIGN REPORT

TABLE OF CONTENTS

<u>Section Number</u>	<u>Section and Subsection Title</u>	<u>Page Number</u>
	Certificate of Engineer	
	Table of Contents	
	List of Tables	
	List of Figures	
I	INTRODUCTION	
	1. Authorization	I-1
	2. Purpose	I-1
	3. Design Review	I-2
	4. Acknowledgments	I-3
II	FISH CULTURE REQUIREMENTS	
	1. Introduction	II-1
	2. Program Goals of Fish Culture	II-1
	a. Goals	II-1
	b. Siting	II-1
	3. Cultural Program Criteria	II-3
	a. Water Quality and Quantity	II-3
	b. Life-Cycle Criteria	II-5
	c. Transportation and Release	II-8
	d. Personnel/Housing	II-9
III	KLICKITAT FACILITY DESIGN	
	1. General Description of Site	III-1
	a. Vicinity Location	III-1
	b. Alternative Sites	III-1
	c. Facility Size	III-1
	d. Production Goals Review	III-2
	e. Current Land Use and Ownership	III-2
	2. Site Development	III-2
	a. Access Roads	III-2
	b. Drainage and Snow Removal	III-3
	c. Construction Clearing and Grubbing	III-3
	d. Site Work and Slope Protection	III-3
	e. Wetlands	III-4
	f. Flood Analysis	III-4
	g. Power Supply	III-5

TABLE OF CONTENTS  
(continued)

<u>Section Number</u>	<u>Section and Subsection Title</u>	<u>Page Number</u>
III	KLICKITAT FACILITY DESIGN (continued)	
3.	Water Supply	III-5
	a. Water Requirements	III-5
	b. River Water Development	III-7
	c. River Sedimentation Reservoir	III-9
	d. Spring Water Development	III-9
	e. Station Reservoir and Degasification	III-11
	f. Water Chillers	III-11
	g. Planting Truck Fill Station	III-12
4.	Fish Production Facilities	III-12
	a. Adult Collection	III-12
	b. Adult Holding	III-13
	c. Incubation and Early Rearing Building	III-13
	d. Rearing	III-15
	e. Marking	III-16
5.	Facility Buildings	III-17
	a. Hatchery Building	III-17
	b. Fish Food Freezer	III-17
	c. Mechanical and Electrical Room	III-17
	d. General Storage	III-17
	e. Shop and Garage	III-18
	f. Hatchery Housing	III-18
6.	Water Effluent Treatment	III-18
	a. Hatchery Effluent and NPDES Pollution Abatement Ponds	III-18
	b. Waste Cleaning System	III-19
	c. Disease and Chemical Control	III-19
7.	Facility Equipment	III-19
	a. Equipment List	III-19
8.	Operation and Maintenance	III-20
	a. Hatchery Monitoring and Control System	III-20
	b. Alarm System	III-20
	c. Data Management	III-21
	d. Fuel Consumption	III-21
IV	FACILITY ENGINEERING	
1.	Structural Design	IV-1
	a. Load Criteria	IV-1
	b. Structural Systems and Materials	IV-1

TABLE OF CONTENTS  
(continued)

<u>Section Number</u>	<u>Section and Subsection Title</u>	<u>Page Number</u>
IV	FACILITY DESIGN (continued)	
2.	Civil/Mechanical Design	IV-2
a.	Codes and Standards	IV-2
b.	Piping Materials	IV-2
c.	Valves and Material	IV-3
d.	Manholes and Catch Basins	IV-3
e.	Heating, Ventilation and Air Conditioning	IV-3
f.	Insulation	IV-3
g.	Domestic Water Supply	IV-3
h.	Fire Protection Supply	IV-4
i.	Domestic Sewage Treatment	IV-4
3.	Electrical Design	IV-4
a.	Commercial Power Supply	IV-4
b.	Emergency Power Supply	IV-5
c.	Power Distribution	IV-5
d.	Lighting System	IV-6
e.	Pump and Large Load Power Supply	IV-6
f.	Controls	IV-6
g.	Future Electrical Loads	IV-6
h.	Residence Power	IV-6
i.	Phone System	IV-7
V	COST ESTIMATION AND IMPLEMENTATION SCHEDULE	
1.	Costs	V-1
2.	Required Permits	V-2
3.	Construction Staging	V-3
4.	Design and Construction Schedule	V-3
VI	REFERENCES	
VII	APPENDICES	
	A - Fish Culture Program, Computer Estimates, Fish Management Consultants	
	B - Site Investigation Report, R. W. Beck	
	C - Flood Stage Analysis	
	D - U.S. Bureau of Reclamation Raw Water Quality Data	
	E - Hatchery Equipment List	

## LIST OF TABLES

<u>Table Number</u>	<u>Title</u>
II-1	Total Smolt Releases From the Klickitat Hatchery
II-2	Proposed Enhancement Facility Sites in the Klickitat River Basin
II-3	Suggestive Temperature Profile for the Klickitat Hatchery Design
II-4	Minimum Water Flow Requirements, Klickitat Hatchery
II-5	Returning Adult Criteria
II-6	Recommended Adult Holding Units at the Klickitat Hatchery
II-7	Incubation Criteria for the Klickitat Hatchery
II-8	Recommended Minimum Incubation Units for the Klickitat Hatchery
II-9	Rearing Criteria for the Klickitat Hatchery
II-10	Required Rearing Units for the Klickitat Hatchery
II-11	Monthly Food Requirements at the Klickitat Hatchery
II-12	Truck Hauling Fish Transportation Schedule in Truck Days in the Klickitat River Basin
II-13	Suggested Staff Level in Staff Months at the Klickitat Hatchery
III-1	Quality of Water Sources for the Klickitat River Basin Enhancement Facility Compared to ADF&G (1983) Water Quality Standards for Salmonid Aquaculture
III-2	Klickitat Hatchery Spring Water Flows
III-3	Summary of Fish Production Facilities at the Klickitat River Basin Enhancement Facility
III-4	Hatchery Building Room Square Footage
IV-1	Electrical Power Demands

## LIST OF FIGURES

<u>Figure Number</u>	<u>Title</u>
II-1	Klickitat Fish Hatchery Showing Rearing Vessels Used for Adult and Juvenile Steelhead
II-2	Klickitat Fish Hatchery Showing Rearing Vessels Used for Spring Chinook
III-1	Vicinity Map
III-2	Site Plan
III-3	Hatchery Site Plan
III-4	New Electric Power Supply Route
III-5	Klickitat River Basin Enhancement Facility Water Flow Rates vs. Month
III-6	Water Temperatures vs. Month, Klickitat River, Cascade and Kidder Springs
III-7	Schematic Hydraulic Profile
III-8	Cascade Spring Intake, Profile View
III-9	Raceway and Rearing Pond Plans and Sections
III-10	Hatchery Building Plan and Elevations
V-1	Design and Construction Schedule

## SECTION I

### INTRODUCTION

#### 1. AUTHORIZATION

The Klickitat Salmon and Steelhead Hatchery Preliminary Design Report was jointly prepared by R. W. Beck and Associates; Bonneville Power Administration, Fish and Wildlife Division (BPA); Yakima Indian Nation; and Fish Management Consultants. The funding and authorization for the Preliminary Design Report were provided by BPA under the terms in the Northwest Power Planning Council's Columbia River Basin Fish and Wildlife Program, 1987 (NPPC, 1987), Sections 703(f)(3), 503(c)(2), and 803(d). R. W. Beck and Associates' authorization and payment has been provided under a Professional Services Agreement dated December 23, 1988.

#### 2. PURPOSE

The reason for planning and constructing a salmon and steelhead hatchery in the Klickitat River Basin, as outlined in the NPPC Program (NPPC, 1987), is to test the hypothesis that new artificial propagation in the basin can be used to increase harvest and enhance natural production while maintaining genetic resources of wild stock fishes.

Salmon and steelhead populations in the Klickitat River Basin are a fraction of their pre-1900 levels. The Klickitat River anadromous fish runs have been impacted from the construction and operation of Bonneville Dam and ocean and river overfishing. (BPA, Environmental Assessment, 1989.) For these reasons, BPA funded the predesign, design, and construction of the Klickitat Salmon and Steelhead Hatchery, which is planned to produce anadromous spring chinook and steelhead species.

This Preliminary Design Report is a result of 14 months of joint efforts by the Technical Work Group including BPA, R. W. Beck and Associates, Yakima Indian Nation, and members of the various fish and wildlife agencies. It serves as a guide that can be used by the Technical Work Group and the design engineers when the process of final design begins.

## 3. DESIGN REVIEW

Klickitat Salmon and Steelhead HatcheryActive Participants  
Technical Work GroupBonneville Power Administration

Project Manager: Tom Clune (509) 575-5805  
 Senior Project Manager  
 Yakima Project  
 Fish and Wildlife Division  
 Bonneville Power Administration  
 Sunfair Professional Building  
 103 South Third Street  
 P.O. Box 2685  
 Yakima, Washington 98907

Environmental  
 Coordinator: Kevin Ward (503) 230-5373  
 PGA  
 Bonneville Power Administration  
 P.O. Box 3621  
 Portland, Oregon 97208

Yakima Indian Nation

Project Manager,  
 Hatchery: Tom Scribner (509) 865-5121  
 FRM  
 Yakima Indian Nation  
 P.O. Box 151  
 Toppenish, Washington 98948

Washington Department of Fisheries

Contact: Bill Hopley (206) 753-6600  
 Assistant Chief Assessment  
 and Development  
 Washington Department of Fisheries  
 115 General Administration Building  
 Olympia, Washington 98504

Jim Gearheard (206) 753-2902  
 Washington Department of Wildlife  
 600 North Capitol Way  
 Olympia, Washington 98504

Active Participants  
Technical Work Group (continued)

Consultants

Contact:	Harry Senn	(206) 456-3826
	President	
	Fish Management Consultants	
	8137 Rainier Road, S.E.	
	Olympia, Washington 98503	

Consulting Engineer

Project Manager:	Jay Kidder	(206) 441-7500
	Senior Engineer	(206) 347-8873
	R. W. Beck and Associates	
	2101 Fourth Avenue	
	Seattle, Washington 98121-2375	

4. ACKNOWLEDGMENTS

We acknowledge the assistance of the Yakima and Klickitat Hatchery Technical Work Group through their lengthy and continual discussion and review of the preliminary design work. We also acknowledge the assistance of the staffs of the Bonneville Power Administration hatchery team and the Yakima Indian Nation for their excellent guidance and review throughout the project.

## SECTION II

### FISH CULTURE REQUIREMENTS

#### 1. INTRODUCTION

This report is founded on the initial fish production goals that were adopted into the appropriate sections of the NPPC Columbia River Basin Fish and Wildlife Program and as later modified by the current Technical Work Group involved in the predesign. This report specifies a facility that will meet the hatchery goal of being a low-cost facility for the enhancement of the target species.

Section II<sup>(1)</sup> describes the biological and physical fish culture requirements of the Klickitat Hatchery System from which the concepts for the design are formulated in Section III. Biological criteria are presented that provide a basis to size for the water system, adult holding space, incubation units, rearing space, and finally transportation and release methods. The biological criteria address the number and type of water vessels, and the related support requirements. To be assured the components of the system meet all program demands, each life phase from adult capture to the juvenile transfer into acclimation sites is analyzed.

#### 2. PROGRAM GOALS OF FISH CULTURE/SITING

##### a. Goals

The Northwest Power Planning Council's Facility Master Plan (FMC, 1987) provides the basis for the fish production goals that are set for the Klickitat River Basin. This predesign report references these goals as those that drive the size and extent of the proposed Klickitat Hatchery. Fish production goals are outlined in Table II-1, and include a production level at the 10th year of operation of 2,100,000 spring chinook and 270,000 summer steelhead juvenile releases.

##### b. Siting

The proposed sites to culture fish are listed in Table II-2. A description of sites within the Klickitat River Basin is included in Section III of this report. The site listed as a central facility include operations for adult holding, spawning, egg incubation, and early and extended rearing, as well as acclimation and release. (See BPA, Environmental Assessment, 1989, p. 8.) Acclimation sites receive fish from the central facility for short-term holding and rearing prior to release. This reduces transportation stress and acclimate fish to the receiving waters. (BPA, Environmental Assessment, 1989, p. 13.)

---

(1) Section II, Fish Culture Requirements, was provided in cooperation with Fish Management Consultants, Olympia, Washington.

TABLE II-1

TOTAL SMOLT RELEASES FROM THE KLICKITAT HATCHERY  
(YEAR 10 PRODUCTION GOAL)

(With the number of Experimental  
Study Groups in Parentheses)<sup>(1)(2)</sup>

<u>Stock</u>	<u>Release Size</u>	<u>Klickitat</u>
Spring chinook	15/1b	2,100,000 (130)
Steelhead	9/1b	260,000 (8)
Coho	15/1b	

(1) The listings in this table supersede all previous production and study design numbers.

(2) Provided by Experimental Design Work Group (EDWG).

TABLE II-2

PROPOSED ENHANCEMENT FACILITY SITES  
IN THE KLICKITAT RIVER BASIN

<u>Central Facilities</u>	<u>Satellite Facilities</u>
Cascade Springs (upper site)	None
<u>Acclimation Facilities</u>	<u>Trapping and Hauling</u>
Various Upper Klickitat Basin Sites	Falls 5 Fishway Klickitat Hatchery (WDF) Castile Falls Fishway

Figures III-1 and III-2 illustrate the general location of the selected site.

### 3. FISH CULTURAL PROGRAM CRITERIA

#### a. Water Quality and Quantity

The controlling criteria for the fish culture program are the water quality and quantity. Criteria for these follow:

##### (1) Quality

##### (a) Water Chemistry

The general water chemistry guidelines for the enhancement facility are shown in Table III-1 (Alaska Department of Fish and Game Water Quality Standards), along with the findings for water chemistry for each water source on the Klickitat River.

##### (b) Disease Criteria as a Part of Water Quality

Several criteria have been agreed upon in the hatchery design that relate to disease. These include:

- o The initial incubation of all eggs will use disease-free water, e.g., spring or well water. Isolation in bucket incubators is suggested initially for steelhead and will be designed for future use options on chinook.
- o Rearing will be conducted only with first pass water.
- o Second or third pass water can be used for holding adults.
- o To reduce stress and potential disease outbreaks, dissolved oxygen gas in the water shall remain 7.0 ml/l or above. Thus, inflowing water or second pass water should be returned to near saturation.
- o The rearing of steelhead in raceways or troughs shall be physically isolated from chinook to reduce the chance of disease-bearing water from being easily transferred, e.g., raceways should not have common walls between steelhead and chinook.

(c) Temperature

The criteria for water temperature can be flexible; however, Table II-3, Suggestive Temperature Profile for Hatchery Design, documents a target for the design engineer.

TABLE II-3  
SUGGESTIVE TEMPERATURE PROFILE  
FOR THE KLICKITAT HATCHERY DESIGN

Species	Adults	Incubation		Rearing		
		First 21 Days	After 21 Days	7 Days	After 7 Days to Smoltification	7 Months Smoltification
Spring Chinook	50 F	42	38	44	54	Seasonal stream temp.
Steel head 1 yr. Smolts	52	53	53	54	56	Seasonal stream temp.
Steel head 2 yr. Smolts	Seasonal stream or 45	42	42	44	44	Seasonal stream temp.

(2) Water Quantity

The minimum quantity of water required for the Klickitat Hatchery is summarized in Table II-4, Minimum Water Flow Requirements. A detailed analysis is included in Section III-3.a.(2), and in the discussions that follow on adult holding, incubation, and rearing.

TABLE II-4  
MINIMUM WATER FLOW REQUIREMENTS  
FOR DESIGN OF  
THE KLICKITAT HATCHERY

Location	Surface		Spring		Total (gpm/cfs)
	(gpm)	(cfs)	(gpm)	(cfs)	
Klickitat	13,658	30	9,298	21	22,456/51

b. Life-Cycle Criteria

(1) Adult Holding and Spawning

Adult brood stock will be trapped at the Falls 5 Fishway, and at the WDF Klickitat Hatchery as shown in Table II-2. Table II-5 identifies returning adult criteria.

Presented in Table II-6, Recommended Adult Holding Units at the Klickitat Hatchery, are the required numbers of 20,000 ft<sup>3</sup> ponds and 5,000 ft<sup>3</sup> raceways that will be used to hold adults. The spring chinook adults require two ponds and the steelhead adults require one raceway.

TABLE II-6  
RECOMMENDED ADULT HOLDING UNITS  
AT KLICKITAT HATCHERY<sup>(1)</sup>

<u>Facility</u>	<u>20,000 ft<sup>3</sup> Asphalt Pond</u>	<u>5,000 ft<sup>3</sup> Raceways</u>
Spring Chinook .....	2	0
Steel head .....	0	1

<sup>(1)</sup> All adult holding facilities will be used for juvenile rearing.

(2) Incubation of Eggs and Alevins

The proposed strategy for incubation of eggs is to employ deep trough incubators (Senn, et al, 1984, pp. 89-93) for all salmon and IsoFlow buckets for steelhead. The incubation strategy will be to chill incubation water to slow the development rate of all salmon that are to be reared for more than 12 months. This strategy will match closely the emergence of fry from the naturally spawning population. Two-year smolt Klickitat River steelhead will be incubated as 12-month reared salmon using chilled incubation water.

All salmon incubation will include substrate. Table II-7, Incubation Criteria for the Klickitat Hatchery, provides a summary of incubation criteria. Incubation criteria include spawning, incubation as a percentage of survival, and development rates. Table II-8 is a summary of the number of incubation units required to meet the goals of the hatchery.

TABLE II-5  
RETURNING ADULT CRITERIA

	<u>Klickitat River Basin</u>	
	<u>Spring Chinook</u>	<u>Steelhead</u>
<u>Adult</u>		
Collection Sites .....	Falls Five/ WDF	Falls Five/ WDF
Holding Facility .....	Cascade Sp.	Cascade Sp.
Arrival Time (month/day)		
From .....	5/1	6/15
To .....	9/10	11/1
Male/Female Ratio .....	1.5:1	1:1
Male/Female Holding Ratio .....	1.5:1	1:1
Average Weight .....	15	8
% Pre-Spawn Survival .....	80	90
% Female Suitable for Spawning .....	100	90
% Female Collected for Spawning .....	80	80
% of Run Held at One Time .....	100	100
Flow as per FMC, 1984, pg. 69 <sup>(1)</sup> (gpm/adult) .....	1.0	0.5
Holding Space (ft <sup>3</sup> /adult) .....	10	2.5
<u>Spawning</u>		
Max. No. Females Spawed per Male .....	2	1
Spawning Period (month/day)		
From .....	8/15	1/15
To .....	9/20	4/1
Average No. Eggs/Female .....	3,600	3,750
Average No. Eggs/lb (eyed) .....	1,600	3,500
Number of Females Spawed to Meet Goals	980	118

(1) Compendium of Low-Cost Pacific Salmon and Steelhead Trout Production Facilities and Practices in the Pacific Northwest, U.S. Department of Energy, Bonneville Power Administration, Division of Fish and Wildlife, Senn, Harry; Mack, John; and Rothfus, Lloyd, Fish Management Consultants (FMC), 1984.

(2) 100 females to be used.

TABLE II-7

INCUBATION CRITERIA  
FOR THE YAKIMA AND KLICKITAT  
BASIN ENHANCEMENT FACILITIES

	<u>Klickitat River Basin</u>	
	<u>Spring Chinook</u>	<u>Steelhead</u>
<u>Spawning</u>		
Average No. Eggs/Female .....	4,300	4,500
Average No. Eggs/lb (eyed) .....	1,600	3,500
<u>Incubation</u> (Survival rates in %)		
From Fertilization to Eyed Stage .....	92	92
From Fertilization to First Feeding ...	90	90
Fertilization to Release (see Table 4)	65	60
<u>Development Rate</u>		
Days to First Feeding @ 52°F .....	83	32
Days to First Feeding @ 48°F .....	104	36
Days to First Feeding @ 39°F .....	186	N/A
Total Eggs Required for Program .....	4,200,000	433,000
Location of Incubation Station .....	Upper Cascade Spring	Upper Cascade Spring
Water flow/deep trough = 7 gpm to eye = 10 gpm after hatching		
Water flow/ISO bucket = 0.32 gpm		
Water temperature - See Table II-3		
Egg density in ISO bucket = 7,500 to eye and hatch		
Egg density/deep trough = up to 1,000,000 to eye; 180,000 coho and spring chinook and 152,000 fall chinook		

(1) Compendium of Low-Cost Pacific Salmon and Steelhead Trout Production Facilities and Practices in the Pacific Northwest, U.S. Department of Energy, Bonneville Power Administration, Division of Fish and Wildlife, Senn, Harry; Mack, John; and Rothfus, Lloyd, Fish Management Consultants (FMC), 1984.

TABLE II-8  
 RECOMMENDED MINIMUM INCUBATION UNITS  
 FOR THE KLICKITAT HATCHERY<sup>(1)</sup>

<u>Facility</u>	<u>Deep Trough</u>	<u>IsoFlow Buckets</u>
Klickitat (Cascade Springs)	22	52

(1) The incubation of steelhead eggs should be isolated until certification is complete or until eggs are eyed.

(3) Rearing of Juveniles

The flow and density indexes are the most important design criteria for design of rearing vessels and are described in Table II-9, Rearing Criteria for the Klickitat Hatchery. Also summarized in this table are some of the early rearing criteria for feeding and projected growth rates.

TABLE II-9  
 REARING CRITERIA FOR THE KLICKITAT HATCHERY

	<u>Klickitat River Basin</u>	
	<u>Spring Chinook</u>	<u>Steelhead</u>
<u>Rearing</u>		
First 30 Days of Feeding .....	97	97
First 100 Days of Feeding .....	93	93
First Feeding until Smolt .....	72	72
% Survival from Fertilization to Release .....	65	65
<u>Growth</u>		
MTU/inch of length .....	30	32
(MTU = Monthly Temperature Units)		
<u>Release</u>		
<u>Time of Smolt Release</u>		
From .....	4/1	4/20
To .....	5/1	5/10
Size at Release as Smolts (fish/lb) ...	15	7
Location of Rearing Station .....	Upper Cascade Springs	Upper Cascade Springs

Note: Release sites to be determined.

Figures II-1 and II-2 present the description of rearing vessel utilization with time and species. These figures show that year-round use of the raceways will be the normal practice for both steelhead and spring chinook and that adult space sharing must be integrated into the timing of raceway use.

(a) Water Flow Index

Flow rates for individual rearing vessels will be designed according to the following formula for raceway and pond loadings:

$$\text{lbs of fish/gpm} = \frac{(4)(\text{available oxygen, ppm})}{\% \text{ food fed}}$$

The peak flow requirement for the 5,000 ft<sup>3</sup> raceways is 1.5 cfs and for the 20,000 ft<sup>3</sup> ponds is 3.0 cfs.

or

$$Q \text{ gpm/lb} = \frac{(\% \text{ food fed})}{(4)(\text{available oxygen, ppm})}$$

Note: available oxygen = influent concentration - effluent concentration

(b) Rearing Density Index

Rearing densities use the following formula which is applied to the appropriate rearing vessel. The results of these calculations are shown in Table II-10, Required Rearing Units for the Klickitat Hatchery, which shows 42 raceways and three ponds required for the program goals.

$$\text{Density lb/ft}^3 = (0.175 \text{ raceways})(\text{fish length, inches})$$

Densities in the ponds will be according to the following formula:

$$\begin{aligned} \text{Density lb/ft}^3 &= (0.150 \text{ hatchery ponds})(\text{fish length inches}) \\ \text{Density lb/ft}^3 &= (0.11 \text{ acclimation ponds}) \end{aligned}$$

TABLE II-10

REQUIRED REARING UNITS FOR  
THE KLICKITAT HATCHERY

	5,000 ft <sup>3</sup> Raceways (ea)	20,000 ft <sup>3</sup> Ponds (ea)
Klickitat (Cascade Springs)	42(1)	3

(1) This allows for two spare raceways at peak usage. The peak raceway usage is in mid-April.

(c) Food Conversion and Amount of Food

The estimated food conversions and total food requirements are presented in the calculations supplied by Fish Management Consultants. These estimates are contained in Appendix A and summarized in Table II-11, Monthly Food Requirements at the Klickitat Hatchery. The total annual food requirement for the Klickitat Hatchery is 337,000 pounds.

TABLE II-11

MONTHLY FOOD REQUIREMENTS  
AT THE KLICKITAT HATCHERY

<u>Period Ending Date</u>	<u>Lbs. Food Required by Species</u>		<u>Total Lbs. Food Required</u>
	<u>Spring Chinook</u>	<u>Steelhead</u>	
01/29/90	14,112	2,436	16,547
02/28/90	21,718	3,670	25,388
03/30/90	42,924	10,325	53,249
04/30/90	34,144	12,375	46,520
05/30/90	7,421	2,783	10,204
06/30/90	10,626	3,329	13,955
07/30/90	14,486	3,782	18,268
08/29/90	17,357	4,239	21,596
09/29/90	21,883	4,903	26,786
10/29/90	42,830	8,737	51,566
11/29/90	28,036	5,306	33,342
12/29/90	16,281	2,924	19,205
			<u>336,626</u>

(d) Growth Rates

Growth in inches per fish is calculated using the Monthly Temperature Units (MTU) available. MTUs are determined from the mean temperature (F) for the month minus 32F, e.g., if July averages 52°F then July has 20 MTU or 52°F - 32°F. If 40 MTUs is the requirement to obtain an inch of growth then it will take 2 months at 52. Each species' MTUs and growth are documented in Table II-9, Rearing Criteria for the Klickitat Hatchery.

c. Transportation and Release

Smolts will be programmed to volitionally exit from their last culture facility to a nearby stream.

Because of outplanting goals, extensive transportation will be required in the Klickitat Basin. Table II-12 shows the transportation requirements for truck hauled fish in the Klickitat River Basin.

TABLE II-12  
 TRUCK HAULING FISH TRANSPORTATION SCHEDULE  
 IN TRUCK DAYS IN THE KLICKITAT RIVER BASIN  
 (Truck Day = 8 Hours of Time)

<u>Month</u>	<u>Spring Chinook</u>		<u>Steelhead</u>		<u>Total</u>
	<u>Adult</u>	<u>Smolt<sup>(1)</sup></u>	<u>Adult</u>	<u>Smolt<sup>(1)</sup></u>	
Jan.					
Feb.		0			
Mar.		13			16
April		14			17
May	10				10
June	15		(2)		15
July	15		(2)		15
Aug.	15		(2)		15
Sept.	5		2		7
Oct.			4		4
Nov.			4		4
Dec.					
					<u>103</u>

(1) This assumes 27 study groups of spring chinook and six study groups of steelhead are transferred to acclimation sites - and two trips/truck day.

(2) Haul with spring chinook in the second compartment.

The Klickitat River Basin will require 103 truck days.

d. Personnel/Housing

The Klickitat Hatchery will require approximately 106 staff months for operation as presented in detail in Table II-13. The requirements include specialized training and, at other times, some overlapping of tasks such as truck driving that will be accomplished by the fish culturists.


TABLE II-13  
 SUGGESTED STAFF LEVEL IN STAFF MONTHS  
 AT THE KLICKITAT HATCHERY<sup>(1)</sup>  
 (In Staff Months)

	<u>Manager</u>	<u>Asst. Manager</u>	<u>Culturist</u>	<u>Temp.</u>	<u>Truck Driver</u>	<u>Pathologist</u>	<u>Total</u>
Klickitat	12	12	60	10		12	106

<sup>(1)</sup> Assumes contracting all mechanical repair; major hatchery repairs; does not include main office assistance, experimental design assistance in fish identification and is based on levels similar to WDW and WDF.


Security at the Klickitat Hatchery was the basis of reasoning for the number of houses that are planned to be built. Four, 1,500-square-foot houses are required at the Klickitat Hatchery. This will include the construction of one duplex for capital cost savings. Each house will have finished basements for seasonal employee housing space.

**FIGURE II-1**  
**KLICKITAT FISH HATCHERY**  
 SHOWING REARING VESSELS USED FOR  
 ADULT AND JUVENILE STEELHEAD



**FIGURE II-2**  
**KLICKITAT FISH HATCHERY**  
 SHOWING REARING VESSELS USED FOR  
 SPRING CHINOOK

RL85X11



SECTION III  
Klickitat Facility Design

1. GENERAL DESCRIPTION OF SITE

a. Vicinity Location

The site for the Klickitat Hatchery is known as Upper Cascade Springs. It is located approximately three-quarters of a mile upstream from Cascade Springs along the Klickitat River (River Mile 40.8, refer to Figure III-1, Vicinity Plan). The site is located on a stable river bar composed of sand, gravel, and large boulders formed by a meander of the Klickitat River. The bench is approximately 20 feet higher than the normal river water elevation. The bench is estimated to be several hundred years old based on the presence of old growth Douglas fir and ponderosa pine.

b. Alternative Sites

The following alternative sites were considered for some form of facility development, ranging from a centralized station with acclimation sites through the Klickitat Basin to a divided station with a portion of the rearing capacity located at several different rearing ponds and acclimation sites. (See Master Plan for the Klickitat Station--KCM, 1988; FMC, 1989.) The alternative sites are:

White Creek Site  
Summit Creek Site  
Klickitat WDF Station, Cooperative  
Wonder Springs Site  
Indian Ford Springs Site

The multiple site approach to the Klickitat Hatchery was discounted primarily for difficulty of winter operation and the capital costs associated with the development of the facility. The Upper Cascade Springs site was selected considering pipeline costs, spring diversions, access roads, bridges, and site grading and operations. (A Site Investigation Letter Report is included in Appendix B.)

c. Facility Size

The Klickitat Hatchery will cover much of the proposed site. The bench where the hatchery will be located is the largest piece of land for approximately 10 river miles up and downstream that could adequately accommodate the hatchery. The bench containing the facility is about 150 feet wide and 1,500 feet long. The overall development area is approximately 5 acres. The Cascade Springs intake is 3,000 feet from the hatchery, the river intake is 300 feet from the hatchery, and Kidder Springs is 500 feet from the hatchery.

d. Production Goals Review

As shown in Table II-1, the Klickitat Hatchery will produce 2,700,000 spring chinook smolts and 270,000 steelhead smolts for release into the Klickitat River Basin. The spring chinook will be divided into 130 experimental study groups. The steelhead will be divided into eight experimental study groups. The spring chinook will be grown from hatching time in January to release in April of the same year. With a 2-year growth cycle, the steelhead will hatch in January-February with release in May of the following year.

e. Current Land Use and Ownership

Current ownership of the hatchery site varies among three entities. The bench of land that the hatchery buildings, rearing ponds, and the Kidder Springs diversion will be located on is owned by the Plumb Creek Timber Company. The road and right-of-way along and accessing the site is owned by Champion Timber International. The site where Cascade Springs is to be diverted is owned by the Yakima Indian Nation. All three areas are considered to be timber lands. Coordination with the U.S. Forest Service must be provided through the design phase, as this section of the Klickitat River is planned to be incorporated into a wild and scenic river designation. Easements and purchase of appropriate lands will occur through a coordinated effort among the Bonneville Land Acquisition Office, design team, landowners, and the Yakima Tribe.

2. SITE DEVELOPMENT

a. Access Roads

Access road requirements will include access to the spring intakes and access to the hatchery site. The planned facility is approximately four miles up the valley. This road is maintained by the Champion Timber International Company and will require special use agreements between the Tribe and Champion. The access road will be used consistently by logging trucks and equipment at all hours of the day during the year, depending on the severity of the winter. The facility designer must consider safety and traffic ramifications and how the Klickitat Hatchery can share this road with other users. Please refer to Figure III-2, Site Plan.

The road bisects the planned facility, with the residences on the east side and the hatchery facility on the west side. A design feature is a vehicle and pedestrian underpass. Using a large arch culvert, the hatchery complex can be accessed from the residences without crossing over Champion Road. The arch culvert will allow free passage by hatchery personnel and families to and from the residences and the hatchery, and unrestricted movement of road traffic by the timber company. Champion Road, adjacent to the hatchery site, will be paved with an asphalt pavement for dust and drainage control. The design wheel loads for this section of asphalt pavement will be

adequate to withstand loads in excess of HS20. All roadway designs will conform to Champion Timber International Co. specifications.

Cable cars, identical to the cable trams employed by the U.S. Geological Survey, will provide access to the two spring intakes. The terminals for these cable trams will be set above the road far enough to prevent interference with oversize logging equipment traffic. This will also provide year-round foot access to the spring intakes.

b. Drainage and Snow Removal

Site grading will be designed for maximum drainage efficiency during the spring snow melt. Hatchery grounds will be covered with a top coarse of 3/4-inch minus crushed rock, and the access road will be asphalt concrete paved with proper crown and ditching to control water runoff. The stormwater ditches will be directed toward a detention pond dedicated for stormwater only, with discharge into the Klickitat River. The detention pond must be sized by the designer to conform with Klickitat County stormwater code. The pedestrian and vehicle underpass will be designed to prevent significant snow and water accumulation.

Snow removal will be performed using a pickup-mounted blade to push the snow into proper areas for storage and melting. Designated areas will be provided for winter storage of built-up snow away from the roads and parking areas. Curbs and catch basins must be given special consideration for snow removal strategies.

c. Construction Clearing and Grubbing

The proposed site for the Klickitat Station is presently timbered with old growth Douglas fir, ponderosa pine, and oak. To build the hatchery, timber must be removed. Heavy logging equipment will need to be used to harvest selected trees. Grubbing of other areas to remove topsoil and overburden shall follow with conventional heavy equipment.

Some additional site work must be initiated at the time of clearing. This includes fill work and slope protection of the riverward slopes of the site. This phase of construction will overlap the clearing, site preparation, and finish site work phases of construction.

d. Site Work and Slope Protection

Site work includes several tasks including site grading for drainage and stormwater control, provision for parking areas, provision for the access road and pedestrian underpass, fill of the south edge of the site for the pollution abatement ponds and the hatchery discharge, excavation for the pipelines, river crossings, building foundations, and raceways and rearing ponds. In addition to the site grading and excavation for pipelines, site work will include the filling and slope revetment of the riverbank along the

southern downstream end and along the upstream end of the site. The approximate quantity of this fill and revetment will be 12,000 total cubic yards of material. The fill and revetment, composed of heavy, loose riprap and light, loose riprap found locally, will need to be placed along the outward and downstream portion of the site. Revetment of large riprap will need to be placed along the upstream face of the site for protection from high flow events. The areas of fill and riprap are shown on the attached site plan. Please refer to Figure III-3, Hatchery Site Plan.

e. Wetlands

The facility designers will be required to mitigate for lost wetland habitat so that there is no net loss of wetland habitat due to the hatchery construction. This will be accomplished by reseeding native grasses, willows, and thules along the revetted slopes and by actively designing bays and groins into the slopes to increase the surface area and wetland areas to equal preconstruction levels. Upstream of the adult fish weir and in the hatchery discharge channel, creating slow moving meanders and weirs will provide for pools and marshy areas. During the final design phase, the engineer must meet with the Washington State Department of Ecology, the Klickitat County Shoreline Protection Group, Yakima Indian Nation, and a landscape architect/wetland specialist familiar with the construction of wetlands commonly found in the Klickitat basin to design a net increase of wetland habitat at the site.

f. Flood Analysis

A flood analysis was carried out for the Klickitat River around the proposed hatchery location at River Mile 40.8. Approximately 69 years of water flow records are available from the USGS gaging station "Number 14110000 Klickitat River, Near Glenwood" (located at River Mile 51) that was used as the gage of record.

Attached in Appendix C is an analysis of the flood flows and associated calculations of flood elevations. The approximate proposed elevation of the finished site is above elevation 1175.0 feet MSL at the upstream end of the site and above 1168.0 feet MSL at the downstream end of the site. The flood elevations that result from the 100-year flood event, plus a factor of safety of approximately four times this flow, display elevations 10 feet higher than the original water surface at normal flows. These flood flow elevations are approximately 1172.0 feet MSL at the upstream end of the site and 1163.0 feet MSL at the downstream end of the site, carrying the existing river gradient along the riverbed at about 0.7% or 0.007 foot/foot.

The flood flow elevations are based on a standard hydrologic method of statistical analysis and provide a rough envelope of elevations to prevent important structures or facilities from being sited below mean elevation. From this elevation and above, flood events of 100-year duration should not occur. Calculations for the Flood Flow Elevations can be found in Appendix C.

g. Power Supply

Electrical power for the Klickitat Hatchery will be installed from a distance of approximately 1.0 to 1.5 miles, with new overhead power cables and treated wood support poles. See Figure III-4, New Electric Supply Route. The preferred location for the starting point for the new power supply line is at the existing WDF Klickitat Station. A new, single line upgrade installed along the existing route from the Glenwood-Goldendale Road to the existing WDF hatchery is anticipated. From this point to the Upper Cascade site is a distance of about 1.5 miles and new power line right-of-way will have to be cleared and wood support poles installed. The new route would lead from the WDF rearing ponds, across the Klickitat River to the existing Wonder Springs access road, and then along this road and the Champion Timber International Co. logging road to the hatchery site. The facility will require the new construction of a 7,200-volt, 3-phase, 4-wire primary power line from the existing WDF station. The Klickitat County Public Utility District office that will be in charge of service for this line will be the White Salmon office, telephone No. 1-800-548-8358, contact engineer, Bill Hamm.

The sequence of work for the construction of the new power supply will begin with the clearing of a power line right-of-way approximately 30 feet wide. The PUD prefers that the power lines travel along existing roads for ease of maintenance. From the west side of the Klickitat River and adjacent to the existing WDF hatchery, the power lines will cross the river with two poles and a system of deadends for support. The new right-of-way will need clearing on the east side of the river near the existing Wonder Spring intake system. This portion of the route is along an existing primitive road and will require limited widening. The proposed power line route then turns south along the existing Champion Timber International Co. logging road. Along this section of the route, pole setbacks must be considered for off-road logging truck and logging equipment traffic. The route terminates at the hatchery in a new transformer that will step the power down to usable voltages. The proposed transformer is preliminarily sized to be a 7,200-volt/480-volt, 300 kVA, 3-phase unit.

3. WATER SUPPLY

A U.S. Bureau of Reclamation report (USBR, 1990) contains information on the condition of water sources that are planned to be developed for water supply. This information is identical to the data presented in the following section. However, because of separate contract requirements, this Preliminary Design Report will outline the required water characteristics necessary for a successful fish culture program at the hatchery.

a. Water Requirements

Water for the Klickitat Hatchery will come from three sources. Used separately, no one source is of adequate quantity or quality to provide the entire supply demand for the hatchery year-round. The three sources are: Cascade Spring, Kidder Spring, and the Klickitat River.

### (1) Quality

Water quality is the single most important water characteristic that determines the success of hatchery-produced fish. The water quality along the Klickitat River and its tributaries is exceptionally high quality. The basin itself is classified as a Double A River in the Washington State Water Quality Standards For Surface Waters and will be an excellent source for the Klickitat Hatchery.

The required minimum standards for the successful culturing of salmonids is presented in Table III-1. This table compares the three sources of water supply proposed for the hatchery with established ADF&G water quality standards. Alaska Department of Fish & Game (ADF&G) Standards for Salmonid Aquaculture are commonly used in siting hatcheries. All sources of water supply meet or surpass the minimum requirements for water quality in terms of chemical constituency except those noted. Several constituents must be tested in additional sampling efforts before appropriate measures can be taken during design. The constituents above maximum standards include carbon dioxide, chlorine, hydrogen sulfide, iron, oils, and zinc.

The Klickitat River experiences a very high concentration of glacial silt and fine mud during the summer months when glaciers melt in the river's headwaters. During this phenomenon, the hatchery will use significantly less river water and shift water supply toward the springs. USBR raw water data are contained in Appendix D. See Figure III-5, Klickitat River Basin Enhancement Facility Flow Rates vs. Month.

### (2) Quantity

Water quantity from the three proposed sources has been measured by various people throughout the course of the hatchery feasibility study. The summaries of the measured flows are presented below in Table III-2 for the two spring water sources only. The river water source flow rates are assumed to be as presented in the USBR report to be published in 1990. The summer 7-day, 10-year low flow rate and the winter 7-day, 10-year low flow rate were not available from the USBR at the time of printing. The lowest recorded flow rate is 236 cfs during the month of November.

The flows of Cascade and Kidder springs were measured twice during the preliminary design investigations. Dye injection flow analysis was used to measure the water flow rate at both springs. The method included an assessment of the flow rate in August 1988 and a dye injection flow analysis in spring. The accuracy of the methodology is a function of adequate dye mixing in the subject water flow. The mixing of dye in Kidder Spring was rated at fair to good and the mixing in Cascade Spring was excellent. Together with the educated guess, the flow results from the dye injection were consistent. The first measurement was on April 3, 1989 and the second measurement was on August 22, 1989.

TABLE III-1  
 QUALITY OF WATER SOURCES  
 FOR THE KLICKITAT ENHANCEMENT FACILITY  
 COMPARED WITH ALASKA DEPARTMENT OF FISH AND GAME (ADF&G 1983)  
 WATER QUALITY STANDARDS FOR SALMONID AQUACULTURE

<u>Water Qualities</u>	<u>Salmonid Aquaculture Standards (ADF&amp;G 1983)</u>	<u>Klickitat River at WDF Hatchery 6/21/89</u>	<u>Cascade Spring Klickitat River River Mile 40 6/20/89</u>	<u>Kidder Spring Klickitat River River Mile 41 6/20/89</u>	<u>Water Supply Exceeds Standard</u>
Alkalinity .....	Undetermined		.38 mg/l	36 mg/l	
Aluminum .....	0.01 mg/l		0.010 mg/l	0.15 mg/l	
Ammonia (un-ionized) ..	0.0125 mg/l	0.00009 mg/l	0.00011 mg/l	0.0003 mg/l	
Arsenic .....	0.05 mg/l	0.005 mg/l	0.005 mg/l	0.005 mg/l	
Barium .....	5.0 mg/l	0.005 mg/l	0.005 mg/l	0.005 mg/l	
Cadmium .....	0.0005 mg/l ( 100 mg/l alk.) 0.005 ( 100 mg/l alk.)	0.0005 mg/l	0.0005 mg/l	0.005 mg/l	
Calcium Hardness .....	mg/l	21 mg/l	28 mg/l	27 mg/l	
Carbon Dioxide .....	1.0 mg/l		1.8 mg/l	6.7 mg/l	x
Chloride .....	4.0 mg/l	0.4 mg/l	0.4 mg/l	0.4 mg/l	
Chlorine .....	0.003 mg/l		0.01 mg/l	0.01 mg/l	x
Chromium .....	0.03 mg/l	0.002 mg/l	0.002 mg/l	0.002 mg/l	
Copper .....	0.006 mg/l ( 100 mg/l alk.) 0.03 mg/l ( 100 mg/l alk.)	0.005 mg/l	0.005 mg/l	0.005 mg/l	
Dissolved Oxygen .....	7.0 mg/l	10.6 mg/l	11.9 mg/l	11.8 mg/l	
Fluorine .....	0.5 mg/l	0.10 mg/l	0.10 mg/l	0.10 mg/l	
Hydrogen Sulfide .....	0.003 mg/l		0.01 mg/l	0.01 mg/l	x
Iron .....	0.1 mg/l	0.13 mg/l	0.010 mg/l	0.04 mg/l	x
Lead .....	0.02 mg/l	0.002 mg/l	0.002 mg/l	0.002 mg/l	
Magnesium .....	15 mg/l	2.1 mg/l	3.3 mg/l	3.2 mg/l	
Manganese .....	0.01 mg/l	0.010 mg/l	0.005 mg/l	0.005 mg/l	
Mercury .....	0.0002 mg/l	0.0002 mg/l	0.0002 mg/l	0.0002 mg/l	
Nickel .....	0.01 mg/l	0.010 mg/l	0.010 mg/l	0.010 mg/l	
Nitrate (NO <sub>3</sub> ) .....	1.0 mg/l	combined 0.1 mg/l	combined 0.2 mg/l	combined 0.1 mg/l	
Nitrite (NO <sub>2</sub> ) .....	0.1 mg/l	combined 0.1 mg/l	combined 0.2 mg/l	combined 0.1 mg/l	
Nitrogen (N <sub>2</sub> ) .....	110% Total Gas Pressure ( 103% nitrogen gas)		100%	100%	
Oxygen .....	90% Saturation	100%	101.9%	100.9%	
Petroleum (oil) .....	0.001 mg/l		1.0 mg/l	1.0 mg/l	x
pH .....	6.5 - 8.0	7.32	7.62	7.03	
Potassium .....	5.0 mg/l	1.17 mg/l	1.96 mg/l	1.96 mg/l	
Salinity .....	5.0 Parts per 1,000				
Selenium .....	0.01 mg/l	0.010 mg/l	0.010 mg/l	0.101 mg/l	
Silver .....	0.003 mg/l	0.002 mg/l	0.002 mg/l	0.002 mg/l	
Zinc .....	0.005 mg/l	0.010 mg/l	0.01 mg/l	0.010 mg/l	x
Sodium .....	75.0 mg/l	2.99 mg/l	3.68 mg/l	3.68 mg/l	
Sulfate (SO <sub>4</sub> <sup>-2</sup> ) .....	50.0 mg/l	2.4 mg/l	0.4 mg/l	0.5 mg/l	
Temperature .....	0° - 15°C	13.4°C, 56.1°F	7.3°C, 45.1°F	7.3°C, 45.1°F	
Total Dissolved Solids	400.0 mg/l	56 mg/l	75 mg/l	73 mg/l	
Total Settleable Solids	80.0 mg/l (25 JTU)				

The results are as follows:

TABLE III-2  
KLUCKITAT HATCHERY  
SPRING WATER FLOWS

	<u>April 3, 1989</u>	<u>August 22, 1989</u>	<u>Average</u>
Cascade Spring	24 cfs	21 cfs	22.5 cfs
Kidder Spring	17 cfs	13 cfs	15 cfs

Sufficient information concerning flow quantity from both springs has been gathered to date. The above information is a conservative figure to base the preliminary design upon. The true quantity of water that is actually delivered to the facility will not be known until the spring intakes are constructed, and in-place and functioning. Both springs are constant in flow rates as measured 5 months apart. The combined peak flow required from the springs is 21 cfs. Please refer to Figure III-5 to review the hatchery water demand requirements for a one-year cycle.

### (3) Temperature

Generally, the temperatures are stable for the two spring sources. However, there is a slight variation in temperature, which is critical for the fish programming at this hatchery. The cool temperatures can be used in a positive fashion for temperature modulation during the incubation phases. If there is a difference in the temperatures between what was measured and what is actually delivered to the hatchery in the future, fine-tuning adjustments must be made for fish protection. Figure III-6 shows the dates and temperatures for the three water sources for the Klickitat Hatchery.

The Klickitat River varies in temperature over a range of about 20°F through the year. The hatchery fish programming considers this variation and will use all three water sources in concert to provide the desired water quality and temperature for various species and lifestages. (See Figure III-5, Water Flow Rates vs. Month.)

#### b. River Water Development

The river water supply will be the only water supply system at the Klickitat Hatchery that will require pumping. The reason for pumping is founded on economics and environmental impacts. Construction of a pipeline that will provide gravity-supplied water to the hatchery is not cost-effective based on our evaluations.

The gradient along the stretch of the Klickitat River in front and above the proposed site is approximately 0.7 foot of rise per 100 feet of run. The total river water system head requirements will be approximately 20 feet. Therefore, the pipeline will be approximately 3,000 to 3,500 feet in length. The route the pipeline would take is along the river's edge. Construction would be difficult because of the water and the very large boulders present in this canyon. The environmental impacts associated with a pipeline route along the river's edge would be high. The route would require a 30-foot right-of-way and room to cast the large boulders aside. Blasting of some of the boulders would be required. The estimated cost to construct a pipeline of approximately 30 inches in diameter along a route on the river edge would be roughly \$200/foot of length in-place, and would total approximately \$700,000. This concept was compared with a riverside pumping station and shortened delivery pipe. Construction of a pump station and delivery pipe will be more economical.

The suggested water supply alternative is to construct a pumped river intake approximately 300 feet upstream from the hatchery site and along the riverbank adjacent to a deep pool. A natural pool is created by a hydraulic control just above the hatchery site. The intake will require a cast-in-place concrete intake with trash rack, screen, and pump footing structure to be built next to the river and into the bank next to the existing logging road. Four vertical turbine pumps, each capable of delivering 10 cfs running simultaneously will be set under cover of a small building on top of a concrete slab. The design flow capacity from this pump station will be 40 cfs; however, only 30 cfs is required for the hatchery at any one time. Providing four pumps allows for one pump to sit idle as a redundant pump. This assures that the hatchery river water supply will be maintained in the event that one pump fails. Screens and trash rack assembly structures will help keep floating debris and animals out of the intake. The river water will flow by gravity through the trash rack and screen and into the pump sump where water will be pulled from the river and delivered to the sedimentation structure at the hatchery. The river intake system will require a pipeline of approximately 400 feet in length and 30 inches in diameter.

The screens at the river intake will be designed for the safe bypass of fish fry and smolts. The screen mesh size will be a maximum of 3/16 inch across the largest opening. In addition to the maximum mesh requirements, the screen area will have to be sufficiently large to create a maximum through screen velocity of 0.2 fps.

The trash rack and screen at the river intake will be accessible by the existing logging road and will be covered with a small metal building to keep snow and falling debris out. However, the screens will be susceptible to frazzle ice that floats in the river or forms at the screen. To keep the screen from plugging with ice, 45°F spring water will be delivered to the river intake screen during the winter. The spring water is warm enough to keep ice from forming on the screen and trash rack and support structure. Spring water flow will be controlled by valves and a nozzle system at the discretion of the hatchery manager. The river intake building will be a

secured and locked facility. The estimated cost of the pump station and the pipeline is approximately \$300,000 and provides substantial capital savings compared to the gravity pipeline alternative.

c. River Sedimentation Reservoir

The Klickitat River experiences a heavy load of rock flour and mud from the snow and ice melt of the glaciers. This silt will be carried into the pump station and must not be transported into the hatchery water system. The velocities in the pump station will be held to a minimum, yet some material will be carried into the pumps. The silt which is pumped into the delivery pipe will be removed in the sedimentation reservoir between the pipeline and the station reservoir.

The sedimentation reservoir will be a concrete structure designed for silt and sand settling. The design of this reservoir will allow for the characteristic settling velocities of the material and will be sized to a capacity of 40 cfs. The settled material will be either flushed back to the river or removed by vacuum pumps to a solid waste disposal site. The water surface elevation of the sedimentation reservoir will allow for gravity flow of the river water out and into the station reservoir. Gas stabilization of the river water will not be necessary.

d. Spring Water Development

Developing spring water supplies will be the most difficult construction aspect of the entire project. Both Cascade and Kidder springs are located on the west side of the river opposite the site. Both springs will be developed using a similar method. Cascade Spring will be the most sensitive to environmental impact from the standpoint of its visibility to the public that travel along the private logging road. Both springs will require special attention by the designer, contractor, and construction inspectors to maintain aesthetics.

Cascade Spring will be diverted from a point above a rock bench that is not visible from the logging road. The elevation of this point of diversion is approximately 1210.0 feet MSL datum. The intake system that will be employed at this location will be a concrete structure with an inclined plane screen with a bypass. Please see Figures III-2, 3, and 7. The structure will straddle the creek, in which water from the spring will flow over the top of the inclined plane screen and fall through the mesh to the basin below. The debris carried onto the screen will be spilled over the spillway and transported down the creek toward the Klickitat River. The basin water surface elevation will be set at the head required to drive the gravity supply of the Cascade Spring water down the hill, across the Klickitat River, and up along the logging road to the station. The screen diversion will be covered to keep animals and falling debris out. The diverted water will flow through a butterfly valve located on the downstream side of the diversion and at the top end of the delivery pipeline. Adjacent to this valve will be a spillway

at the end of the screen that will allow extra water to be diverted past the intake and over the falls. See Figure III-8, Cascade Spring Intake Profile View.

The ability to divert excess water will be critical for the Cascade Spring intake because of the high aesthetic value of the Cascade Spring Falls. The intake design flow will be set at 25 cfs. There will be some leakage. For aesthetic reasons, the falls must remain intact. The water right permit process, which is conducted during design, will address this requirement and the exact quantities of water that can be diverted and when.

The delivery pipeline will be an above-ground pipeline originating at the intake structure. It will proceed down the hill to the river's edge on the right bank. This will minimize impact to the hillside, as this is mostly solid bedrock. Extensive blasting would be needed to bury the pipeline. The pipeline will be supported by concrete plinths at certain intervals down the hill depending on the pipeline material and the size. It is anticipated that the pipeline will be approximately 24 inches in diameter; however, the final size will be determined when the diversion is constructed and operating. At the base of the hill and adjacent to the river's edge, the pipeline will plunge into the riverbed below. An architectural thrust block will restrain the pipe from forces exerted on it by the moving water. At this point, the pipeline will be buried underneath the Klickitat River, below the level of the riverbed, and will remain buried until termination at the hatchery reservoir. The trench will cross the river perpendicular to the stream lines and then turn upstream at the embankment of the existing logging road. The construction of this trench will entail special scheduling for protection of aquatic species during sensitive times and river diversion of water around construction. The required permit to perform the work will be granted through a Hydraulic Project Permit with the Departments of Fisheries and Wildlife. See Section VI-3.

The architectural thrust block will be designed to act as a concrete dead weight on the pipe. Attention will be given to blending the concrete and pipe into the surrounding terrain. Colored concrete and texture of tree branches will help to accomplish this. If possible, the thrust block will be buried out of sight. Individual trees will be marked for removal in the final design phase, and strict penalties will be levied for damage or removal of other trees by the construction company. The pipeline will be painted to match the surroundings or will be black in color. Repair to the construction scar will include planting of native trees and bushes. There will be no net loss of wildlife or wetland habitat allowed. These aspects of construction will require extensive construction inspection to assure their compliance.

The access to the springs will be by use of an aerial tram identical to the type employed by the U.S. Geological Survey stream gaging hydrologists. The cable car tram is supported by wire rope and two support towers on opposite sides of the river. The car is accessed by a ladder and the car is pulled across the cable by hand to the opposite tower. At Cascade Springs there will

be timber stairs built up to the intake structure. The cleaning of the spring screens will need daily attention during certain months of the year and no attention during others.

The spring diversion for the Kidder Spring intake will be identical to the Cascade Spring intake. Special care will be taken as well to protect this spring. The pipeline will be above ground down to the river at which point it will be below grade until it reaches the hatchery.

e. Station Reservoir and Gas Stabilization

Spring water quality is exceptionally good in all regards except the total gas pressures and dissolved gas concentration of nitrogen. This can cause stress and gas bubble disease in juvenile salmon and steelhead. The level of nitrogen and argon gas saturation for Cascade Springs was measured once by the U.S. Bureau of Reclamation on June 20, 1989, and was measured to be at 100.0%. The level of nitrogen and argon gas saturation for Kidder Springs was measured once by the U.S. Bureau of Reclamation on June 20, 1989, and was 100.0%, also. These levels of saturation are below the critical level for fish culture of 102.0% maximum; however, the measurements were a one-time sample and the design of the spring source water supply system will include gas stabilization. Spring water supply pipelines will empty into the station reservoir by falling through 6-foot-high packed columns. The packed columns will be open atmosphere type. This precaution will provide protection from some supersaturation that may occur.

The packed columns will empty into the station reservoir. A constant elevation will be maintained that is sufficient to drive the entire system's hydraulics. The hatchery reservoir will be constructed of reinforced concrete and will be covered by a shed roof to keep snow and debris from disrupting the flow and entering the system. Butterfly valves will control flow into the reservoir from Cascade and Kidder springs. The Klickitat River water will flow into the reservoir over a weir. Water supply to the hatchery will be controlled by butterfly valves and then into the distribution system of pipes that will deliver water to the raceways, hatchery building, and the ponds.

f. Water Chillers

Spring water will be circulated for incubation supply. Water chillers will be used to modify the temperature of the recirculating incubation water system from a constant 45° to the goal of 38°.

The water chillers will be modular, 120-volt, 1-hp electric type units as manufactured by Frigid Units of Toledo, Ohio or equals. These modular units will be plugged into a receptacle and will have switches to turn them on and off. The system will consist of four units with a recirculation ratio of 90 parts recirculated water and 10 parts new water. The required temperature requirements are outlined for all lifestages in Table II-3 and will be further reviewed during the final design.

g. Planting Truck Fill Station

A very important aspect of the Klickitat Hatchery is the outplanting of the majority of the smolt production away from the station. This outplanting task will be done using planting trucks specifically equipped to transport fish. The trucks carry water and fish in large, baffled, compartmented trucks. The trucks will be filled at the planting truck fill station, which will be supplied by gravity-fed water from the station reservoir. This fill station will include a concrete pad and an 8-inch-diameter pipe riser and flexible hose used to direct the water into the tankers. Control of this riser will be done using a butterfly valve set below the frost depth.

4. FISH PRODUCTION FACILITIES

Table III-3 lists the fish production components and their size as related to the Klickitat Hatchery.

a. Adult Collection

Adult collection will occur at several locations throughout the basin. Falls Five Fishway, the Klickitat Hatchery, the WDF Klickitat Station, and the Castile Falls Fishway sites are discussed in this report. It is assumed that the adult collection facilities are a separate construction project to be coordinated by BPA, and therefore no design or cost discussions are included.

The Falls Five Fishway is an existing fishway that has an adult trap that has fallen into disrepair. This trap will be repaired and modified as required to trap adult spring chinook and steelhead and for subsequent transport back to the Klickitat Hatchery for extended holding. The cost to repair and modify this trap is not included in the cost estimate, Section V-1., and will be addressed in an adult passage report that will be prepared by the USBR.

Another potential site for adult collection is the Klickitat Hatchery. The preliminary design calls for a fish rack to stop adults from entering the hatchery discharge; however, the design will allow for the future incorporation of an adult trap into the hatchery discharge if the plan for collection allocations of adults should change. There are no plans for the construction of adult trapping facilities at the Klickitat Hatchery.

The other potential sites for adult collection are the WDF Klickitat Station and the Castile Falls Fishway, both upriver from the proposed hatchery. The WDF Klickitat site does not require any modification for trapping as a trap already exists; however, there is a problem with collection of hatchery stock adults rather than target F2 generation adults and mixing of WDF stocks. Plans for modifying the Castile Falls Fishway are in progress.

**TABLE III-3**  
**SUMMARY OF FISH PRODUCTION FACILITIES**  
**AT THE**  
**KLICKITAT RIVER BASIN ENHANCEMENT FACILITY**

<b>Location:</b>	<b>Klickitat River</b>
<b>Species:</b>	<b>Spring Chinook and Steelhead</b>
<b><u>ADULT HOLDING</u></b>	
<b>Size:</b>	<b>15 lb Spring Chinook 8 lb Steelhead</b>
<b>No. of Adult Fish On Hand:</b>	<b>2,000 Spring Chinook 500 Steelhead</b>
<b>No. of Ponds:</b>	<b>2 Spring Chinook</b>
<b>No. of Raceways:</b>	<b>1 Steelhead</b>
<b>Size of Pond:</b>	<b>150 x 45 x 6 feet</b>
<b>Volume:</b>	<b>20,000 cubic feet</b>
<b>Construction:</b>	<b>Gravel with concrete inlets and outlets</b>
<b>Design Flow:</b>	<b>3.0-cfs Ponds 1.0-cfs Raceways</b>
<b>Flow Index:</b>	<b>1.0 GPM/Adult Spring Chinook 0.5 GPM/Adult Steelhead</b>
<b>Density Index:</b>	<b>10 cubic feet/Adult Spring Chinook 2.5 cubic feet/Adult Steelhead</b>

INCUBATION

Egg Capacity:	4,200,000 Spring Chinook 433,000 Steelhead
Incubator Type:	Deep Trough IsoFlow Buckets Stacked Tray Cabinets
No. Eggs/Bucket:	7,500 to eye
No. Eggs/Tray:	5,000 to hatch
No. Eggs/Deep Trough:	180,000 to hatch 1,000,000 to eye
No. Cabinet Stacks (16 tray):	4
No. Deep Troughs:	22
No. IsoFlow Buckets:	52
Chilled Water Temperature:	38F <sup>o</sup>
Deep Trough Flow:	10 gpm max.
IsoFlow Bucket Flow:	0.38 gpm
Total Chilled Water Flow:	150 gpm

REARING

Early Rearing Inside

No. Deep Troughs:	22
Size:	1'4" x 1'4" x 16'0"
Volume:	19 cu ft
Flow:	10 gpm max.
Total Flow:	220 gpm

Outdoor Rearing

No. Raceways:	32 Spring Chinook 10 Steelhead
Volume each:	5,000 cu ft
Volume total:	210,000 cu ft
Flow index:	_____
Density Index:	_____
Flow in each Raceway:	1.0 cfs
Total Flow:	42 cfs
Total Flow at Station:	51 cfs
No. Ponds:	3
Size of Pond:	150 ft x 45 ft x 6 ft
Volume:	20,000 cu ft
Construction:	Gravel with concrete inlets and outlets
Pond Design Flow:	3.0 cfs

b. Adult Holding

Adult holding of both spring chinook and steelhead will occur on-site. The spring chinook and steelhead will be held in both ponds and raceways, respectively. The spring chinook will be held from the time of capture, approximately May 1, until spawning in August in the gravel-lined pond with the spawning shed. See Table II-5 and Figure III-9. The pond will have fencing and partitioning to allow for sorting of adults during the ripening phase of the holding cycle and just prior to their spawning. The bottom of the ponds will be lined with an asphalt paver along the centerline and to the edge of the sloped bank for ease of access and crowding.

Adult steelhead will be held in the concrete raceways that are also used for rearing. These raceways will have no special adult design characteristics except that three raceways will have an up-welling type water supply in addition to the header type supply with jets. The up-welling supply will have its own control valve and will have a covered metal grate in the head end of the raceway. The raceways will have adult sorting tubes made of 10-inch-diameter pipe that can be directed between them. No spawning shed or other arrangements are planned for the raceways at this time. See Figure III-9, Raceway and Rearing Pond Plans and Elevations. Hypalon liners that can be removed and disinfected will be used to prevent adult abrasion on the concrete raceway walls.

c. Incubation and Early Rearing Building

The hatchery building will be constructed for the purpose of housing the incubation, early rearing, feed storage, general storage, office, laboratory, and mechanical/electrical control room. The building will be set on the site so that access to the built-in freezer and loading dock will be easily maneuvered by a 45-foot truck and trailer. The building will have 60 feet of buffer between it and other structures. There will be a drive-through feature so that access from the hatchery indoor rearing troughs to the ponds can be conducted by truck for fry ponding. See Figure III-10, Hatchery Building Plan and Elevations.

A description of the structural system and material selection will follow in Section IV. A listing of the rooms and their associated square footage is shown in Table III-4 following.

TABLE III-4  
HATCHERY BUILDING ROOM SQUARE FOOTAGE

<u>Room</u>	<u>Dimension</u>	<u>Square Feet</u>
Hatchery Building - Total	54 x 100	5,400
Office	25 x 25	625
Laboratory	12 x 25	300
Restroom	10 x 8	80
Mechanical/Electrical	12 x 25	300
Hatchery	50 x 50	2,500
Walk-in-Freezer	25 x 25	625
Storage	9 x 15	135
Generator Room	9 x 10	90
Shop and Garage	16 x 25	400
Loading Dock Covered Area	16 x 50	800
Halls and Wall Space		335

The hatchery building is set between the steelhead rearing raceways and the spring chinook raceways to retard the transmission of disease between the two groups of fish, as there will be year-round rearing of steelhead to age two. The steelhead raceways will be on the upstream side of the building while the spring chinook raceways will be on the downstream side of the building. Incubation will occur simultaneously; however, steelhead and spring chinook will be separated in timing and physically with IsoFlow buckets, movable drop curtains, equipment, and tools for handling fish. The troughs that will be used after incubation of spring chinook and for early rearing of steelhead will be disinfected and dried before transfer of species.

The office will be located in the southeast corner of the building to provide the best view to raceways, ponds and most of the facility except the steelhead raceways. During discussions with the design team it was decided that the gains in less disease transmission provided by the split facility arrangement would outweigh the loss of security visibility toward the steelhead raceways. The office will include for the manager, the assistant manager and the lunch room for the crew. The "hatchery personnel only" restroom will adjoin the office and will be the minimum size required by the building code. No public restrooms are planned for this hatchery.

The laboratory will be equipped with cabinetry and storage space for a microscope, sampling equipment, tissue and disease culture and analysis equipment and supplies. The lab will have the space for traveling pathologists to set up equipment and to conduct small-scale experiments and field pathology work.

The hatchery room will be the largest room of the building. It will house the deep trough incubators and the cabinet tray type incubators

that will be used for both species. This room will also be used for incubation and early rearing. Contained in this room will be storage space for nets and dip nets for use in the hatchery and yard. Boot washes will be located at all points of entry into this room for disinfection and disease control.

Two sets of personnel doors and overhead rolling doors will be located on the north and south sides of the building for trucks and personnel access. Lighting and window shading in this room will be controlled with switches and hand-operated blinds. Control of light during incubation and early lifestages is essential for fish health. Cool white fluorescent lights operated by delay start dimmers and incandescent lights that can be operated in the off season are included. The use of pull cord-type lights connected to reels in the form of drop lights will allow for lighting of a small area by an individual during egg picking or inspection without having to turn on the entire bank of lights.

The water supply to the hatchery room will be delivered through an overhead large-diameter pipe, which will act as a manifold to supply water to the cabinet incubators and to all the deep troughs. This manifold will be large enough in capacity to provide very low interference between each valve control and to points of demand so that one valve can be changed without the entire bank of valves having to be readjusted. Each deep trough will have a water supply for supplying the upper end of the trough for early rearing or non-isolation rearing and also for the supply of water to the IsoFlow buckets that will be placed directly into the trough for isolation incubation and hatching. The water supply will have a dual system that will provide chilled water as required for incubation water temperature modulation. This will be supplied in a separate pipe system and delivered to the incubators with proper mixing before application.

The chilled water will be circulated through a recirculation system that will return water to the incubators at the desired temperature. The recirculation system and chillers will be a self-contained system. Four chillers, as discussed in Section III-3.f., will provide enough chilled water to incubate the desired number of eggs. The return water will flow by gravity back to a sump where the chillers will cool this and the 10% makeup water. A continual-operation circulation pump will recirculate water back to the incubators via the chilled water delivery pipes.

d. Rearing

Early rearing will occur indoors for all species. The early rearing will be accomplished in deep troughs. Hatching of eggs will occur in both cabinet type incubators and IsoFlow buckets at which shortly thereafter the alevins will be transferred to the deep troughs and early rearing can begin. Each deep trough will have its own set of buckets, baskets, baffles, and screens for water control. Table II-7 describes the time and size fry that will be ponded to the outdoor raceways or ponds.

Extended rearing of fingerlings to smolts will be conducted outdoors in earthen ponds and concrete raceways. The concrete raceways will be constructed with overall dimensions of 10' x 110' x 6' high with a usable rearing volume of 5,000 cubic feet. The raceways will be constructed with 8-inch walls and will have an 8-inch-thick slab as the floor. Water stops will be used at all expansion and construction joints. Screen slots will be provided at the end location only, and two sets of screens of different mesh size will be manufactured for each raceway.

Water supply will be delivered via an 8-inch-diameter manifold that will straddle the head end of the raceway, and will be controlled by underground butterfly valves. Two sets of standpipe drains will allow for drainage and water level control of the raceway while fish production is in progress. One standpipe will flow directly to the sedimentation pond as wastewater, which will be used for raceway cleaning and the other standpipe will provide water level control and will direct continual raceway water to the hatchery discharge without treatment. Vacuum pumping systems will be able to discharge directly into this standpipe for daily pond cleaning. Occasionally, these standpipes can be pulled for final mop-up and cleaning of the raceway after fish are outplanted. All water supplies to the raceways will be first use water except those raceways that will be plumbed to receive second use and gravity water from the hatchery. Wood drainboards will provide access to clean river silt out of the raceways.

The earthen ponds will have a gravel-sloped side, with a slope of 3:1. An asphalt strip will run the full length of the pond, along its centerline, and will extend to the toe of the slope. Water will be supplied by a 12-inch-diameter manifold that will direct the flow parallel to the centerline of the pond. At the inlet and outlet ends of the pond, concrete slabs will provide erosion control. These slabs will provide locations to pump fish for outplanting work and during crowding operations. At the inlet end of the adult holding pond, a spawning shed will be constructed of treated wood and concrete to provide a spawning area for adult salmon. At the outlet of each pond, an array of screens and wood damboards for fish and water level control will be constructed. There will be six drains in each pond, three for flow-through rearing water directed back to the river, and three directed to the sedimentation ponds for use during cleaning operations.

e. Marking

There will be an extensive fish marking program at the Klickitat Hatchery. Special consideration must be given to this aspect of the hatchery and appropriate facilities will be provided for marking, temporary water supply, electric power, and return water and fish piping. The hatchery site will have a concrete pad located adjacent to the raceways to park a mobile tagging trailer. The concrete pad will provide a footing where the tagging trailer can accept water through a 4-inch-diameter supply hose with quick disconnects. 240-volt outdoor electrical power will be provided. The concrete pad will be elevated sufficiently to provide enough head to return the fish back into the raceways by gravity using a pipeline or flexible hose.

## 5. FACILITY BUILDINGS

### a. Hatchery Building

The hatchery building will have several features in addition to fish production facilities. The exterior will be a prefabricated metal-shelled pole building with a wood-frame support structure. Treated timber columns will support wood trusses, roof purlins, and wall girts. The roof will be a standing seam roof with 4-foot eaves and gable overhangs for snow protection. No gutters will be attached because of ice buildup. The roof pitch will be 6 in 12 to provide for snow accumulation and removal. The color of the facility will be prescribed by the client.

The building will have windows that are metal clad Thermopane, with 3/8-inch dead space thickness between the glass. The personnel doors will be metal insulated solid-type doors. The rollup doors will be metal and insulated. Insulated wall and roof panels will be Robertson, Formawall foam sandwich type or equal.

### b. Fish Food Freezer

The fish food freezer will be a built-in, walk-in type freezer with a self-contained compressor unit. The freezer's capacity will allow for 100,000 pounds of Oregon Moist pellets stacked on pallets. The freezer will have a floor strong enough to support a forklift. Outside of the freezer will be a thawing and scale area for weighing and proportioning rations. A rollup door will provide access to this room from the loading dock.

### c. Mechanical and Electrical Room

The mechanical and electrical room will be shared. The generator system will be placed in the northeast corner of the building. This room will contain the domestic water system hydropneumatic pressure tank, the building heating system for the office and lab, the pump motor control centers, the electric power supply panel, and the automatic switching panel for emergency power start-up of the generator. There will be some limited storage in this room. The generator will also be located in this room. An additional mechanical room will be adjacent to the storage room and will have additional HVAC and electrical panels as required.

### d. General Storage

The general storage room for the hatchery will be located centrally for easy access. This storage space will be dedicated for the indoor items that need seasonal or intermittent use. Outside door access will not be provided.

e. Shop and Garage

The shop and garage, approximately 400 square feet, are located on the north side of the hatchery building. Two overhead rollup doors will provide access and a personnel door will open into the general storage room. The shop will be equipped with light tools and hand tools required for routine maintenance of hatchery equipment and grounds. There will be a table saw and drill press located in the shop. Space is provided for two full size pickup trucks. Lighting in this room will be provided by cool white fluorescent tubes. Diesel and gasoline fuel storage tanks will be located adjacent to the garage. A 1,000 gallon diesel and 500 gallon gasoline tank will be provided. Special anti-leak tank lining and containment construction will be specified.

f. Hatchery Housing

Residences at the Klickitat Hatchery include three single-family homes and a duplex. The houses will be located adjacent to the Champion Timber International Co. logging road. The houses are approximately 1,500 to 1,800 square feet in size with finished daylight basements for temporary housing apartments. The duplex will be a modification and extension of one of the single-family plans. The homes are situated so that the hatchery manager's home would be the closest to the hatchery building in case of an emergency. Insulation would be as specified by the BPA "Good Cents" program and wood stoves will be provided as backup heat. The primary source of heat will be fuel oil, centralized forced air heat. Each house will have its own fuel oil storage tank and a separate electric meter. Views from the houses will be directed at the hatchery site. Access roads and driveways will be set back from the logging road approximately 50 feet. A frontage road will allow for travel into the underpass without traveling on the logging road. Furniture is not included in the cost estimate; however, the houses will be equipped with carpeting, cabinetry, and drapes.

6. WATER EFFLUENT TREATMENT

a. Hatchery Effluent and NPDES Pollution Abatement Ponds

The Klickitat Hatchery will require a National Pollution Discharge Elimination System permit to operate. The lead agency for this permit is the Washington Department of Ecology. This permit will include Best Management Practices that govern hatchery operations with regards to the fish culture process and minimizing the facility's pollution impacts.

Hatchery effluent, because of its quality, will not require sedimentation treatment. However, on a daily basis the raceways will be vacuum cleaned of ash waste products, waste food, and river silt. Vacuumed and other waste from the raceways and ponds will be removed and directed down the separate waste drain toward the sedimentation ponds for treatment.

The sedimentation ponds will be lined with native gravels and sands of the site and will be a square- or rectangular-shaped pond of about 25' x 25' x 2' deep and will have an inlet that will direct flow across the entire cross-section of the pond. Likewise, the outlet will have a skimmer weir that will pull an even flow from all points of the pond. The design detention time required for fish waste constituents is approximately 5 hours. In the proposed pond, the calculated detention time will be approximately 24 hours, providing a factor of safety of 5. There will be two identical ponds with this capacity so that one can be rested, dried, and cleaned while the other pond is being used for the waste stream.

b. Waste Cleaning System

The waste cleaning system will be a system of pipes that will carry waste toward the sedimentation ponds from all connected rearing and hatchery drains. The pipes will be designed to carry the waste at a minimum velocity of 2.5 fps. The system will terminate at the raceways as a "waste stand-pipe." The waste drain will also be placed to carry waste from the hatchery at various points in the building. The large earthen rearing ponds will also have waste drains for the annual cleaning of these ponds after the rearing season.

In addition to the drain pipes that will carry waste to the ponds, there will be two electric vacuum pumps that will be supplied with a pool-type attachment for vacuuming waste from off the bottom of the raceways. The electric pumps, which will handle solids, will be rated at 30 gpm with 20 feet of water pressure head.

c. Disease and Chemical Control

The Best Management Practices outlined in the NPDES permit will describe how treatment of some of the disease will be carried out. Formalin is a technique that will commonly be used for the treatment of fungus. Effluent containing formalin will be sent down the waste drain and directed toward the sedimentation ponds. Iodine solutions, erythromycin, and formalin will be the three chemicals most commonly used at this hatchery.

7. FACILITY EQUIPMENT

a. Equipment List

A list of equipment is included in the operation and maintenance cost estimate. This equipment is necessary for the normal operation and maintenance of the Klickitat Hatchery. See Appendix E.

## 8. OPERATION AND MAINTENANCE

### a. Hatchery Monitoring and Control System

A control and monitoring system is designed for the hatchery. The system is operated by an IBM-compatible central computer which monitors various phases of the hatchery operation that are deemed important. It also controls emergency alarms and records their frequency.

The control panels for the pumps and heating system will be located in the hatchery office. The automatic switch and generator controls will be located in the mechanical and electrical room. The central computer, which will monitor all these controls, will be located in the hatchery office.

### b. Alarm System

The alarm system will include alarms and an automatic telephone dialer that will automatically dial personnel in the event an alarm is triggered. The alarm system will be designed to work in concert with the monitoring and control system central computer by placement of various alarm sensors strategically in the hatchery system.

The following locations will have water level sensors for the detection of low water levels:

- Hatchery water reservoir
- Each outside raceway
- Each outside rearing pond

The following locations will have flow sensors for the detection of low water flow in the pipe or open channel;

- River water supply pipe
- Kidder Spring water supply pipe
- Cascade Spring water supply pipe

All sensors will communicate with the central computer for alarm firing and recording. Alarms will consist of an audible siren. The alarm will be located away from the computer screen. The automatic telephone dialer will call the residences and up to a total of eight phone numbers in a preset sequence. Acknowledgment of the call must occur before the dialer quits calling.

In addition to the water alarms there will be fire, smoke, and electrical failure alarms all tied into the monitoring and control central computer. This system will have a dedicated emergency backup battery power supply.

c. Data Management

(1) Monitoring Sensors

The monitoring system will be set to monitor dissolved oxygen and waste product levels at any point in the water supply system. This monitoring system will also log and monitor the pump station's electric motors and will provide a record of their run time for maintenance purposes.


(2) Central Computer

The central computer will be used only for the monitoring, alarm, and recording tasks of the hatchery. It cannot be used for special projects. Separate computers will need to be installed for special projects. The central computer will be located in the manager's office. It will provide the manager with immediate information on where alarm sensors might have been activated in alarm actions, and it will give the manager the record of any sensor that has been recording the water temperature or dissolved oxygen content over the past few months or years.

d. Fuel Consumption


Fuel consumption will consist of fuel oil for heating the hatchery building and the residences, diesel fuel for the trucks and generator, and gasoline for the other hatchery vehicles. The estimated annual fuel consumptions for the Klickitat Station are estimated to be:

Fuel Oil	2,000 gallons
Gasoline	5,000 gallons




**FIGURE III-1**  
**BONNEVILLE POWER ADMINISTRATION**  
**KLICKITAT SALMON AND STEELHEAD**  
**HATCHERY**

**VICINITY MAP**




SITE PLAN  
NO SCALE

USGS DATUM MSL = CL. 0.0




COPYRIGHT 1982, R.W. BECK AND ASSOCIATES, AL. STATE 88000400

NO.	BY	DATE	DESCRIPTION	REV.	BY	DATE	DESCRIPTION	<b>R.W. BECK</b> AND ASSOCIATES	BIRMINGHAM POWER ASSOCIATION KUKITAT SALMON AND STEELHEAD HATCHERY SITE PLAN	11/11 82-11102-1-111-01 11/11/82 Fig. 11-2



**HATCHERY SITE PLAN**  
SCALE 1"=60'



USGS DATUM MSL - EL. 0.0

COPYRIGHT 1988 R.W. BECK AND ASSOCIATES. ALL RIGHTS RESERVED.


REV.	DATE	BY	CHKD.	APPROVED	DESCRIPTION

DATE	BY	CHKD.	APPROVED

**R.W. BECK**  
AND ASSOCIATES

BOHEMILLE POND ADMINISTRATION  
Klickitat SALMON AND STEELHEAD HATCHERY  
HATCHERY SITE PLAN


DATE: 08-11-88  
BY: R.W. BECK  
CHKD.:  
APPROVED:  
Fig III-5



**FIGURE III-4**  
**BONNEVILLE POWER ADMINISTRATION**  
**Klickitat Salmon and Steelhead**  
**HATCHERY**  
**NEW ELECTRIC POWER**  
**SUPPLY ROUTE**

# KLICKITAT RIVER HATCHERY


## WATER FLOW RATES vs. MONTH



R.W. BECK  
AND ASSOCIATES


FIGURE III-5

# WATER TEMPERATURES vs. MONTH Klickitat River, Cascade and Kidder Springs



R.W. BECK  
AND ASSOCIATES

FIGURE III-6



**SCHEMATIC HYDRAULIC PROFILE**


SCALE: NONE

COPYRIGHT 1988, R.W. BECK AND ASSOCIATES, ALL RIGHTS RESERVED


REV.	DATE	BY	CHK'D	APPROVAL	DESCRIPTION




BOISEVILLE POWER ADMINISTRATION  
 KLICKITAT SALMON AND STEELHEAD HATCHERY  
 SCHEMATIC HYDRAULIC PROFILE




CASCADE SPRING INTAKE  
**PROFILE VIEW**  
 NO SCALE




REARING RACEWAY PLAN



20,000 FT<sup>3</sup>  
REARING POND PLAN




SECTION Q-Q




RACEWAY SECTION

COPYRIGHT 1988, R.W. BECK AND ASSOCIATES. ALL RIGHTS RESERVED.


REV.	DATE	BY	CHKD.	APP'D.	<p><b>R.W. BECK</b> AND ASSOCIATES</p>	<p>GENERAL POND CONSTRUCTION KLICKITAT SALMON AND STEELHEAD HATCHERY RACEWAY AND REARING POND PLANS AND SECTIONS</p>	<p>DATE 10-10-88 FIG. NO. III-9</p>



NORTH ELEVATION




SOUTH ELEVATION



PLAN



EAST ELEVATION



COPYRIGHT 1988, R.W. BECK AND ASSOCIATES. ALL RIGHTS RESERVED.

REV.	DATE	BY	CHK'D	APPROVALS	DESCRIPTION

**R.W. BECK**  
AND ASSOCIATES

JOHN WALKER FISHBUSH ARCHITECTS BUILT FOR  
KLUCKITAT SALMON AND STEELHEAD HATCHERY  
HATCHERY BUILDING  
PLAN AND ELEVATIONS

NO. 10  
Fig. III-10

SECTION IV  
FACILITY ENGINEERING

1. STRUCTURAL DESIGN

The Building Codes that will be referenced during the design of the **Klickitat** hatchery are;

Uniform Building Code, **1988**  
Uniform Plumbing Code, **1988**  
Uniform Fire Code, **1988**  
American National Standards Institute, **ANSI 1982**  
American Standards for Testing Materials, **ASTM**  
American Concrete Institute, **ACI 318-83**  
American Timber Institute  
Structural **Welding** Code, **AWS D1.1-84**  
**Klickitat** County, Local Codes  
Occupational Safety and Health Administration, **OSHA**

a. Load Criteria

The following load criteria will be used to govern the design of the station:

(1) Snow

ANSI **A58.1-82**  
Ground snow load: **135 psf**  
Occupancy Importance Factor: **1.0** (low occupancy)  
Roof snow load: **110 psf** or as governed by  
**Klickitat** County

(2) Wind

Base wind velocity: **70** mph or as required by the local  
building authorities.  
Exposure: C (open territory)  
Occupancy  
Importance Factor: **1.0** (low occupancy)

(3) Seismic

Seismic Zone **2B**  
Occupancy Importance Factor: **1.0**  
Per **UBC 1988**

(4) Soil

Active Pressure: To be **determined**  
 Passive Pressure: To be **determined**  
**Coefficient of Friction: 0.25**  
 Surcharge due to **HS20** wheel loads: 100 **psf**  
 Allowable soil bearing pressure: 2,000 **psf**

(5) Floor Loads

All floor areas: 100 **psf**

b. Structural Systems and Materials

The hatchery **building will** be constructed **with** a concrete slab on grade. The incubation and rearing room floor **will** be covered by an agricultural-style pole **building with** treated timber columns. Adjacent office and lab areas **will** use a slab on grade floor and sheet rock **partition** walls and ceiling system. The exterior walls and roof **will** be a **painted** galvanized steel skin. The roof system **will** be a **standing** seam-type roof to prevent leakage. No gutters **will** be installed along the roof edges to **avoid** breakage by ice. The wall panels **will** be an insulated sandwich-type panel **with** a metal **covering** on the interior and exterior surfaces. The **approximate size** of the **building will** be 54 x 100 feet. There **will** be a 25 x 25-foot bay for the access and **receiving** dock for **fish** food transfer into the freezer area. The roof system of the bay area will consist of treated wood pole columns and wood trusses.

## 2. CIVIL/MECHANICAL DESIGN

a. Codes and Standards

The applicable codes that **will** be considered during design are:

Uniform **Plumbing** Code, 1988  
 Uniform Fire Code, 1988  
 Uniform Mechanical Code, 1988

b. Piping Materials

The **piping materials** used for the design of the **Klickitat** Hatchery **will** be specifically selected for **suitability** in the culture of fish. No **material will** be **specified** that **will** be in contact with process water that contains yellow metals such as brass or bronze. PVC and HOPE pipe will be **specified** where **possible**.

c. Valves and Material

Valves and joining materials will be chosen specifically for fish culture compatibility. **No** yellow metals or copper will be specified for use in the process water system. Internal parts will be specified as cast iron, stainless steel, or rubberized cast iron.

d. Manholes and Catch Basins

Manholes and catch basins will be specified as precast concrete type, standard **4-foot-diameter** sewer appurtenances.

e. Heating, Ventilation and Air Conditioning

The rearing and incubation room of the hatchery building will be heated with eight **10,000 BTU/hr** space heaters with **individual** thermostats. The design indoor incubation room temperature shall be set at **45°F year-round**. The office and laboratory will be heated with a forced air oil, or forced air **electric** furnace system. The office and lab space **will** be heated to an indoor **design** temperature of **72°F**. The outside design temperature shall be assumed at **-10°F**.

f. Insulation

Insulation of the hatchery building will be contained in the insulated wall and roof panels. Other select areas that will require more insulation will utilize rigid **batts**. The walls in the office and lab that are adjacent to the incubation room will require a glass blanket-type wall insulation that will be installed into a rigid sheetrock partition. Walls and roof insulation shall be minimum **R:30** rated for the office and lab spaces.

Special consideration shall be given to vapor and draft control throughout the hatchery building. The interior partition walls will be vapor sealed and will have waterproof sheet rock for water damage protection. The exterior walls will be sheathed with the metal surface on the interior of the panel and will act as a self-contained water vapor barrier. The interior walls between the hatchery room and the office and laboratory will have a special polyethylene vapor barrier to prevent the transfer of moisture into the office.

g. Domestic Water Supply

The domestic water supply system will be supplied with untreated spring water. The water will be circulated by a booster pump to a **hydro-pneumatic** tank which **will** provide a constant pressure and deliver a constant flow to the residences and the hatchery **building**. The water demand design flow to the residences will be **40 gpm** each and to the hatchery building will be **40 gpm**. The residual pressure at a **40-gpm** flow rate at the tap will be set at **40 psi**.

#### h. Fire Protection Supply

A **fire** protection system will be designed to be supplied with **800 gpm** of water from the **station reservoir** at all times. The system will include an electric booster pump with a separate **fire protection** system of pipe to **distribute** water to the **residences** and the hatchery building. **Fire** fighting hose reels will be located at strategic points throughout the hatchery site. The **electric** booster pump will be automatically switched on in the event of a **fire** alarm being activated. The fire **fighting electrical** system **will** be backed up by the diesel generator on the **essential circuit** of the hatchery **electrical** system. The **residual** pressure at the hose reels will be set at **40 psi** with a **combined** fire flow rate of **800 gpm** at any **two** hose reels.

#### i. Domestic Sewage Treatment

The domestic sewage at the **Klickitat** station will be generated at the hatchery building as well as the residences. The system **will** be based on a pressurized sewage system **commonly** known as a septic tank effluent pumping (STEP) system. The system is composed of **individual** septic tanks located at each residence, two at the duplex and one at the hatchery **building**, a pressurized **comminuting** effluent pump, and system of small-diameter pipes that lead to a **common** soil absorption **field (drainfield)**. The **soil absorption** field will be located at the east end of the site adjacent to the **sedimentation** ponds.

### 3. ELECTRICAL DESIGN

#### a. Commercial Power Supply

**Commercial 3-** phase power **will** be required for the hatchery site. The large hatchery water supply pumps **will require 3-phase** power. The hatchery power supply will be **480-volt**. Large **motors** will be required for **equipment operation** at this site. The following table lists the power loads that are anticipated at the **Klickitat** Hatchery; Table IV-1 shows the estimated consumption of power for the **Klickitat** Hatchery and the **associated** large power motors and lights that are **consuming** the power. **This** list is an estimate of power demand during the design phase. The **facility** designer must be aware that this **list is** a partial list of what will probably be installed in the hatchery. The column labeled **Essential/Non** indicates if the electrical load listed **is supplied with** emergency power backup.

TABLE IV-1  
ELECTRICAL POWER DEMANDS

<u>Item</u>	<u>Quantity</u>	<u>Essential /Non</u>	<u>Power Demand Each/Total</u>
Pumps, 50 hp	4 ea	3 Ess	37.5 kW/150 kW
Pumps, 10 hp	2 ea	Ess	7.5 kW/15 kW
Hatchery Lights	60 ea	1/4 Ess	0.2 kW/12 kW
Hatchery Space Heaters	8 ea	1/4 Ess	10 kW/80 kW
Hatchery Forced Air Electric Heat	1 ea	1/4 Ess	20 kW/20 kW
Walk-in Freezer	1 ea	Ess	40 kW/40 kW
Shop Equip.	Misc.	Non	30 kW/30 kW
Outlets	60	1/4 Ess	0.05 kW/3 kW
Alarm System	1 ea	Ess	1 kW/1 kW
Residences	4 ea	Non	10 kW/40 kW
Yard Lighting	10 ea	1/4 Ess	2 kW/20 kW
Predator Control Fence	1 ea	Non	2 kW/2 kW
Total Power Demand			413 kW
Total Essential Power Demand			202 kW

b. Emergency Power Supply

Emergency power will be supplied by an **automatically** switched generator, dedicated to the hatchery and other **essential** power demands. The generator will be **equipped** with an **automatic** switch for immediate start **sequencing** during a power outage. **Essential equipment** such as water supply pumps, water heaters, alarms and **certain lights** will be on the essential side of the circuit. The **diesel** generator is **preliminarily** sized to be a **220-kW** unit and will have an extended tank of 1-day fuel capacity.

c. Power Distribution

Power **distribution** throughout the hatchery will be in underground **rigid plastic conduit** encased in sand filled trenches and marked with a metal detectable **plastic** tape. Power will be **supplied** overhead to the mechanical/**electrical** room, at which **point** the power is stepped down at a **720/480-volt, 300-kVA** transformer and distributed through the hatchery. The hatchery **building** will be supplied with **400** amperage service.

d. Lighting System

Incandescent and fluorescent **lights** will be specified in **certain** areas of the hatchery **building**. All fluorescent **lights will** be of a spectrum that is acceptable for fish culture (cool white). All hatchery **lighting** will be controlled with delay switches to reduce the light shock to the fish present indoors. Several separate banks of lights will be provided with individual **switches** for **versatility**. Drop light fixtures will be **strategical-ly** located in the **incubation** room for use with tasks during the incubation cycle that require limited light for working.

e. Pump and Large Load Power Supply

Pump and large load power supply **will** be provided with **3-phase 480-volt service**. The power **will** be **supplied** through burlled plastic **conduit** that will originate In the motor control centers In the hatchery building electrical room and lead to the point of demand at the pump or motor. Four **50-hp** pump motors will be located at the river water supply Intake. The walk-in freezer will also require a large power supply of **460** volts for operation of Its compressor.

f. Controls

Control **indicator** panels for the water supply pumps and other **equipment** will be **provided** and housed In the hatchery office. The motor control centers for these water supply pumps will be located in the **electrical** room. Some control of **lights**, heaters and certain other **electrical equipment** may be controlled through the control computer. (See Section **III-8.a.**)

g. Future Electrical Loads

Future electrical capacity and emergency backup **capacity** of electrical loads will be included in the final design. The **additional** capacity that **will** be allowed for is **20 kW** and is reflected In the size of the power supply system and the emergency power generator.

h. Residence Power

The **residential** power will be single-phase **240-volt**. Residence power will be supplied from the overhead power supply. through the transformer at the hatchery **building**, through a **meter** in that room and then **directly** to individual **200-ampere** service panels at the **residences**. The **residences** will not be **supplied** backup power In the event of an **electrical** power outage. Oil, wood, or propane sources of heat **must** be utilized If the **homes** are on the nonessential power circuit and, therefore, a wood **burning** stove Is specified for each **residence**. Standard lighting and electrical **equipment** and appliances **will** be installed in the houses.

i. Phone System

The hatchery **office** and each of the **residences** will be **equipped with** telephones. Six pairs of wires must be brought from **existing** telephone service lines to the hatchery site. The telephone system will be Installed on shared poles **with** the power supply system. The telephones **will** be wired underground in plastic **conduit** through the hatchery site to the houses from the hatchery building. The automatic **dialing** system of the control computer **will** be equipped to dial the residences or some other off **station** telephone number in the case of an emergency and alarm **sequencing**.

## SECTION V

### COST ESTIMATION AND IMPLEMENTATION SCHEDULE

#### 1. COSTS

The cost estimate that follows contains a **description** of each item as well as the unit costs for material and labor. The quantity and unit costs are **multiplied** to arrive at the total cost of the item. Contractor overhead and profit are included in the column titled "Amount." This column is added and subtotaled to **arrive** at the construction cost.

A **design** engineering and construction management fee of **18%** of the **construction** cost is added to the **construction** cost subtotal. A cost associated with the **administrative** and legal costs of **7%** of the construction costs is also added and another subtotal is summed. The total cost for construction of the Klickitat Hatchery, **including** five **acclimation** sites and fees for design and construction **engineering**, legal and administrative fees, is **\$9,040,000**.

The total cost of the project includes additional items beyond capital expenses required for final **design**, such as: floodplain computer modeling, **geotechnical** and **foundation** investigations, water quality continuing review, route surveying, and environmental **permitting**. The total cost does not include sales tax for the construction **materials**. It does not include the cost of **acclimation sites** that **will** likely be developed in the basin in the future and it does not include the costs to design and construct adult collection **facilities**.

The annual **capital** cost to produce one pound of combined salmon and steelhead can be calculated by dividing **\$9,040,000** by **180,000** pounds of annual production. The estimated annual cost to produce one pound of **fish** is **\$50.00**.

The operation and **maintenance** costs are **estimated** to be approximately **\$220,000** annually for the Klickitat Hatchery.

## 2. REQUIRED PERMITS

The permits that are **identified** as required for the Klickitat station are:

### Klickitat County:

**Building** Permit  
**Compliance** with County **Shoreline** Management Regulations; included by **definition** In the Environmental Assessment document  
 On-site Wastewater Discharge **Permit**

### Washington State:

Department of Ecology:  
 State Environmental Policy Act; in-place **within Environmental**  
 Assessment  
**Water Right Permit**  
 Flood Control Zone Permit  
 Water Quality Exception or Certification  
 National Pollution Discharge **Elimination** System, **NPDES**  
 Department of **Wildlife** and **Fisheries:**  
**Hydraulic** Project Approval  
 Department of Natural Resources:  
 Notification of work

### United States Corps of Engineers:

Section **10 Permit**  
 Section **404** Permit

### United States Forest Service:

**Notification** and Coordination

### United States Fish and **Wildlife** Service:

**Notification** and **Coordination**

### Yakima Indian Nation:

Water Use Permit  
 Stream Zone Alteration **Permit**  
 Zoning **Permit**  
**Conditional** Use Permit  
 Lease Agreement, **BIA**  
 Building **Permit**

### Champion **International** Timber:

Land Purchase Agreement  
 Road Use and Easement Agreement

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COSTOWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	ITEM	QUANTITY	UNIT	UNIT MATERIAL COST	UNIT LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	MOBILIZATION	1	LS		\$75,000.00		\$75,000.00	\$75,000.00
2	SCHEDULING	1	LS		\$1,000.00		\$1,000.00	\$1,000.00
3	CONSTRUCTION SURVEYING	1	LS		\$20,000.00		\$20,000.00	\$20,000.00
4	INSURANCE/BONDING	1	LS		\$50,000.00		\$50,000.00	\$50,000.00
5	CLEAN-UP AND DEMOBILIZE	1	LS		\$75,000.00		\$75,000.00	\$75,000.00
6	SITE WORK CLEARING AND GRUBBING	10	AC	\$1,000.00	\$3,000.00	\$10,000.00	\$30,000.00	\$40,000.00
7	ACCESS ROADWAY IMPROVEMENTS-ASPHALT	5000	SY	\$3.50	\$3.00	\$17,500.00	\$15,000.00	\$32,500.00
8	ACCESS ROADWAY IMPROVEMENTS-ARCH CULVERT	50	LF	\$300.00	\$350.00	\$15,000.00	\$17,500.00	\$32,500.00
9	ACCESS ROADWAY IMPROVEMENTS-SHOULDER WOR	600	LF	\$8.00	\$10.00	\$4,800.00	\$6,000.00	\$10,800.00
10	SITE ROADWAYS 25' WIDTH	2000	LF	\$8.00	\$10.00	\$16,000.00	\$20,000.00	\$36,000.00
11	SITE SURFACING	5000	SY	\$1.25	\$2.00	\$6,250.00	\$10,000.00	\$16,250.00
12	SITE GRADING	5	AC		\$5,000.00		\$25,000.00	\$25,000.00
13	SITE DRAINAGE, CULVERTS AND CATCH BASINS	250	LF	\$60.00	\$60.00	\$15,000.00	\$15,000.00	\$30,000.00
14	RIPRAP LIGHT LOOSE	18000	TON	\$6.00	\$2.00	\$108,000.00	\$36,000.00	\$144,000.00
15	RIPRAP HEAVY LOOSE	9000	TON	\$5.00	\$2.00	\$45,000.00	\$18,000.00	\$63,000.00
16	GEOTEXTILE	5000	SY	\$1.10	\$0.50	\$5,500.00	\$2,500.00	\$8,000.00
17	LANDSCAPING	5	AC	\$2,000.00	\$5,000.00	\$10,000.00	\$25,000.00	\$35,000.00
18	ELECTRIC POWER SUPPLY LINES	4	MI	\$20,000.00		\$80,000.00		\$80,000.00
19	SERVICE TRANSFORMER, 7.2 KV TO 480 V	1	EA	\$10,000.00		\$10,000.00		\$10,000.00
20	TELEPHONE SERVICE	4	MI	\$5,000.00		\$20,000.00		\$20,000.00
						\$363,050.00	\$441,000.00	\$804,050.00
SUBTOTAL								\$804,050
SUBTOTAL								\$804,050
SUBTOTAL								\$804,050
TOTAL								\$804,050

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COST

OWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	WATER SUPPLY AND DRAINS ITEM	QUANTITY	UNIT	UNIT MATERIAL COST	UNIT LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	CASCADE SPRINGS INTAKE, 20x10x5 CONCRETE	25	CY	\$100.00	\$250.00	\$2,500.00	\$6,250.00	\$8,750.00
2	SCREENS, MISC STEEL, LADDERS	1	LS	\$6,000.00	\$1,000.00	\$6,000.00	\$1,000.00	\$7,000.00
3	24" DIAMETER BUTTERFLY VALVE	1	LS	\$1,800.00	\$1,000.00	\$1,800.00	\$1,000.00	\$2,800.00
4	MISC FITTINGS	1	LS	\$8,000.00	\$2,000.00	\$8,000.00	\$2,000.00	\$10,000.00
5	24" HDPE PIPE TO RIVER W/PLINTHES	120	LF	\$85.00	\$75.00	\$10,200.00	\$9,000.00	\$19,200.00
6	ARCHITECTURAL THRUST BLOCK	10	CY	\$100.00	\$250.00	\$1,000.00	\$2,500.00	\$3,500.00
7	USGS AREIAL TRAM	1	LS	\$8,000.00	\$4,000.00	\$8,000.00	\$4,000.00	\$12,000.00
8	24" DUCTILE IRON PIPE RIVER CROSSING	100	LF	\$80.00	\$150.00	\$8,000.00	\$15,000.00	\$23,000.00
9	24" DIAMETER ISOLATION BF VALVE	2	LS	\$1,800.00	\$1,000.00	\$3,600.00	\$2,000.00	\$5,600.00
10	24" WATER SUPPLY PIPELINE TO STATION	4400	LF	\$75.00	\$80.00	\$330,000.00	\$352,000.00	\$682,000.00
11	KIDDER SPRINGS INTAKE, 20x10x5 CONCRETE	25	CY	\$100.00	\$250.00	\$2,500.00	\$6,250.00	\$8,750.00
12	SCREENS, MISC STEEL, LADDERS	1	LS	\$6,000.00	\$1,000.00	\$6,000.00	\$1,000.00	\$7,000.00
13	24" DIAMETER BUTTERFLY VALVE	2	LS	\$1,800.00	\$1,000.00	\$3,600.00	\$2,000.00	\$5,600.00
14	MISC FITTINGS	1	LS	\$8,000.00	\$2,000.00	\$8,000.00	\$2,000.00	\$10,000.00
15	24" HDPE PIPE TO RIVER W/PLINTHES	100	LF	\$85.00	\$75.00	\$8,500.00	\$7,500.00	\$16,000.00
16	ARCHITECTURAL THRUST BLOCK	10	CY	\$100.00	\$250.00	\$1,000.00	\$2,500.00	\$3,500.00
17	USGS AREIAL TRAM	1	LS	\$8,000.00	\$4,000.00	\$8,000.00	\$4,000.00	\$12,000.00
18	24" DUCTILE IRON PIPE RIVER CROSSING	240	LF	\$80.00	\$150.00	\$19,200.00	\$36,000.00	\$55,200.00
19	24" DIAMETER ISOLATION BF VALVE	1	LS	\$1,800.00	\$1,000.00	\$1,800.00	\$1,000.00	\$2,800.00
20	24" WATER SUPPLY PIPELINE TO STATION	200	LF	\$75.00	\$80.00	\$15,000.00	\$16,000.00	\$31,000.00
						\$452,700.00	\$473,000.00	\$925,700.00
						SUBTOTAL		\$925,700
						SUBTOTAL		\$925,700
						SUBTOTAL		\$925,700
						TOTAL		\$925,700

23-Jan-90

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COST

PAGE 3

OWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	ITEM	QUANTITY	UNIT	UNIT MATERIA COST	UNIT LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	KLICKITAT RIVER INTAKE, 30x15x20 CONCRET	90	CY	\$80.00	\$250.00	\$7,200.00	\$22,500.00	\$29,700.00
2	SCREENS, MISC STEEL	300	SF	\$150.00	\$50.00	\$45,000.00	\$15,000.00	\$60,000.00
3	10 CFS, 50 HP VERTICAL TURBINE PUMPS	4	EA	\$35,000.00	\$2,000.00	\$140,000.00	\$8,000.00	\$148,000.00
4	EXCAVATION	200	CY	\$7.00	\$10.00	\$1,400.00	\$2,000.00	\$3,400.00
5	24" MANIFOLD, W/FITTINGS	1	LS	\$40,000.00	\$10,000.00	\$40,000.00	\$10,000.00	\$50,000.00
6	24" BF VALVES	4	EA	\$1,800.00	\$1,000.00	\$7,200.00	\$4,000.00	\$11,200.00
7	MISC FITTINGS, REDUCERS	10	EA	\$1,500.00	\$1,000.00	\$15,000.00	\$10,000.00	\$25,000.00
8	METAL BUILDING COVER	450	SF	\$10.00	\$10.00	\$4,500.00	\$4,500.00	\$9,000.00
9	DE-ICING EQUIPMENT	1	LS	\$3,000.00	\$1,000.00	\$3,000.00	\$1,000.00	\$4,000.00
10	30" WATER SUPPLY PIPELINE TO STATION	400	LF	\$90.00	\$95.00	\$36,000.00	\$38,000.00	\$74,000.00
11	10" DE-ICING PIPELINE	400	LF	\$15.00	\$10.00	\$6,000.00	\$4,000.00	\$10,000.00
12	RIVER WATER SEDIMENTATION BASIN, 20x20x15	60	CY	\$100.00	\$200.00	\$6,000.00	\$12,000.00	\$18,000.00
13	MISC FITTINGS, 30"	4	EA	\$2,500.00	\$1,000.00	\$10,000.00	\$4,000.00	\$14,000.00
14	WATER SUPPLY RESERVOIR, 20x20x15	60	CY	\$100.00	\$200.00	\$6,000.00	\$12,000.00	\$18,000.00
15	RESERVOIR COVERS	4	EA	\$2,000.00	\$500.00	\$8,000.00	\$2,000.00	\$10,000.00
16	36" BF VALVES	1	EA	\$2,300.00	\$1,500.00	\$2,300.00	\$1,500.00	\$3,800.00
17	24" BF VALVES	2	EA	\$1,800.00	\$1,000.00	\$3,600.00	\$2,000.00	\$5,600.00
18	36" WATER SUPPLY PIPING	720	LF	\$100.00	\$120.00	\$72,000.00	\$86,400.00	\$158,400.00
19	24" WATER SUPPLY PIPING	650	LF	\$75.00	\$80.00	\$48,750.00	\$52,000.00	\$100,750.00
20	MISC FITTINGS	10	EA	\$1,500.00	\$100.00	\$15,000.00	\$1,000.00	\$16,000.00
						\$476,950.00	\$291,900.00	\$768,850.00
SUBTOTAL								\$768,850
SUBTOTAL								\$768,850
SUBTOTAL								\$768,850
TOTAL								\$768,850

23-Jan-90

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COST

PAGE 4

OWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	ITEM	QUANTITY	UNIT	UNIT MATERIAL COST	UNIT LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	12" BF VALVE W/SIDE ACTUATOR	42	EA	\$650.00	\$100.00	\$27,300.00	\$4,200.00	\$31,500.00
2	RACEWAY WATER SUPPLY RISER AND MANIFOLD	42	EA	\$500.00	\$500.00	\$21,000.00	\$21,000.00	\$42,000.00
3	HATCHERY BUILDING WATER SUPPLY 24", 12"	200	LF	\$75.00	\$80.00	\$15,000.00	\$16,000.00	\$31,000.00
4	HATCHERY INDOOR PIPING AND MANIFOLDS	1	LS	\$20,000.00	\$25,000.00	\$20,000.00	\$25,000.00	\$45,000.00
5	SEALED PACKED COLUMNS	4	EA	\$3,500.00	\$1,000.00	\$14,000.00	\$4,000.00	\$18,000.00
6	STATION RESERVOIR PIPING	4	EA	\$1,500.00	\$1,500.00	\$6,000.00	\$6,000.00	\$12,000.00
7	24" WASTE DRAIN	1350	LF	\$60.00	\$60.00	\$81,000.00	\$81,000.00	\$162,000.00
8	36" HATCHERY DRAIN	1450	LF	\$100.00	\$120.00	\$145,000.00	\$174,000.00	\$319,000.00
9	STANDPIPES, 12"	42	EA	\$50.00	\$25.00	\$2,100.00	\$1,050.00	\$3,150.00
10	STANDPIPES, 10"	42	EA	\$45.00	\$25.00	\$1,890.00	\$1,050.00	\$2,940.00
11	POND MANIFOLDS	3	EA	\$4,500.00	\$1,500.00	\$13,500.00	\$4,500.00	\$18,000.00
12	POND DRAINS, CORRUGATED METAL RISERS	3	EA	\$3,500.00	\$2,000.00	\$10,500.00	\$6,000.00	\$16,500.00
13	4' PRECAST MANHOLE	2	EA	\$2,000.00	\$1,000.00	\$4,000.00	\$2,000.00	\$6,000.00
14	SEDIMENTATION PONDS	600	CY	\$20.00	\$8.00	\$12,000.00	\$4,800.00	\$16,800.00
15	RACEWAYS, CONCRETE 110x10x6, 76 CY EA	42	EA	\$26,000.00	\$25,000.00	\$1,092,000.00	\$1,050,000.00	\$2,142,000.00
16	PONDS	3	EA	\$45,000.00	\$10,000.00	\$135,000.00	\$30,000.00	\$165,000.00
17	SCREENS	84	EA	\$3,000.00	\$250.00	\$252,000.00	\$21,000.00	\$273,000.00
18	WETLAND CONSTRUCTION	1	LS	\$5,000.00	\$2,000.00	\$5,000.00	\$2,000.00	\$7,000.00
19	DOMESTIC SEWAGE DISPOSAL SYSTEM	1	LS	\$41,000.00	\$2,000.00	\$41,000.00	\$2,000.00	\$43,000.00
20	DOMESTIC WATER SUPPLY SYSTEM	1	LS	\$35,000.00	\$5,000.00	\$35,000.00	\$5,000.00	\$40,000.00
						\$1,933,290.00	\$1,460,600.00	\$3,393,890.00
SUBTOTAL								\$3,393,890
SUBTOTAL								\$3,393,890
SUBTOTAL								\$3,393,890
TOTAL								\$3,393,890

23-Jan-90

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COST

PAGE 5

OWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	ITEM	QUANTITY	UNIT	UNIT MATERIAL COST	UNIT LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	HATCHERY BUILDING	5000	SF	\$18.00	\$15.00	\$90,000.00	\$75,000.00	\$165,000.00
2	WALK-IN FREEZER, WITHIN BUILDING	325	SF	\$20.00		\$6,500.00		\$6,500.00
3	LOADING DOCK	900	SF	\$5.00		\$4,500.00		\$4,500.00
4	LABORATORY SPECIAL CONSTRUCTION	325	SF	\$10.00		\$3,250.00		\$3,250.00
5	RECIRCULATION SYSTEM	1	LS	\$5,000.00	\$1,000.00	\$5,000.00	\$1,000.00	\$6,000.00
6	DEEP TROUGHS AND PLUMBING TO EACH	22	EA	\$1,600.00	\$800.00	\$35,200.00	\$17,600.00	\$52,800.00
7	CABINET INCUBATORS, 16 TRAY STACK	8	EA	\$1,300.00	\$200.00	\$10,400.00	\$1,600.00	\$12,000.00
8	BUILDING HEATING, SPACE HEATERS	8	EA	\$600.00	\$200.00	\$4,800.00	\$1,600.00	\$6,400.00
9	BUILDING HEATING, FORCED AIR FURNACE	1	LS	\$6,000.00	\$1,000.00	\$6,000.00	\$1,000.00	\$7,000.00
10	BUILDING ELECTRICITY	1	LS	\$20,000.00	\$10,000.00	\$20,000.00	\$10,000.00	\$30,000.00
11	BUILDING LIGHTING	1	LS	\$8,000.00	\$5,000.00	\$8,000.00	\$5,000.00	\$13,000.00
12	SITE ELECTRICAL	8	EA	\$500.00	\$200.00	\$4,000.00	\$1,600.00	\$5,600.00
13	SITE LIGHTING	8	EA	\$500.00	\$200.00	\$4,000.00	\$1,600.00	\$5,600.00
13	CONDUIT AND CONDUCTORS	1	LS	\$12,000.00	\$5,000.00	\$12,000.00	\$5,000.00	\$17,000.00
14	MOTOR CONTROL CENTERS	4	EA	\$5,000.00	\$1,200.00	\$20,000.00	\$4,800.00	\$24,800.00
15	CENTRAL ALARM SYSTEM AND COMPUTER	1	LS	\$40,000.00	\$20,000.00	\$40,000.00	\$20,000.00	\$60,000.00
16	BACKUP GENERATOR, 220 KW	220	KW	\$1,000.00	\$25.00	\$220,000.00	\$5,500.00	\$225,500.00
17	RESIDENCE POWER SUPPLY AND METERS	4	EA	\$1,500.00	\$1,000.00	\$6,000.00	\$4,000.00	\$10,000.00
18	RESIDENCES, 1500 SF, PREFAB OR STICK	4	EA	\$120,000.00	\$2,000.00	\$480,000.00	\$8,000.00	\$488,000.00
19	HATCHERY EQUIPMENT, TOOLS, FISH CULTURE	1	LS	\$200,000.00		\$200,000.00		\$200,000.00
20	1 TON FLATBED & 3/4 TON PICKUP, 4x4'S	2	EA	\$24,000.00		\$48,000.00		\$48,000.00
						\$1,223,650.00	\$161,700.00	\$1,385,350.00
SUBTOTAL								\$1,385,350
SUBTOTAL								\$1,385,350
SUBTOTAL								\$1,385,350
TOTAL								\$1,385,350

23-Jan-90

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COST

PAGE 6

OWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	ITEM	QUANTITY	UNIT	UNIT MATERIAL COST	UNIT LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	FIRE PROTECTION SYSTEM	1	LS	\$45,000.00	\$20,000.00	\$45,000.00	\$20,000.00	\$65,000.00
2								
3								
4								
5								
6								
7								
8								
9								
10								
11								
12								
13								
14								
15								
16								
17								
18								
19								
20								
						\$45,000.00	\$20,000.00	\$65,000.00
SUBTOTAL								\$65,000
SUBTOTAL								\$65,000
SUBTOTAL								\$65,000
TOTAL								\$65,000

23-Jan-90

ENGINEER'S ESTIMATE OF PROBABLE CONSTRUCTION COST  
PRELIMINARY DESIGN COST

PAGE 7

OWNER: BONNEVILLE POWER ADMINISTRATION  
PROJECT: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY

ITEM NO.	ITEM	QUANTITY	UNIT	UNITY MATERIAL COST	UNITY LABOR COST	MATERIAL COST	LABOR COST	AMOUNT
1	SUMMARY							
2	PAGE 1	1	EA	\$804,050.00		\$804,050.00		\$804,050.00
3	PAW 2	1	EA	\$925,700.00		\$925,700.00		\$925,700.00
4	PAGE 3	1	EA	\$768,850.00		\$768,850.00		\$768,850.00
5	PAGE 4	1	EA	\$3,393,890.00		\$3,393,890.00		\$3,393,890.00
6	PAGE 5	1	EA	\$1,385,350.00		\$1,385,350.00		\$1,385,350.00
7	PAGE 6	1	EA	\$65,000.00		\$65,000.00		\$65,000.00
8								
9								
10								
11								
12								
13								
14								
15								
16								
17								
18								
19								
20								
						\$7,342,840.00		\$7,342,840.00
CONTRACTOR OVERHEAD AND PROFIT INCLUDED						SUBTOTAL		\$7,342,840
DESIGN AND CONSTRUCTION ENGINEERING, ADMINISTRATIVE, AND LEGAL FEES, 25%						0.25		\$1,835,710
						SUBTOTAL		\$9,178,550
ADDITIONAL ENGINEERING REQUIREMENTS FOR FINAL DESIGN:								
NEC 2 FLOOD PLAIN MODELLING								\$135,000
GEOTECHNICAL AND FOUNDATION ENGINEERING								\$180,000
WATER QUALITY REVIEW AND ADDITIONAL INVESTIGATION								\$20,000
PIPELINE ROUTE SURVEYS								\$35,000
ENVIRONMENTAL PERMITTING								\$85,000
TOTAL								\$9,634,000

### 3. CONSTRUCTION STAGING

The cost to **build** and design the **Klickitat Station** will depend on the schedule of **construction** and whether the **construction** can be staged to any degree. The **Klickitat** Hatchery construction can be staged into two or three phases. The first stage would be to complete the site work and construct the **building**, raceways that would be required for year one **operation**, **sedimentation** ponds, and the water intakes and supply. This level of construction would allow for operation of the **facility** the **first** year and the **additional** raceways and rearing ponds could be built during Phase 2 of the construction. The steelhead program at this **station** is planned to be a two-year **smolt** program, which will allow for **construction** staging. The logical components to build **in** stages are the concrete raceways. One **12-raceway** bank of chinook raceways may be **built** the first year along **with** the **10** steelhead raceways. **This** would leave **21** raceways to be constructed **during** Phase 2 construction and would save approximately **\$500,000** In construction costs **during** the first year.


### 4. DESIGN AND CONSTRUCTION SCHEDULE

A design and construction schedule follows.

FIGURE V-1

KLICKITAT SALMON AND STEELHEAD HATCHERY

# Design and Construction Schedule



## SECTION VI

### REFERENCES

1. Fish Management Consultants, Yakima and Klickitat Rivers Central Out-planting Facility Proposed Master Plan. 1987.
2. Bonneville Power Administration, Draft Environmental Assessment Yakima/Klickitat Production Project. June 1989.
3. Northwest Power Planning Council, Columbia River Basin Fish and Wildlife Program.
4. Fish Management Consultants, Compendium of Low Cost Pacific Salmon and Steelhead Trout Production Facilities and Practices in the Pacific Northwest, 1984.

**SECTION VII**

**APPENDICES**

APPENDIX A

**FISH CULTURE PROGRAM,  
COMPUTER **ESTIMATES**,  
FISH MANAGEMENT CONSULTANTS**

**FINAL WATER AND SPACE  
CALCULATIONS  
FOR KLUCKITAT  
WITH ADDED COMMENTS**

By Fish Management Consultants

**Olympia, WA 98503  
(206)456-3826**

**May 1989**

# Fish Management Consultants

**TO:** Jay Kidder, R. W. Beck  
**FROM:** Harry Senn   
**DATE:** May 2, 1989  
**SUBJECT:** Final Water and Space Calculations for Klickitat With Added Comments

## A. Reference Water Needs

Tables 1A and 1B summarize rater flow recommendations. Several comments are:

- If a hatchery is to be over-design\* here's the place to do it. We are suggesting this (see computer runs at end). Based on recent studies, we could likely get by on half of the rater without changing survival, however, I would surely cut elsewhere Wore I'd cut here.
- Table 1B would be my recommended design flow, however, in the feasibility report, it may be best to show the flow in Table 1A then comments on Table 1B. There is no difference in pounds/gpm between the program of Table 1A and Table 1B.
- Computer runs are enclosed for review showing flow/space.

## B. Space

- Table 2 shows suggested space design
- Reference adult raceways
  1. We suggest two pairs of two each with access by truck to the outside wall. Consider a center wall with Pus through slots for easy adult sorting.
  2. Raceways are not highly recommended for holding spring chinook. WDF has suggested (P.C. Peck, 1989) epoxy paint may solve abrasions and high losses. Tea feet may be pretty narrow. Epoxy is another variable. Could we cost in removable liners in the four raceways. It may help.
- Space is not conservative, but realistic until we know better or go to lower cost units.

**Table 1 - Klickitat Water Design**

**Table 1A - Klickitat Water Design: without mixing spring water with river water during last 5 months**

	<b>Spring Chinook</b>	<b>Steelhead</b>	<b>Total</b>
Spring Source	<b>30 cfs</b>	<b>10 cfs</b>	<b>40 cfs</b>
River	<b>60 cfs</b>	<b>15 cfs</b>	<b>75 cfs</b>

- or -

**Table 1B - Klickitat Water Design: by mixing spring water with river water during December through April**

	<b>Spring Chinook</b>	<b>Steelhead</b>	<b>Total</b>
Spring Source	<b>33.0 cfs</b>	<b>7.0 cfs</b>	<b>40 cfs</b>
River (approx.)	<b>30.0 cfs</b>	<b>8.0 cfs</b>	<b>38 cfs</b>
			<hr/>
	<b>Total used at one time:</b>		<b>78 cfs</b>

Table 2 - Klickitat - Raceways/adult/deep trough

Steelhead	Minimum
Raceways =	6 for 2+ smolts 2 for 1+ smolts 1 for adults (100 females, 433,333 eggs) 1 spare
Deep trough= Raceways =	(20) trough for rearing need about 20, use 22 10 total (set in bank of 10)

Spring Chinook

Raceways =	5 for overlap period- March 1 to May 35 for smolts 0 for adults (need 4 raceways set up for adults out of the 35 through September 15). 2 spare
Deep trough= Raceways =	(21) 4.1 million green eggs 42 total (need 20.5 - we 22 deep)

'Note: The number 35 may not be compatible for Lars. The option would be to use one spare with 36 groups or reduce the study raceways from 35 to 33; retain one spare.

C. Pollution Runs

Please find these at the end of this report. They are only added to update the records.

HS:bp050289  
Enclosure

CC: Clune  
Scribner  
Ward  
Boyce  
Gatton

# Spring Chinook program growth/food

Culture Program for Spring Chinook at Cascade Springs  
with 30 T.O./Inch of Growth

R.A. NAME: PYS 114

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	MORT.	AVE. TEMP. (F)	BTU'S /IN.	LENGTH (MM)	NO FISH /LB.	BIOMASS (LBS.)	CONV RATE	14 DAY FEED REQ. (LBS.)	% FOOD FED /DAY
1	03/06/89	3,738,461				33.3	1,496.1	2,499			
15	03/20/89	3,444,351	7.91	45.0	30.0	38.4	978.4	3,523	1.00	1,024	2.9
29	04/03/89	3,246,443	5.35	45.0	30.0	42.5	674.4	4,914	1.04	1,337	3.7
43	04/17/89	3,111,779	3.60	45.0	30.0	46.5	464.4	6,424	1.07	1,725	2.6
57	05/01/89	3,020,207	2.45	45.0	30.0	53.6	359.6	8,399	1.11	2,167	2.4
71	05/15/89	2,957,938	1.67	45.0	30.0	58.7	274.2	10,787	1.14	2,729	2.3
85	05/29/89	2,915,596	1.13	45.0	30.0	63.7	213.9	13,634	1.16	3,355	2.2
99	06/12/89	2,886,803	0.77	45.0	30.0	68.8	170.0	16,982	1.21	4,066	2.1
113	06/26/89	2,867,223	0.52	45.0	30.0	73.9	137.3	20,876	1.25	4,867	2.0
127	07/10/89	2,853,753	0.36	45.0	30.0	78.9	112.6	25,355	1.29	5,759	2.0
141	07/24/89	2,843,024	0.29	45.0	30.0	84.0	93.4	30,444	1.32	6,725	1.9
155	08/07/89	2,832,768	0.27	45.0	30.0	89.1	78.3	36,163	1.36	7,761	1.8
169	08/21/89	2,822,791	0.27	44.0	30.0	93.5	67.2	42,017	1.39	8,154	1.6
183	09/04/89	2,813,106	0.26	44.0	30.0	98.4	58.1	48,459	1.43	9,203	1.6
197	09/18/89	2,803,711	0.25	44.0	30.0	103.1	50.5	55,517	1.46	10,334	1.5
211	10/02/89	2,794,626	0.24	44.0	30.0	107.8	44.2	63,216	1.50	11,549	1.5
225	10/16/89	2,785,265	0.23	44.0	30.0	112.5	38.9	71,585	1.54	12,852	1.5
239	10/30/89	2,777,438	0.23	44.0	30.0	117.2	34.4	80,650	1.57	14,245	1.4
253	11/13/89	2,769,315	0.22	44.0	30.0	121.8	30.6	90,439	1.61	15,732	1.4
267	11/27/89	2,761,526	0.21	44.0	30.0	126.5	27.3	100,979	1.64	17,316	1.4
281	12/11/89	2,754,062	0.20	39.0	30.0	129.2	25.7	107,365	1.68	18,720	0.8
295	12/25/89	2,746,921	0.19	36.0	30.0	131.6	24.3	113,008	1.71	9,673	0.6
309	01/08/90	2,740,104	0.18	36.0	30.0	133.1	23.5	116,784	1.75	6,607	0.4
323	01/22/90	2,733,611	0.17	36.0	30.0	134.7	22.7	120,650	1.79	6,903	0.4
337	02/05/90	2,727,442	0.17	36.0	30.0	136.3	21.9	124,607	1.82	7,209	0.4
351	02/19/90	2,721,597	0.16	37.0	30.0	138.2	21.0	129,754	1.86	9,558	0.5
365	03/05/90	2,716,076	0.15	38.0	30.0	140.6	19.9	136,178	1.89	12,160	0.7
379	03/19/90	2,710,717	0.14	40.0	30.0	143.7	18.7	145,160	1.93	17,323	0.9
393	04/02/90	2,705,358	0.14	42.0	30.0	147.6	17.2	156,991	1.96	23,240	1.1
407	04/16/90	2,700,000	0.14	43.0	30.0	151.9	15.8	170,743	2.00	27,503	1.3

BIOMASS PRODUCED (LBS.) = 170,743  
 TOTAL FOOD FED (LBS.) = 271,816      AVERAGE CONVERSION = 1.62

Spring Chinook **flow/space**

Water Flow and Space Requirements for a Single Run of Swing Chinook  
at Cascade Springs (using 30 T.U./Inch of Growth)

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

SPRING WATER = 13,500 GPM (30 cfs; used first 9 months of rearing)  
RIVER WATER = 27,000 GPM (60 cfs; used from December 1st to release)  
RACEWAY SPACE = 200,000 CU.FT.

HYKLIAR	-----WATER FLOW REQMT'S-----						-----RACEWAY REQMT'S-----			
	PERIOD	PERIOD	TOTAL	ACTUAL	ALLOW-	FLOW	ACTUAL	ALLOW-	TOTAL	
ENDING	ENDING	BIOMASS	WATER	ACTUAL	ABLE	REQ'D	RACEWAY	ACTUAL	ABLE	TOTAL
DAY	DATE	(LBS.)	FLOW	LBS./	LBS./	(GPM)	SPACE	LBS./	LBS./	CU.FT.
			USED	GPM	GPM		USED	CU. FT	CU.FT.	REQ'D
1	03/06/89	2,490	1350	1.85	5.74	435	25000	0.10	0.26	9,446
15	03/20/89	3,523	1350	2.61	5.74	614	25000	0.14	0.26	13,316
29	04/03/89	4,614	1350	3.57	6.20	777	25000	0.19	0.30	16,074
43	04/17/89	6,424	1350	4.76	6.56	979	25000	0.26	0.33	19,210
57	05/01/89	8,399	13500	6.62	6.91	1,216	155000	0.05	0.37	22,743
71	05/15/89	10,787	13500	8.80	7.24	1,490	155000	0.07	0.40	26,686
85	05/29/89	13,634	13500	11.01	7.56	1,803	155000	0.09	0.44	31,045
99	06/12/89	16,952	13500	13.26	7.89	2,154	155000	0.11	0.47	35,822
113	06/26/89	20,876	13500	15.55	8.21	2,544	155000	0.13	0.51	41,014
127	07/10/89	25,355	13500	17.88	8.53	2,974	155000	0.16	0.54	46,615
141	07/24/89	30,444	13500	20.26	8.87	3,423	155000	0.20	0.58	52,595
155	08/07/89	36,163	13500	22.68	9.23	3,919	155000	0.23	0.61	58,919
169	08/21/89	42,617	13500	25.11	10.93	4,445	155000	0.27	0.65	65,041
183	09/04/89	49,459	13500	27.59	11.25	4,998	155000	0.31	0.68	71,448
197	09/18/89	56,517	13500	30.11	11.55	5,585	155000	0.36	0.71	78,140
211	10/02/89	63,216	13500	32.68	11.84	6,197	175000	0.36	0.74	85,115
225	10/16/89	71,585	13500	35.30	12.12	6,836	175000	0.41	0.77	92,373
239	10/30/89	80,650	13500	37.97	12.38	7,504	175000	0.46	0.81	99,915
253	11/13/89	90,439	13500	40.70	12.63	8,160	175000	0.52	0.84	107,739
267	11/27/89	100,979	13500	43.48	12.87	8,846	175000	0.58	0.87	115,846
281	12/11/89	107,365	27000	46.38	26.38	9,571	175000	0.61	0.89	120,571
295	12/25/89	113,008	27000	49.19	31.08	10,336	175000	0.65	0.91	124,652
309	01/08/90	116,784	27000	51.33	47.89	11,149	175000	0.67	0.92	127,308
323	01/22/90	120,650	27000	53.47	47.37	12,007	175000	0.69	0.93	129,999
337	02/05/90	124,607	27000	55.62	46.86	12,909	175000	0.71	0.94	132,726
351	02/19/90	129,754	27000	57.81	36.50	13,855	175000	0.74	0.95	136,259
365	03/05/90	136,178	27000	60.04	29.88	14,848	175000	0.78	0.97	140,625
379	03/19/90	145,160	27000	62.38	21.57	15,889	175000	0.83	0.99	146,646
393	04/02/90	156,991	27000	64.81	16.44	17,004	175000	0.90	1.02	154,408
407	04/16/90	170,743	27000	67.32	14.70	18,212	175000	0.98	1.05	163,190

Steelhead growth/food

2 Year Culture Program for Steelhead at Cascade Springs  
with 39 T O/Linch of Growth

RUN NAME: HYR034

PERIOD ENDING DAY	PERIOD ENDING DATE	NO. FISH	MORT.	AVE. TEMP. (F)	#TU'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	% FOOD EFF. /DAY
1	05/01/89	390,000				25.8	2,806.1	139			
15	05/15/89	357,462	8.34	45.0	36.0	29.8	1,820.4	196	0.80	46	2.4
29	05/29/89	335,194	5.71	45.0	38.0	33.8	1,247.2	269	0.83	60	2.2
43	06/12/89	320,194	3.65	45.0	36.0	37.8	892.4	359	0.85	77	2.0
57	06/26/89	309,994	2.62	45.0	38.0	41.8	659.2	470	0.88	97	1.9
71	07/10/89	303,058	1.79	45.0	38.0	45.8	501.0	601	0.90	121	1.6
85	07/24/89	298,341	1.21	45.0	38.0	49.8	389.7	766	0.93	149	1.8
99	08/07/89	295,134	0.82	44.0	38.0	53.5	314.4	936	0.95	164	1.9
113	08/21/89	292,953	0.56	44.0	38.0	57.2	257.3	1,136	0.98	195	2.5
127	09/04/89	291,453	0.38	44.0	38.0	60.9	213.3	1,367	1.00	228	2.4
141	09/18/89	290,258	0.31	44.0	38.0	64.6	178.7	1,624	1.03	264	2.4
155	10/02/89	289,115	0.29	44.0	38.0	68.3	151.3	1,911	1.05	302	2.3
169	10/16/89	258,004	0.28	44.0	38.0	72.0	129.1	2,230	1.08	343	1.3
183	10/30/89	286,925	0.28	44.0	38.0	75.7	111.1	2,582	1.10	387	1.2
197	11/13/89	285,879	0.27	44.0	38.0	79.4	96.3	2,968	1.13	434	1.2
211	11/27/89	284,867	0.26	44.0	38.0	83.0	84.0	3,390	1.15	485	1.2
225	12/11/89	283,891	0.25	39.0	38.0	85.2	77.8	3,648	1.18	503	0.6
239	12/25/89	282,951	0.24	38.0	38.0	87.0	73.0	3,678	1.20	275	0.5
253	01/08/90	282,047	0.23	36.0	38.0	88.3	70.0	4,032	1.23	189	0.3
267	01/22/90	281,180	0.22	36.0	38.0	89.5	67.1	4,190	1.25	198	0.4
281	02/05/90	280,348	0.21	36.0	38.0	90.7	64.4	4,352	1.28	207	0.4
295	02/19/90	279,553	0.20	37.0	38.0	92.3	61.2	4,564	1.30	276	0.5
309	03/05/90	278,793	0.19	38.0	38.0	94.1	57.7	4,831	1.33	353	0.6
323	03/19/90	278,070	0.19	40.0	36.0	96.6	53.4	5,206	1.35	507	0.7
337	04/02/90	277,383	0.18	42.0	38.0	99.7	48.6	5,706	1.38	687	0.9
351	04/16/90	276,732	0.17	43.0	38.0	103.1	44.0	6,293	1.40	821	1.0
365	04/30/90	276,117	0.16	45.0	38.0	107.1	39.2	7,039	1.43	1,063	1.2
379	05/14/90	275,520	0.15	45.0	38.0	111.1	35.1	7,841	1.45	1,163	1.2
393	05/28/90	274,923	0.15	45.0	38.0	115.1	31.6	8,701	1.48	1,268	1.2
407	06/11/90	274,326	0.15	45.0	38.0	119.1	28.5	9,620	1.50	1,378	1.1
421	06/25/90	273,729	0.15	45.0	38.0	123.1	25.8	10,600	1.53	1,494	1.1
435	07/09/90	273,132	0.15	45.0	38.0	127.1	23.5	11,643	1.55	1,616	1.1
449	07/23/90	272,535	0.15	45.0	38.0	131.1	21.4	12,750	1.58	1,744	1.1
463	08/06/90	271,938	0.15	44.0	38.0	134.8	19.7	13,828	1.60	1,725	1.0
477	08/20/90	271,342	0.15	44.0	38.0	138.5	18.1	14,964	1.63	1,845	1.0
491	09/03/90	270,745	0.15	44.0	38.0	142.1	16.8	16,158	1.65	1,971	0.9
505	09/17/90	270,148	0.15	44.0	38.0	145.8	15.5	17,412	1.68	2,101	0.9
519	10/01/90	269,551	0.15	44.0	38.0	149.5	14.4	18,728	1.70	2,236	0.9
533	10/15/90	268,954	0.15	44.0	38.0	153.2	13.4	20,105	1.73	2,377	0.9
547	10/29/90	268,357	0.15	44.0	38.0	156.9	12.5	21,547	1.75	2,523	0.9
561	11/12/90	267,760	0.15	44.0	38.0	160.6	11.6	23,053	1.78	2,674	0.9
575	11/26/90	267,163	0.15	44.0	38.0	164.3	10.8	24,625	1.80	2,830	0.9
589	12/10/90	266,566	0.15	39.0	38.0	166.5	10.4	25,550	1.83	1,687	0.5
603	12/24/90	265,969	0.15	36.0	38.0	168.3	10.1	26,351	1.85	1,481	0.4
617	01/07/91	265,372	0.15	36.0	38.0	169.5	9.9	26,873	1.88	979	0.3
631	01/21/91	264,775	0.15	36.0	36.0	170.8	9.7	27,401	1.90	1,003	0.3

2 Year Culture Program for Steelhead at Cascade Springs  
with 36 T.U./Inch of Growth

PERIOD ENDING DAY	PERIOD ENDING DATE	NO.	FISH	2 MORT.	AVE. TEMP. (F)	FISH'S /IN.	LENGTH (MM)	NO. FISH /LB.	BIOMASS (LBS.)	CONV. RATE	14 DAY FEED REQ. (LBS.)	2 FOOD FED /DAY
645	02/04/91	264,178		0.15	36.0	38.0	172.0	9.5	27,935	1.93	1,028	0.3
659	02/18/91	263,582		0.15	37.0	38.0	173.5	9.2	28,626	1.95	1,349	0.3
673	03/04/91	262,985		0.15	38.0	38.0	175.4	8.9	29,483	1.98	1,692	0.4
687	03/18/91	262,388		0.15	40.0	38.0	177.9	8.6	30,673	2.00	2,379	0.6
701	04/01/91	261,791		0.15	42.0	38.0	180.9	8.1	32,220	2.03	3,132	0.7
715	04/15/91	261,194		0.15	43.0	38.0	184.3	7.7	33,985	2.05	3,619	0.8
729	04/29/91	260,597		0.15	45.0	38.0	188.3	7.2	36,164	2.08	4,522	1.0
743	05/13/91	260,000		0.15	45.0	38.0	192.3	6.8	38,431	2.10	4,760	0.9

BIOMASS PRODUCED (LBS.) = 38,431  
 TC = FOOD FED (LBS.) = 64,868 AVERAGE CONVERSION = 1.69

# Steelhead flow/space

Water Flow and Space Requirements for a Single Run of Steelhead  
at Cascade Springs (using 33 T.U./Inch of Growth)

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

SPRING WATER = 4,500 GPM (10 cfs; used from May 1st to December 1st)

FIVER WATER = 6,750 GPM (15 cfs; used from December 1st to May 1st)

RACEWAY SPACE = 40,000 CU.FT.

PERIOD		TOTAL BIOMASS (LBS.)	-----WATER FLOW REQMT'S-----				-----RACEWAY REQMT'S-----			
ENDING DAY	ENDING DATE		ACTUAL WATER FLOW USED	ACTUAL LBS./ GPM	ALLOW- ABLE LBS./ GPM	FLOW REQ'D (GPM)	ACTUAL RACEWAY SPACE USED	ACTUAL LBS./ CU.FT.	ALLOW- ABLE LBS./ CU.FT.	TOTAL REQ'D
1	05/01/89	129	500	0.28	7.12	20	10000	0.01	0.21	677
18	05/15/89	196	500	0.39	7.12	28	10000	0.02	0.21	957
24	05/29/89	269	500	0.54	7.73	35	10000	0.03	0.23	1,154
43	06/12/89	359	500	0.72	8.23	44	10000	0.04	0.26	1,379
57	06/26/89	470	500	0.94	8.69	54	10000	0.05	0.29	1,623
71	07/10/89	605	500	1.21	9.13	66	10000	0.06	0.32	1,917
85	07/24/89	766	500	1.53	9.57	80	10000	0.08	0.34	2,231
99	08/07/89	939	500	1.88	11.47	82	10000	0.09	0.37	2,547
113	08/21/89	1,138	500	2.28	11.88	96	10000	0.11	0.39	2,869
127	09/04/89	1,367	500	2.73	12.30	111	10000	0.14	0.42	3,258
141	09/18/89	1,624	500	3.25	12.76	127	10000	0.16	0.44	3,650
155	10/02/89	1,911	500	3.82	13.26	144	10000	0.19	0.47	4,064
169	10/16/89	2,230	500	4.46	13.74	162	10000	0.22	0.50	4,498
183	10/30/89	2,582	500	5.16	14.21	182	10000	0.26	0.52	4,953
197	11/13/89	2,968	500	5.94	14.65	203	10000	0.30	0.55	5,429
211	11/27/89	3,390	500	6.78	15.07	225	10000	0.34	0.57	5,925
225	12/11/89	3,648	1350	2.70	31.28	117	10000	0.36	0.59	6,215
239	12/25/89	3,978	1350	2.87	37.08	105	10000	0.39	0.60	6,466
253	01/08/90	4,032	1350	2.99	57.56	70	10000	0.40	0.61	6,629
267	01/22/90	4,190	1350	3.10	57.10	73	10000	0.42	0.62	6,794
281	02/05/90	4,352	1350	3.22	56.66	77	10000	0.44	0.63	6,962
295	02/19/90	4,564	1350	3.38	44.16	103	10000	0.46	0.64	7,179
309	03/05/90	4,831	1350	3.58	36.20	133	10000	0.48	0.65	7,449
323	03/19/90	5,206	1350	3.86	26.14	199	10000	0.52	0.67	7,824
337	04/02/90	5,706	1350	4.23	19.94	286	10000	0.57	0.69	8,310
351	04/16/90	6,293	1350	4.66	17.89	352	10000	0.63	0.71	8,863
365	04/30/90	7,039	1350	5.21	13.92	506	10000	0.70	0.74	9,544
379	05/14/90	7,841	4000	1.96	14.23	551	30000	0.26	0.77	10,248
393	05/28/90	8,701	4000	2.18	14.54	598	30000	0.29	0.79	10,976
407	06/11/90	9,620	4000	2.41	14.85	648	30000	0.32	0.82	11,728
421	06/25/90	10,600	4000	2.65	15.14	700	30000	0.35	0.85	12,502
435	07/09/90	11,643	4000	2.91	15.43	755	30000	0.39	0.88	13,299
449	07/23/90	12,750	4000	3.19	15.70	812	30000	0.42	0.90	14,119
463	08/06/90	13,828	4000	3.46	18.21	759	30000	0.46	0.93	14,893
477	08/20/90	14,964	4000	3.74	18.46	810	30000	0.50	0.95	15,687
491	09/03/90	16,158	4000	4.04	18.71	864	30000	0.54	0.98	16,499
505	09/17/90	17,412	4000	4.35	18.95	919	30000	0.58	1.00	17,329
519	10/01/90	18,728	4000	4.68	19.19	976	30000	0.62	1.03	18,178
533	10/15/90	19,105	4000	5.03	19.42	1,036	30000	0.67	1.06	19,044
547	10/29/90	21,547	4000	5.39	19.64	1,097	30000	0.72	1.08	19,929
561	11/12/90	23,053	4000	5.76	19.86	1,161	30000	0.77	1.11	20,832
575	11/26/90	24,625	4000	6.16	20.07	1,227	30000	0.82	1.13	21,753

# Steelhead

## Water Flow and Space Requirements for a Single Pan of Steelhead at Cascade Springs (Using 30 % 1/2 inch of Growth)

GIVEN THE FOLLOWING MAXIMUM WATER FLOW AND SPACE REQUIREMENTS:

SPRING WATER = 4,500 GPM (10 cfs; used from May 1st to December 1st)  
 COLDER WATER = 6,750 GPM (15 cfs; used from December 1st to May 1st)  
 RACEWAY SPACE = 40,000 CU.FT.

HYKL34F		-----WATER FLOW REQMT'S-----					-----RACEWAY REQMT'S-----			
PERIOD	PERIOD	TOTAL	ACTUAL	ACTUAL	ALLOW-	ACTUAL	ACTUAL	ALLOW-	TOTAL	
ENDING	ENDING	BIO MASS	WATER	LBS./	ABLE	FLOW	RACEWAY	ABLE	CU.FT.	CU.FT.
DAY	DATE	(LBS.)	USED	GPM	LBS./	REQ'D	SPACE	LBS./	REQ'D	REQ'D
				GPM	GPM	(GPM)	USED	CU.FT.	CU.FT.	
569	12/10/90	25,550	5400	4.73	40.87	625	30000	0.85	1.15	22,277
603	12/24/90	26,351	5400	4.98	48.29	546	30000	0.69	1.16	22,723
617	01/07/91	26,673	5400	4.98	75.37	357	30000	0.90	1.17	23,005
631	01/21/91	27,401	5400	5.07	75.01	365	30000	0.91	1.18	23,288
645	02/04/91	27,935	5400	5.17	74.66	374	30000	0.93	1.19	23,572
659	02/18/91	28,626	5400	5.30	57.98	494	30000	0.95	1.20	23,941
673	03/04/91	29,483	5400	5.46	47.37	622	30000	0.98	1.21	24,328
687	03/18/91	30,673	5400	5.68	34.00	902	30000	1.02	1.23	25,031
701	04/01/91	32,220	5400	5.97	25.77	1,250	30000	1.07	1.25	25,846
715	04/15/91	33,965	5400	6.29	22.93	1,482	30000	1.13	1.27	26,762
729	04/29/91	36,164	5400	6.70	17.68	2,046	30000	1.21	1.30	27,872
743	05/13/91	38,431	5400	7.12	17.87	2,151	30000	1.28	1.33	29,003

Discharge - Klickitat

Estimated PPM of Pollutants Generated Daily for  
all Species Programmed at Cascade Springs

HYAL14F

PERIOD ENDING DAY	PERIOD ENDING DATE	FOOD FED ALL SPECIES (LBS.)	GPM WATER ACTUAL	POLLUTANTS GENERATED IN PPM **					RECEIVING WATER (CFS)
				TOTAL AMMONIA	NH3	NITRATE	PHOSPHATE	SETTLED SOLIDS	
.	06/01/89	334	18,000	0.05	0.0001	0.13	0.01	0.46	0.53
15	06/15/89	354	18,000	0.06	0.0001	0.16	0.01	0.55	0.62
29	06/29/89	461	18,000	0.07	0.0001	0.19	0.01	0.64	0.73
43	07/13/89	535	18,000	0.08	0.0001	0.22	0.01	0.74	0.84
57	07/27/89	616	18,000	0.09	0.0001	0.25	0.01	0.85	0.97
71	08/10/89	689	18,000	0.10	0.0002	0.28	0.02	0.96	1.08
85	08/24/89	729	18,000	0.11	0.0002	0.29	0.02	1.01	1.14
99	09/07/89	814	18,000	0.12	0.0002	0.33	0.02	1.13	1.28
113	09/21/89	907	18,000	0.13	0.0002	0.37	0.02	1.26	1.43
127	10/05/89	1,006	18,000	0.16	0.0002	0.41	0.02	1.40	1.58
141	10/19/89	1,102	18,000	0.16	0.0003	0.45	0.03	1.54	1.75
155	11/02/89	1,225	18,000	0.16	0.0003	0.49	0.03	1.70	1.93
169	11/16/89	1,346	18,000	0.20	0.0003	0.54	0.03	1.87	2.12
183	11/30/89	1,474	18,000	0.22	0.0003	0.59	0.03	2.05	2.32
197	12/14/89	908	33,750	0.07	0.0001	0.20	0.01	0.67	0.76
211	12/28/89	816	33,750	0.06	0.0001	0.18	0.01	0.60	0.68
225	01/11/90	555	33,750	0.04	0.0001	0.12	0.01	0.41	0.47
239	01/25/90	579	33,750	0.05	0.0001	0.12	0.01	0.43	0.49
253	02/08/90	603	33,750	0.05	0.0001	0.13	0.01	0.45	0.51
267	02/22/90	799	33,750	0.06	0.0001	0.17	0.01	0.59	0.67
281	03/08/90	1,015	35,100	0.08	0.0001	0.21	0.01	0.72	0.82
295	03/22/90	1,517	35,100	0.12	0.0002	0.31	0.02	1.08	1.22
309	04/05/90	2,028	35,100	0.15	0.0002	0.42	0.02	1.44	1.64
323	04/19/90	2,405	35,100	0.18	0.0003	0.50	0.03	1.71	1.94
337	05/03/90	555	18,000	0.08	0.0001	0.22	0.01	0.77	0.87
351	05/17/90	621	18,000	0.09	0.0001	0.25	0.01	0.86	0.98
365	05/31/90	334	18,000	0.05	0.0001	0.13	0.01	0.46	0.53
379	06/14/90	394	18,000	0.06	0.0001	0.16	0.01	0.55	0.62
393	06/28/90	461	18,000	0.07	0.0001	0.19	0.01	0.64	0.73
407	07/12/90	535	18,000	0.08	0.0001	0.22	0.01	0.74	0.84

\*\* The ppm of pollutants in the discharge water is illustrated in the table.  
Vacuum cleaning will significantly reduce the level of settleable solids  
and B.O.D.

APPENDIX B

SITE INVESTIGATION REPORT,  
R. W. BECK AND ASSOCIATES

WV-1715-EA1-AX  
3023

September 14, 1989

Tom Clune  
Senior Project Manager  
Yakima Project  
Fish And Wildlife Division  
Bonneville Power Administration  
Sunfair Professional Building  
103 S. Third Street  
P.O. Box 2685  
Yakima, Washington 98907

Dear Tom:

Subject: **Klickitat Salmon and Steelhead**  
Hatchery Preliminary Design  
Site Investigation Report

Included in this letter report are results to several months of field investigations and measurements. Through the course of approximately one year, starting in August of 1988 R.W. Beck personnel have visited the proposed area for the **Klickitat** Hatchery in the canyon of the **Klickitat** River near Cascade Spring. We began our work where the Waster Plan stopped. We set out to accomplish the preliminary site selection and <sup>design</sup> for the proposed hatchery and we are approaching the completion of this task at the end of October, 1989.

This letter will recap the history and results of the following investigations:

1. **WDF** Hatchery Co-operation Feasibility Review.
2. Property Line Boundary Review.
3. Topographic Site Survey.
4. Water Quality and Quantity Analysis and Review.
5. Measurement of Cascade Spring Water Flow.

6. Indian Ford Spring Water Flow **Measurement/Later** to be replaced <sup>with</sup> Kidder Spring water flow measurement.
7. River Flood Stage Elevation Analysis.

Upon the second trip to the proposed site we discovered another large Spring upriver from the Cascade Spring. This Spring has been named Kidder Spring and is currently ear-marked for about one third of the overall hatchery water demand. As was referenced in our letter dated April 21, 1989 we discussed the reasoning behind investigating the site we called "**Midway Bar**". The other proposed sites at White Creek and Indian Ford are more restrictive in space than the "**Midway Bar**" site and **don't** afford the convenience of the water supply from Kidder and Cascade Springs. We still do not see any "fatal flaws" with this site and we are proceeding with the preliminary design of the **Klickitat** Hatchery located at the "**Midway Bar**" site.

The potential for a co-operation plan with the **WDF** at their already established station on the **Klickitat** was considered as a possible means to provide for the required fish production goals. The idea entertained, was to utilize space at the **Klickitat** Salmon Hatchery at the same time that **WDF** was occupying the facility. This was thought to be possible because the **Klickitat** Salmon Hatchery was not at full capacity. However, when **R. W. Beck** and Associates researched the capacity of the station with the help of **Bill Hopley** of the **WDF**, we ascertained that the station was indeed at full capacity. The **WDF** policy concerning this co-operation idea was positive, however not possible because the station is continuing to operate at full capacity as planned for the long run. For this reason we requested a letter from **Bill Hopley** officially addressing this idea. This letter is attached for reference.

Initially we planned to do a property line description, survey and monument placement for the proposed hatchery site. Once the preliminary design began, your **BPA** office of Lands and Acquisition was engaged to do this task in-house. The results of this investigation are that the hatchery site proper, and Kidder Spring lie on Champion Timber Company land and that Cascade Spring exists on Tribal lands.

We also stated that the preliminary site elevations gathered early in our investigations would allow for gravity flow of water to the **Midway Bar** site from the springs. This can be accomplished through gravity pipelines starting at the Spring sources and flowing toward the hatchery. We now feel comfortable that gravity flow can be provided to the hatchery and its head boxes and supply manifolds by gravity pipelines as can be seen in the site plan and schematic profile attached. The **Klickitat** River water supply system will be more economical to pump than to construct a gravity pipeline the approximately **3500** feet upstream required for a

gravity feed to the hatchery. During the final phases of design, the final elevations and grades between the Spring and River water supplies and the Hatchery must be refined one step further to provide topographic resolution sufficient for construction. The Midway Bar was the only site surveyed for topography because of the discounting of the White Creek and Indian Ford sites. Attached is the topographic survey to the nearest 5 feet for the Midway Bar site and the two spring water sources.


We measured the Spring flows of Cascade and Kidder Springs twice through the course of our investigations. The first measurement was on April 3rd, 1989 and the second measurement was on August 22nd, 1989. Both Springs were measured using the dye injection flow measurement technique discussed in the letter of April 3, 1989. The results are as follows:

	<u>April 3</u>	<u>August 22</u>	<u>Average</u>
Cascade Spring	24 CFS	21 CFS	22.5 CFS
Kidder Spring	17 CFS	13 CFS	15 CFS

We feel that sufficient information concerning flow quantity from both Springs has been gathered to date and that this information is a conservative figure to base the preliminary design upon. The true quantity of water that is actually delivered to the facility will not be known until the Spring Diversions are in-place and functioning. Both springs are constant in flow rates as measured five months apart and for the most part the temperatures are close to stable. However there is a slight variation in temperature which is critical for the fish programming at this station. The cool temperatures can work for us as Harry Senn has programmed around these small fluctuations. If there is a difference in the temperatures between what was measured and what is actually delivered to the hatchery in the future then there will have to be an adjustment to the programming that allows for the variation. The attached plot of dates and temperatures for the three water sources for the Klickitat station is a culmination of what we know to date about them. Also attached is the hatchery flow requirements for a one year cycle in graphic and tabular format. This data was provided by Harry Senn.


Also attached in a memorandum format to the file is our analysis of the flood flows and associated calculations of flood elevations. The approximate elevation of the finished site is above elevation 1175.0 feet MSL at the upstream end of the site and above 1168.0 feet MSL at the downstream end of the site. Likewise, the flood elevations that result from the 100 year flood event, plus a factor of safety of approximately four times this flow, display elevations ten feet higher than the original water surface at normal flows. The flood elevations are approximately 1172.0 feet MSL at the upstream end of the site and 1163.0 feet MSL at the downstream end of the site. Please see attached memo and calculations.

# WATER TEMPERATURES vs. MONTH Klickitat River, Cascade and Kidder Springs



X Data	KLICKITAT R.	CASCADE SPRING	KIDDER SPRING
JAN	37	43	44
FEB		45	
MAR		45	45
APR	41	45	45
MAY	48	46	46
JUN	49	46	45
JUL	49	45	45
AUG	52	45	45
SEP	55	44	45
OCT		44	
NOV		44	
DEC	36	43	44

# KLICKITAT HATCHERY WATER FLOW RATES vs. MONTH



X Data	KLICKITAT R.	TOTAL RIVER DE	TOTAL SPRING D	TOTAL STA m-v
JAN	637	38.95	37	75.95
FEB	656	38.95	37	75.95
MAR	694	38.45	40	78.45
APR	1178	38.45	40	78.45
MAY	1849	0	37	37
JUN	1552	0	37	37
JUL	859	0	37	37
AUG	542	0	37	37
SEP	441	0	37	37
OCT	453	0.45	37	37.45
NOV	578	0.45	37	37.45
DEC	658	38.95	37	75.95

X Data	SPR CHINOOK 0	STEELHEAD 1 DE	STEELHEAD 2 DE	STEELHEAD
	0.5			8
FEB	0.5	0.45		8
MAR				
APR		0.45		8
MAY				
JUN				
JUL				
AUG				
SEP				
OCT				
NOV				
DEC	0.5			



STATE OF WASHINGTON  
DEPARTMENT OF FISHERIES

115 General Administration Building • Olympia, Washington 98504 • (206) 753-6600 • (SCAN) 234-6600

June 12, 1989

RECEIVED  
JUN 13 1989

R W BECK AND ASSOCIATES  
Seattle, WA 98101

Mr. Jay Kidder  
Project Manager  
R. W. Beck and Associates  
2121 Fourth Avenue, Suite 600  
Seattle, Washington 98121-2317

Dear Jay:

**SUBJ: KLICKITAT RIVER SALMON AND STEELHEAD HATCHERY  
EXISTING FACILITY REVIEW**

Your letter of April 20, 1989 requests confirmation of the fact that no extra water or space is available for incubation or rearing at the Washington Department of Fisheries Klickitat station that could be utilized for a portion of the production program for the Klickitat tribal station.

We concur in general with your assessment. The water and pond use schedule for Klickitat was reviewed and, with one exception, there is no opportunity for additional rearing. The exception is Wonder Springs pond which is vacant between August and January. This time period normally does not offer any particular advantage for added production. There might be some sensible role, such as temperature advantage, that would complement the YKPP on an interim basis but no such role has been identified in the program.

There might also be a moderate level of hatching capacity if newly-hatched fry were ponded elsewhere. I doubt the benefits would be worth the added operational complexity.

In summary, although there might be minor opportunity for interim use of Klickitat Hatchery, there is no opportunity to achieve increased production at Klickitat Hatchery.

Please feel free to call if additional questions should arise.

Sincerely,

Bill Hopley, Asst. Chief  
Assessment & Development

BH:fw

B-10

The water flow measurements performed by the U. S. Fish and Wildlife Biologists from the Vancouver Assistance office are not published within this report because the IFIM study is currently ongoing. This information will hopefully be ready when the final draft of the preliminary design report is finished and will be included at that time. The previously mentioned flood flow elevations are based on a standard hydrologic **method** of statistical analysis and provide a rough envelope of elevations to not set structures or facilities below. From this elevation and above, flood events of 100 year duration should not occur. Some fill will need to be placed along the outward and downstream portion of the site and **revetment of riprap** will need to be placed along the upstream face of the site for protection from high flow events. The areas of fill and **riprap** are shown on the attached site plan.

The outcome of all this field work and data collection is that the Midway **Bar** site for the **Klickitat** Salmon and Steelhead Hatchery is a good choice for the facility. To date there are no "fatal-flaws" with the site and its potential to provide for the proposed fish production program that is to be grown there. If there is any one problem with the development of the **Midway Bar** site, it is the affects that will be caused to the Springs and the Site by construction of the buildings and the water supply structures. Otherwise, the site development will require a moderate to high level of difficulty during construction of the water supply system and a moderate level of difficulty for construction of the hatchery facilities proper. The site is 40 miles remote from Goldendale and this may cause some inconvenience with certain phases of construction.

If you perceive any problems or have requests and questions please feel to call.

**Sincerely,**  
**R.W. Reck and Associates**




---

Jay **S.** Kidder  
Project **Manager**

R. W. BECK AND ASSOCIATES	<u>KUCKITAT HATCHERY PREDESIGN</u>			PROJECT <u>KUCKITAT</u>
	<u>RIVER FLOOD STAGE</u>			FILE NO. _____
	COMP. <u>R</u>	CHK. _____	REV. _____	PAGE <u>1</u> OF <u>8</u> PAGES
	DATE <u>6/20/87</u>	DATE _____	DATE _____	

I PURPOSE: TO CALCULATE THE RIVER FLOOD STAGE AT THE PROPOSED HATCHERY SITE THE RIVER STAGE WAS MEASURED WITH SURVEY INSTRUMENTS AND A CROSS SECTION WAS DEVELOPED AT THE SECTION VISUALLY CHOSEN TO BE THE CRITICAL SECTION FOR HYDRAULIC CONTROL IN FRONT OF THE HATCHERY SITE.


III SITE DESCRIPTION



SITE PLAN  
SCALE: NONE

SECTION AA IS CHOSEN AS THE CRITICAL SECTION.

NUMBERS INDICATE SURVEY SHOTS



SCHMATIC SECTION AA  
SCALE: NONE  
B-11

R. W. BECK AND ASSOCIATES	KLICKITAT HATCHERY PREDESIGN			PROJECT	KLICKITAT
	FLOOD STAGE CALCULATION.			FILE NO.	
	COMP.	CHK.	REV.	PAGE	2 OF 8 PAGES
	DATE	DATE	DATE		

SURVEY NOTES

SECTION AA

NUMBER OF STA	HORIZ $\angle$	HORIZ DIST	VERT DIST	ELEV	COMMENT	
①		183.48.37	47.63	-0.53	1274.52	LFT BANK @ RD.
②		209.59.03	59.75	-24.20	1250.85	W/S @ TOE
③		218°-18'-14"	71.61	-27.62	1247.43	EDGE OF POOL
④		238°-34'-49"	100.19	-26.82	1248.23	IN POOL
⑤		239° 37' 19"	107.10	-26.13	1248.92	IN POOL
⑥		241° 24' 19"	120.81	-24.07	1250.98	XVS RT BANK
⑦		243° 45' 02"	132.75	-22.73	1252.23	RT BANK
⑧		247° 23' 24"	148.13	-21.67	1253.38	"
⑨		248° 22' 55"	157.28	-19.71	1255.34	"
⑩		249° 34' 51"	154.6	-17.12	1257.93	TOP OF BENCH
⑪		252° 40' 45"	167.45	-17.42	1257.63	ON BENCH
⑫		250° 01' 21"	260.49	-17.64	1257.41	TOE OF HILL
⑬		251° 28' 48"	268.05	-13.13	1261.92	
⑭		249° 24' 34"	298.42	-4.14	1270.91	
⑮		248° 32' 42"	320.43	0.64	1274.41	

AREA OF WATER CROSS SECTION = 137.8 FT<sup>2</sup>

III ASSUMPTIONS

1. ASSUME THE FLOW IN THE RIVER IS GRADUALLY VARIED OR CONSTANT, DURING THE INSTANCE OF ANALYSIS.
2. ASSUME THE CROSS SECTION AA IS PERPENDICULAR TO THE FLOW STREAMLINES
3. USE MANNINGS EQUATION TO DESCRIBE THE FLOW IN THIS CROSS SECTION.

R. W. BECK AND ASSOCIATES	KLUCKITAT HATCHERY REDESIGN			PROJECT <u>KLUCKITAT</u>
	FLOOD STAGE CALCULATION.			FILE NO. _____
	COMP. <u>JK</u>	CHK. _____	REV. _____	PAGE <u>3</u> OF <u>8</u> PAGES
	DATE <u>6/29/87</u>	DATE _____	DATE _____	

IV CALCULATE HYDRAULIC PARAMETERS OF SECTION AA

DETERMINE Q

ESTIMATED AVERAGE Q @ SECTION AA

AND VERIFIED BY IFIM RECORDS OF USFWS 5/89 MEASUREMENTS.

RE: DONENGLIN  
VACOUVER

$$\bar{Q} \approx 900 \text{ CFS}$$

A RELATIONSHIP OF AVG. Q AND MEAN MAXIMUM Q IS GIVEN BY, BELL, 1989 ; FISHERIES HANDBOOK USCOE.

$$\bar{Q}_{MAX} = 7.72 \bar{Q} \quad \text{EASTERN WASHINGTON}$$

∴ IF  $\bar{Q} = 900 \text{ CFS}$

$$\bar{Q}_{MAX} = (7.72)(900) = 6940 \text{ CFS}$$

USE  $\bar{Q}_{MAX} = 7000 \text{ CFS}$

WITHOUT FURTHER IN DEPTH PROBABILITY ANALYSIS AT THIS POINT USE A FACTOR OF SAFETY OF 4.

$$FS = 4$$

$$Q_{MAX} = (7000)(4) = 28,000 \text{ CFS}$$

USE THE FOLLOWING FLOWS FOR ANALYSIS:

$$\bar{Q} \approx 900 \text{ CFS}$$

$$\bar{Q}_{MAX} \approx 7000 \text{ CFS}$$

$$Q_{MAX} = 28,000 \text{ CFS}$$

R. W. BECK AND ASSOCIATES	CLIENT - HATCHERY PREDESIGN			PROJECT <u>KLUCKIT</u>
	FLOW STAGE CALCULATION			FILE NO. _____
	COMP. <u>SE</u>	CHK. _____	REV. _____	PAGE <u>4</u> OF <u>8</u> PAGES
	DATE <u>10/2/67</u>	DATE _____	DATE _____	

NOTE ALSO THAT IN THE USFWS, 1979  
FEASIBILITY STUDY, THE TWO FLOW STAGES  
NEAR SLEIWOOD AT RIVER MILE 50.3 WERE  
IN 1933 AND 1979 AND MEASURED 1370 CFS AND  
9300 CFS RESPECTIVELY.  
THE PROPOSED HATCHERY SITE IS LOCATED AT  
RIVER MILE ~ 41.0

ASSUME MAINTENANCE n

ASSUME  $n = 0.028$

REF. CHOW, OPEN  
CHANNEL HYDRAULIC  
1959 PG 110.

ONE FORM OF MAINTENANCE EQUATION:

$$AR^{2/3} = \frac{Qn}{1.49\sqrt{S}}$$

- A = AREA OF WETTED CROSS SECTION
- R = HYDRAULIC RADIUS =  $A/P$
- Q = FLOW RATE
- S = REACH SLOPE

REACH SLOPE WAS MEASURED TO BE  
 $S = 0.007$

FOR SECTION AA ACROSS BARRAGE

A = 137.9  $\text{ft}^2$   
P = 61 FT  
R = 2.26  
b = 30' = BOTTOM WIDTH

R. W. BECK AND ASSOCIATES			PROJECT <u>KLUCKWITZ</u>
			FILE NO. _____
	COMP. _____	CHK. R E V _____	PAGE <u>5</u> OF <u>8</u> PAGES
	DATE _____	DATE _____	DATE _____

CHECK GIVEN DIMENSIONS TO GIVEN Q

$$AR^{2/3} = \frac{Q n}{1.49 \sqrt{S}}$$

$$(137.8 \text{ FT}^2 / 2.26)^{2/3} = \frac{(900)(0.029)}{1.49 \sqrt{0.001}}$$

$$237.31 = 202.15 \quad \text{DOES NOT EQUATE}$$

∴ Q = 900 CFS IS LOW

TRY Q = 1000 CFS

$$237.31 = 1000 (0.22)$$

$$237.31 = 224.61 \quad \text{CLOSE}$$

TRY Q = \_\_\_\_\_ CFS

$$237.31 = 1078 (0.22)$$

$$237.31 = 237.31 \quad \text{OK } \checkmark$$

$$Q = 1078$$

∴  $\bar{Q}_{MAX}$  &  $Q_{MAX}$  ARE OK.

SOLVE FOR  $AR^{2/3}$  AT  $Q_{MAX} = 28000 \text{ CFS}$

$$AR^{2/3} = \frac{28000 (0.028)}{1.49 \sqrt{0.001}} = 6160$$

FLOOD  $AR^{2/3} = 6160$  B-15

R. W. BECK AND ASSOCIATES	CLICK IT AT HATCHERY			PROJECT _____
	FLOOD ELEVATION / IS.			FILE NO. _____
	DESIGN COMP. <del>JK</del>	CHK. _____	REV. _____	PAGE <u>6</u> OF <u>8</u> PAGES
	DATE <u>3/11/92</u>	DATE _____	DATE _____	

CALCULATE NORMAL DEPTH

FIRST TRY

$$Q = 28,000$$

$$S = 0.007$$

$$AR^{2/3} = 6160$$

$$b = 30'$$

$$AR^{2/3} / b^{2/3} = 6160 / 30^{2/3} = 6160 / 8689 = 0.71$$

$$y/b = 0.5$$

REF. CHCW Pg 130

$$y = 0.5 (30) = 15'$$

$$A = 1890 \text{ FT}^2$$

$$P = 236'$$

$$R = 1890 / 236 = 7.97$$

$$AR^{2/3} = 7501$$

$$7501 \neq 6160$$

$\therefore y = 15'$  is too deep.

TRY  $y = 14'$

$$A = 1680 \text{ FT}^2 \quad P = 230$$

$$R = 1680 / 230 = 7.30$$

$$AR^{2/3} = 6324 \neq 6160$$

$\therefore y = 14'$  is too

DEEP ALSO

TRY  $y = 13'$

R. W. BECK AND ASSOCIATES	SLICK PIT HATCHERY			PROJECT	SLICK PIT
	ELEVATIONS			FILE NO.	
	COMP. <u>EB</u>	CHK.	REV.	PAGE	OF 5 PAGES
	DATE <u>2/11/00</u>	DATE	DATE		

USE  $Y = 13'$  PLUS INTO MANNINGS EQ.

$$AR^{2/3} = \frac{Q n}{1.49 \sqrt{S}} = 6160 \quad S = 0.007$$

$$AR^{2/3} / b^{2/3} = 6160 / 30^{2/3} = 0.71 \quad \text{RE: CHOW PG 130}$$

$$y/b = 0.5$$

@  $y = 12'$   $A = 1360$   $P = 223'$

$$R = 1360 / 223 = 6.1$$

RE:  $1.49 \sqrt{S}$

$$A = Q = (1360 / 6.1)^{3/2} = 4540$$

$$4540 \neq 6160$$

∴ FLOOD STAGE THROUGH THIS CROSS SECTION WHEN  $Q_{max} = 29,000$  CFS WILL BE A 13.5' DEPTH,


$$y_n \approx 13.5'$$

USE  $y_n = 13.5'$  ALL ALONG HATCHERY SITE TO ESTABLISH THE ELEVATION OF MAXIMUM FLOOD.

THIS ANALYSIS MUST BE CHECKED AGAINST THE STATISTICAL ANALYSIS OF THE FLOOD RECORD. THE STATISTICAL ANALYSIS FOLLOWS.


# CROSS SECTION OF KLiCKITAT RIVER

B-18



## SECTION AA





SITE PLAN

USGS DATUM MSL = 111.00



GRAPHIC SCALE:



COPYRIGHT 1989 R.W. BECK AND ASSOCIATES. ALL RIGHTS RESERVED.

REV	DATE	BY	APP'D	DESCRIPTION

DATE	BY	APP'D	DESCRIPTION

**R.W. BECK**  
AND ASSOCIATES

Klickitat Salmon and Steelhead Hatchery  
SITE PLAN

1

WV-1715-EA1-AX  
3102

August 1, 1989

MEMORANDUM

TO: Lowell Warren, ~~Project Manager~~ PARTNER IN CHARGE  
FROM: Paul Tappel  
SUBJECT: Klickitat River Salmon and Steelhead Hatchery  
Flood Flow Analysis

INTRODUCTION

A Log-Pearson Type III **distribution** was done to analyze flood flows in the **Klickitat River**, and estimate the **100-year** flood to be used **during design** of the hatchery. Flood flow data for the **Klickitat River** were **obtained** for years **1910-1979** for USGS Gauge No. **14110000**, **Klickitat River** near **Glenwood, Washington**. This gauge is about **10 miles** upstream from the proposed hatchery site, and there are no large **tributaries entering** the **Klickitat River** between the gauge and the hatchery site. Therefore, the **Log-Pearson Type III analysis** presented below should **provide reliable estimates** for flood flows at the hatchery site.

DATA AND CALCULATIONS

Calculations were done as suggested in the following reference:

Linsley, R. K., M. A. Kohler, and J. L. H. Paulhus. 1975. Hydrology for Engineers. McGraw-Hill Book Company. New York, New York.

The maximum annual flood flow observed in the **Klickitat River**, from **1910 to 1979**, is shown in Table 1 along with **calculations** related to the **Log-Pearson Type III analysis**.

The **Log-Pearson Type III analysis** generated the following **predictions** of flood flows for the hatchery site:

100-year flood = 7,900 cfs  
50-year flood = 7,200 cfs  
10-year flood = 5,400 cfs  
2-year flood = 3,200 cfs

TABLE 1: PEAK ANNUAL DISCHARGE DATA AND FLOOD-PROBABILITY ANALYSIS FOR USGS GAGE NUMBER 14110000, KLICKITAT RIVER NEAR GLENWOOD

WATER YEAR	PEAK DISCHARGE IN CFS	ORDER M	PLOTTING POSITION		LOG(CFS)-	LOG(CFS)-	LOG(CFS)-
			LOG(CFS)	LOG(X)	LOG(X)SQ	LOG(X)CU	
1910	6250	4	17.50	3.796	0.296	0.088	0.026
1911	2910	43	1.63	3.464	-0.036	0.001	-0.000
1912	2790	48	1.46	3.446	-0.054	0.003	-0.000
1913	3310	30	2.33	3.520	0.020	0.000	0.000
1914	2890	44	1.59	3.461	-0.039	0.001	-0.000
1915	2200	58	1.21	3.342	-0.157	0.025	-0.004
1916	4620	13	5.38	3.665	0.165	0.027	0.004
1917	3300	31	2.26	3.519	0.019	0.000	0.000
1918	6200	5	14.00	3.792	0.293	0.086	0.025
1919	4600	14	5.00	3.663	0.163	0.027	0.004
1920	1840	63	1.11	3.265	-0.235	0.055	-0.013
1921	3770	21	3.33	3.576	0.077	0.006	0.000
1922	3420	27	2.59	3.534	0.034	0.001	0.000
1923	3160	37	1.89	3.500	0.000	0.000	0.000
1924	2230	57	1.23	3.348	-0.151	0.023	-0.003
1925	3030	41	1.71	3.481	-0.018	0.000	-0.000
1926	1750	64	1.09	3.243	-0.257	0.066	-0.017
1927	4490	15	4.67	3.652	0.153	0.023	0.004
1928	3100	38	1.84	3.491	-0.008	0.000	-0.000
1929	2560	51	1.37	3.408	-0.091	0.008	-0.001
1930	1520	67	1.04	3.182	-0.318	0.101	-0.032
1931	2200	59	1.19	3.342	-0.157	0.025	-0.004
1932	2700	49	1.43	3.431	-0.068	0.005	-0.000
1933	3950	19	3.68	3.597	0.097	0.009	0.001
1934	9870	1	70.00	3.994	0.495	0.245	0.121
1935	2680	50	1.40	3.428	-0.071	0.005	-0.000
1936	3070	39	1.79	3.487	-0.012	0.000	-0.000
1937	2390	54	1.30	3.378	-0.121	0.015	-0.002
1938	3960	18	3.89	3.598	0.098	0.010	0.001
1939	2140	60	1.17	3.330	-0.169	0.029	-0.005
1940	2040	62	1.13	3.310	-0.190	0.036	-0.007
1941	1540	66	1.06	3.188	-0.312	0.097	-0.030
1942	2050	61	1.15	3.312	-0.188	0.035	-0.007
1943	3280	33	2.12	3.516	0.016	0.000	0.000
1944	1220	68	1.03	3.086	-0.413	0.171	-0.071
1945	2380	55	1.27	3.377	-0.123	0.015	-0.002
1946	3210	36	1.94	3.507	0.007	0.000	0.000
1947	3970	17	4.12	3.599	0.099	0.010	0.001
1948	4710	11	6.36	3.673	0.173	0.030	0.005
1949	4710	12	5.83	3.673	0.173	0.030	0.005
1950	3410	28	2.50	3.533	0.033	0.001	0.000
1951	3830	20	3.50	3.583	0.084	0.007	0.001
1952	2810	46	1.52	3.449	-0.051	0.003	-0.000
1953	2830	45	1.56	3.452	-0.048	0.002	-0.000
1954	3380	29	2.41	3.529	0.029	0.001	0.000
1955	3500	26	2.69	3.544	0.044	0.002	0.000
1956	4920	7	10.00	3.692	0.192	0.037	0.007
1958	3700	23	3.04	3.568	0.069	0.005	0.000
1959	2230	56	1.25	3.348	-0.151	0.023	-0.003
1960	2800	47	1.49	3.447	-0.052	0.003	-0.000
1961	3060	40	1.75	3.486	-0.014	0.000	-0.000
1962	2410	53	1.32	3.382	-0.118	0.014	-0.002
1963	5110	6	11.67	3.708	0.209	0.044	0.009
1964	2430	52	1.35	3.386	-0.114	0.013	-0.001
1965	3020	42	1.67	3.480	-0.020	0.000	-0.000
1966	3540	25	2.80	3.549	0.049	0.002	0.000
1967	3280	32	2.19	3.516	0.016	0.000	0.000
1968	3590	24	2.92	3.555	0.055	0.003	0.000
1969	3260	35	2.00	3.513	0.014	0.000	0.000
1970	3260	34	2.06	3.513	0.014	0.000	0.000
1971	4010	16	4.38	3.603	0.104	0.011	0.001
1972	4870	8	8.75	3.688	0.188	0.035	0.007
1973	3770	22	3.18	3.576	0.077	0.006	0.000
1974	7600	2	35.00	3.881	0.381	0.145	0.055
1975	4800	9	7.78	3.681	0.182	0.033	0.006
1976	6550	3	23.33	3.816	0.317	0.100	0.032
1977	835	69	1.01	2.922	-0.578	0.334	-0.193
1978	4800	10	7.00	3.681	0.182	0.033	0.006
1979	1650	65	1.08	3.217	-0.282	0.080	-0.022

SUMS: 241.673 2.247 -0.097


MEAN: 3.500  
 STD DEV: 0.182  
 SKEW COEF: -0.245

DISCUSSION AND SUMMARY

**Klickitat River** data (Table 1) were plotted on log-normal paper to relate river flow data to the Log-Pearson Type III **analysis** (Figure 1). There was an excellent **correlation** between the flow data and the Log-Pearson Type III curve (Figure 10).

The **predicted 100-year** flow of **7,900 cfs** would be reasonable for hatchery design if there were no flood flow data **existing** which exceeded **this** amount. However, a peak flow of **9,870 cfs** was reported for Water Year **1934** (Table 1) and this data **point** was **substantially higher** than predicted by the Log-Pearson Type III analysis (Figure 1).

It **is recommended** that a flood flow of **10,000 cfs** be used for **design** of the **Klickitat Hatchery**. **This** flow is larger than the **100-year** flood **predicted** by the Log-Pearson Type III **analysis**, and is also **slightly** larger than the maximum recorded flood **during a 70-year period** of record for the **Klickitat River**.



---

Paul Tappel  
Civil Engineer

cc: Jay Kidder

(L7508C)




FIGURE 1: FLOOD FREQUENCY CURVE FOR THE CLICKITAT RIVER NEAR GLENWOOD, WASHINGTON.

R. W. BECK AND ASSOCIATES	Klickitat River			PROJECT
	Klickitat River			FILE NO.
	COMP. <u>JK</u>	CHK. _____	REV. _____	PAGE <u>8</u> OF <u>8</u> PAGES
	DATE <u>8/11/87</u>	DATE _____	DATE _____	

THE MEMORANDUM DATED 2/1/80 AND TITLED FLOOD FLOW ANALYSIS CONCLUDES THAT THE 100, 50, 10, AND 2 YEAR FLOODS ARE;

100 YR.	-	7,900 CFS
50 YR	-	7,200 CFS
10 YR	-	5,400 CFS
2 YR	-	3,200 CFS.

THEFORE, THE PRECEDING ANALYSIS THAT USES  $Q_{max} = 2Q_{100}$ , OR  $Q_{max} = 4 Q_{10}$  WHERE  $4 = FS$ , IS VERY CONSERVATIVE.

THE NORMAL DEPTH OF  $y_n = 12.5'$  IS

ALSO CONSERVATIVE AND RESULTS IN ABOUT A 10' CHANGE IN STAGE ALL ALONG THE WATCHKAY SITE. ENGINEERS AND THE CITY LEGISLATURE MUST CONSIDER THE FOLLOWING;


100 YR FLOOD,  $Q_{100} = 7,900$  CFS  
 100 YR FLOOD STAGE TO BE  $y_n = 12.5'$  @ SECTION AA AND A 10.0' INCREASE IN DEPTH OF THE KLICKITAT RIVER

APPENDIX C  
FLOOD STAGE ANALYSIS

R. W. BECK AND ASSOCIATES	KUKKITA HATCHERY PREDESIGN			PROJECT
	RIVER FLOOD STAGE			FILE NO.
	COMP. <u>JB</u>	CHK.	REV.	PAGE <u>1</u> OF <u>2</u>
	DATE <u>4/2/81</u>	DATE	DATE	

I PURPOSE: TO CALCULATE THE RIVER FLOOD STAGE AT THE PROPOSED HATCHERY SITE THE RIVER STAGE WAS MEASURED WITH SURVEY INSTRUMENTS AND A CROSS SECTION WAS DEVELOPED AT THE SECTION VISUALLY CHOSEN TO BE THE CRITICAL SECTION FOR HYDRAULIC CONTROL IN FRONT OF THE HATCHERY SITE.


II SITE DESCRIPTION



SITE PLAN  
SCALE: NONE

SECTION AA IS CHOSEN AS THE CRITICAL SECTION.

NUMBERS INDICATE SURVEY STATIONS



SCHMATIC SECTION AA  
SCALE: NONE

R. W. BECK AND ASSOCIATES	KLICKITZ HATCHERY PREDESIGN			PROJECT	KLICKITZ
	FLOOD STAGE CALCULATION			FILE NO.	
	COMP.	CHK.	REV.	PAGE	2 OF 5 PAGES
	DATE	DATE	DATE		

SURVEY NOTES

SECTION AA

NUMBER OF STA	HORIZ $\Delta$	HORIZ DIST	VERT DIST	ELEV	COMMENT
1	183° 48' 37"	47.63	-0.53	1274.52	
2	209° 59' 03"	59.75	-24.20	1250.85	
3	215° 18' 14"	71.61	-27.62	1247.43	
4	233° 34' 49"	100.19	-26.82	1245.23	
5	239° 37' 19"	107.10	-26.13	1245.42	
6	241° 24' 10"	120.81	-24.07	1251.75	
7	243° 45' 02"	132.75	-22.73	1252.23	
8	247° 23' 24"	148.13	-21.67	1253.38	
9	248° 22' 55"	151.29	-19.71	1255.34	
10	249° 34' 51"	154.6	-17.12	1257.93	
11	252° 40' 45"	167.45	-17.42	1257.63	
12	250° 01' 21"	260.49	-17.64	1257.41	
13	251° 28' 48"	268.05	-13.13	1261.92	
14	249° 24' 34"	298.42	-4.14	1270.91	
15	248° 32' 42"	320.43	0.64	1274.41	

AREA OF WATER CROSS SECTION = 137.8 FT<sup>2</sup>

ASSUMPTIONS

1. ASSUME THE FLOW IN THE RIVER IS GRADUALLY VARIED OR CONSTANT. DURING THE INSTANT OF ANALYSIS
2. ASSUME THE CROSS SECTION AA IS PERPENDICULAR TO THE FLOW STREAMLINES
3. USE MANING'S EQUATION TO DESCRIBE THE FLOW IN THIS CROSS SECTION.

R. W. BECK AND ASSOCIATES	Klickitt HATCHERY REDESIGN			PROJECT	Klickitt
	FLOOD STAGE CALCULATION.			FILE NO.	
	COMP. <u>FB</u>	CHK. _____	REV. _____	PAGE <u>3</u>	OF <u>3</u> PAGES
	DATE <u>6/2/89</u>	DATE _____	DATE _____		

IV CALCULATE HYDRAULIC PARAMETERS OF SECTION AA

DETERMINE Q

ESTIMATED AVERAGE Q @ SECTION AA

AND VERIFIED BY IFIM RECORDS OF USFWS 5/89 MEASUREMENTS.

REF DONENGIN VASQUEZ

$\bar{Q} \approx 900$  CFS

A FACTOR OF 4 OF AVG Q AND MAXIMUM Q IS GIVEN BY BELL, 1989 ; FISHERIES WATERWAY USCOE.

$\bar{Q}_{MAX} = 7.72 \bar{Q}$  EASTERN US COAST

$\therefore$  IF  $\bar{Q} = 900$  CFS

$\bar{Q}_{MAX} = 7.72(900) = 6940$  CFS

USE  $\bar{Q}_{DES} = 7000$  CFS

WITHOUT FURTHER IN DEPTH PROBABILITY ANALYSIS AT THIS POINT USE A FACTOR OF SAFETY OF 4.

FS = 4

$Q_{MAX} = (7000)(4) = 28,000$  CFS

USE THE FOLLOWING FLOWS FOR ANALYSIS:

$\bar{Q} \approx 900$  CFS

$\bar{Q}_{DES} \approx 7000$  CFS

$Q_{MAX} = 28,000$  CFS

R. W. BECK AND ASSOCIATES	KLICKIT - HATCHERY PREDESIGN			PROJECT	KLICKIT
	FLOW STAGE CALCULATION			FILE NO.	
	COMP. <u>  </u>	CHK. <u>  </u>	REV. <u>  </u>	PAGE	4 OF 8 PAGES
	DATE <u>  </u>	DATE <u>  </u>	DATE <u>  </u>		

NOTE ALSO THAT IN THE USFWS, 1979 FEASIBILITY STUDY, THE TWO FLOODS OF RECORD NEAR GLENWOOD AT RIVER MILE 50.3 WERE IN 1933 AND 1978 AND MEASURED 9.370 CFS AND 9.300 CFS RESPECTIVELY.

THE PROPOSED HATCHERY SITE IS LOCATED AT RIVER MILE ~ 41.0

ASSUME MANNING'S n

ASSUME  $n = 0.028$

REF. CHOW, OPEN CHANNEL HYDROLOGY 1959 PG 110.

ONE FORM OF MANNING'S EQUATION:

$$AR^{2/3} = \frac{Qn}{1.49\sqrt{S}}$$

- A = AREA OF WETTED CROSS SECTION
- R = HYDRAULIC RADIUS =  $A/P$
- Q = FLOW RATE
- S = REACH SLOPE

REACH SLOPE WAS MEASURED TO BE  $S = 0.007$

FOR SECTION AA

APRIL 13, 1982

A = 137.3 FT<sup>2</sup>

P = 61 FT

R = 2.26

t = 30' = BOTTOM WIDTH

R. W. BECK AND ASSOCIATES				PROJECT <u>KLICKE T</u>
				FILENO. _____
	COMP. _____	CHK. _____	REV. _____	PAGE <u>5</u> OF <u>8</u> PAGES
	DATE _____	DATE _____	DATE _____	

CHECK GIVEN DIMENSIONS TO GIVEN  $\phi$

$$AR^{2/3} = \frac{Q n}{1.49 \sqrt{S}}$$

$$137.8 \text{ FT}^3 / (2.26)^{2/3} = \frac{(900)(0.028)}{1.49 \sqrt{0.007}}$$

$$237.31 = 202.15 \quad \text{DOES NOT EQUAL}$$

$$\therefore Q = 900 \text{ CFS IS LOW}$$

$$\text{TRY } C = 1000 \text{ CFS}$$

$$237.31 = 1000 (0.22)$$

$$237.31 = 224.61 \quad \text{LOWER}$$

$$\text{TRY } C = \quad \text{CFS}$$

$$237.31 = 1078 (0.22)$$

$$237.31 = 237.31 \quad \text{OK } \checkmark$$

$$Q = 1078$$

$$\therefore \bar{Q}_{\text{MAX}} \text{ \& } Q_{\text{MAX}} \text{ ARE OK.}$$

SOLVE FOR  $AR^{2/3}$  AT  $Q_{\text{MAX}} = 28000 \text{ CFS}$

$$1.49 \sqrt{S} = \frac{28000 (0.028)}{1.49 \sqrt{0.007}} = 6160$$

$$\text{FLOOD } 1.49 \sqrt{S} = 6160^{0.6}$$

R. W. BECK AND ASSOCIATES	KLUCKITZ HATCHERY			PROJECT _____
	FLOOD ELEVATIONS			FILE NO. _____
	COMP. <u>  </u>	CHK. _____	REV. _____	PAGE <u>6</u> OF <u>8</u> PAGES
	DATE <u>3/1/80</u>	DATE _____	DATE _____	

CALCULATE NORMAL DEPTH

FIRST TRY

$Q = 28,000$

$S = 0.007$

$AR^{2/3} = 6160$

$D = 30'$

$R^{2/3} / D^2 = 6160 / 30^{2/3} = 6160 / 8689 = 0.71$

$y/D = 0.5$

REF. CL 311 Pg 130

$y = 0.5 (30) = 15'$

$A = 1950 \text{ FT}^2$   
 $AR^{2/3} = 7501$

$P = 236'$

$R = 1950 / 236 = 7.07$

$7501 \neq 6160 \therefore y = \text{depth is too deep.}$

TRY  $y = 14'$

$A = 1680 \text{ FT}^2$      $P = 230$

$R = 1680 / 230 = 7.30$

$AR^{2/3} = 6324 \neq 6160 \therefore y = 14' \text{ is OK}$

DEPTH ALSO

TRY  $y = 13'$

R. W. BECK AND ASSOCIATES	ELEVATIONS			PROJECT
	DESIGNER	CHK.	REV.	FILE NO.
	DATE	DATE	DATE	PAGE OF PAGES

USE  $Y = 13'$  PLUG INTO MANNINGS EQ.

$$AR^{2/3} = \frac{Q N}{1.49 \sqrt{S}} = 6160 \quad S = 0.07$$

$$AR^{2/3} / 1.49 \sqrt{S} = 6160 / 1.49 \sqrt{0.07} = 0.71 \quad \text{PER: CHECK 43 120}$$

$$C/A = 0.5$$

$$Q = 1360 \quad A = 160 \quad P = 203'$$

$$R = 1360 / 203 = 6.7$$

$$1360 (6.7)^{2/3} = 4540$$

$$4540 \neq 6160$$

FLOOD STAGE THROUGH THIS CROSS SECTION AFTER  $Q_{max} = 2800 CFS$  WILL BE APPROXIMATELY


$$Y \approx 13.5'$$

USE  $Y = 13.5'$  ALL ALONG HATCHERY SITE TO

ESTABLISH THE ELEVATION OF MAXIMUM FLOOD.

THIS ANALYSIS MUST BE CHECKED AGAINST THE STATISTICAL ANALYSIS OF THE SURFACE FLOOD. THE STATISTICAL ANALYSIS FOLLOWS.

# CROSS SECTION OF KLICKITAT RIVER



## SECTION AA



August 1, 1989

MEMORANDUM

TO: Lowell ~~Warren, Project Manager~~ **PARTNER IN CHARGE**  
FROM: Paul Tappel  
SUBJECT: Klickitat River Salmon and Steel head Hatchery  
Flood Flow Analysis

INTRODUCTION

A Log-Pearson Type III **distribution** was done to analyze flood flows in the **Klickitat River**, and estimate the **100-year** flood to be used **during** design of the hatchery. Flood flow data for the **Klickitat River** were **obtained** for years **1910-1979** for USGS Gauge No. **14110000**, **Klickitat River** near **Glenwood, Washington**. This gauge is about **10 miles** upstream from the proposed hatchery site, and there are no large **tributaries entering** the **Klickitat River** between the gauge and the hatchery **site**. Therefore, the **Log-Pearson Type III analysis** presented below should **provide reliable** estimates for flood flows at the hatchery **site**.

DATA AND CALCULATIONS

**Calculations** were done as suggested in the following reference:

**Linsley, R. K., M. A. Kohler, and J. L. H. Paulhus. 1975.** Hydrology for Engineers. McGraw-Hill Book **Company**, New York, New York.

The maximum annual flood flow observed in the **Klickitat River**, from **1910 to 1979**, is shown in Table 1 along **with calculations** related to the **Log-Pearson Type III analysis**.

The Log-Pearson Type III analysis generated the following **predictions** of flood flows for the hatchery **site**:

**100-year flood = 7,900 cfs**  
**50-year flood = 7,200 cfs**  
**10-year flood = 5,400 cfs**  
**2-year flood = 3,200 cfs**

TABLE 1: PEAK ANNUAL DISCHARGE DATA AND FLOOD-PROBABILITY ANALYSIS FOR USGS GAGE NUMBER 14110000, KLICKITAT RIVER NEAR GLENWOOD

WATER YEAR	PEAK DISCHARGE IN CFS	ORDER M	PLOTTING POSITION	LOG(CFS)	LOG(CFS)-LOG(X)	LOG(CFS)-LOG(X)SQ	LOG(CFS)-LOG(X)CU
1910	6250	4	17.50	3.796	0.296	0.088	0.026
1911	2910	43	1.63	3.464	-0.036	0.001	-0.000
1912	2790	48	1.46	3.446	-0.054	0.003	-0.000
1913	3310	30	2.33	3.520	0.020	0.000	0.000
1914	2890	44	1.59	3.461	-0.039	0.001	-0.000
1915	2200	58	1.21	3.342	-0.157	0.025	-0.004
1916	4620	13	5.38	3.665	0.165	0.027	0.004
1917	3300	31	2.26	3.519	0.019	0.000	0.000
1918	6200	5	14.00	3.792	0.293	0.086	0.025
1919	4600	14	5.00	3.663	0.163	0.027	0.004
1920	1840	63	1.11	3.265	-0.235	0.055	-0.013
1921	3770	21	3.33	3.576	0.077	0.006	0.000
1922	3420	27	2.59	3.534	0.034	0.001	0.000
1923	3160	37	1.89	3.500	0.000	0.000	0.000
1924	2230	57	1.23	3.348	-0.151	0.023	-0.003
1925	3030	41	1.71	3.481	-0.018	0.000	-0.000
1926	1750	64	1.09	3.243	-0.257	0.066	-0.017
1927	4490	15	4.67	3.652	0.153	0.023	0.004
1928	3100	38	1.84	3.491	-0.008	0.000	-0.000
1929	2560	51	1.37	3.408	-0.091	0.008	-0.001
1930	1520	67	1.04	3.182	-0.318	0.101	-0.032
1931	2200	59	1.19	3.342	-0.157	0.025	-0.004
1932	2700	49	1.43	3.431	-0.068	0.005	-0.000
1933	3950	19	3.68	3.597	0.097	0.009	0.001
1934	9870	1	70.00	3.994	0.495	0.245	0.121
1935	2680	50	1.40	3.428	-0.071	0.005	-0.000
1936	3070	39	1.79	3.487	-0.012	0.000	-0.000
1937	2390	54	1.30	3.378	-0.121	0.015	-0.002
1938	3960	18	3.89	3.598	0.098	0.010	0.001
1939	2140	60	1.17	3.330	-0.169	0.029	-0.005
1940	2040	62	1.13	3.310	-0.190	0.036	-0.007
1941	1540	66	1.06	3.188	-0.312	0.097	-0.030
1942	2050	61	1.15	3.312	-0.188	0.035	-0.007
1943	3280	33	2.12	3.516	0.016	0.000	0.000
1944	1220	68	1.03	3.086	-0.413	0.171	-0.071
1945	2380	55	1.27	3.377	-0.123	0.015	-0.002
1946	3210	36	1.94	3.507	0.007	0.000	0.000
1947	3970	17	4.12	3.599	0.099	0.010	0.001
1948	4710	11	6.36	3.673	0.173	0.030	0.005
1949	4710	12	5.83	3.673	0.173	0.030	0.005
1950	3410	28	2.50	3.533	0.033	0.001	0.000
1951	3830	20	3.50	3.583	0.084	0.007	0.001
1952	2810	46	1.52	3.449	-0.051	0.003	-0.000
1953	2830	45	1.56	3.452	-0.048	0.002	-0.000
1954	3380	29	2.41	3.529	0.029	0.001	0.000
1955	3500	26	2.69	3.544	0.044	0.002	0.000
1956	4920	7	10.00	3.692	0.192	0.037	0.007
1958	3700	23	3.04	3.568	0.069	0.005	0.000
1959	2230	56	1.25	3.348	-0.151	0.023	-0.003
1960	2800	47	1.49	3.447	-0.052	0.003	-0.000
1961	3060	40	1.75	3.486	-0.014	0.000	-0.000
1962	2410	53	1.32	3.382	-0.118	0.014	-0.002
1963	5110	6	11.67	3.708	0.209	0.044	0.009
1964	2430	52	1.35	3.386	-0.114	0.013	-0.001
1965	3020	42	1.67	3.480	-0.020	0.000	-0.000
1966	3540	25	2.80	3.549	0.049	0.002	0.000
1967	3280	32	2.19	3.516	0.016	0.000	0.000
1968	3590	24	2.92	3.555	0.055	0.003	0.000
1969	3260	35	2.00	3.513	0.014	0.000	0.000
1970	3260	34	2.06	3.513	0.014	0.000	0.000
1971	4010	16	4.38	3.603	0.104	0.011	0.001
1972	4870	8	8.75	3.688	0.188	0.035	0.007
1973	3770	22	3.18	3.576	0.077	0.006	0.000
1974	7600	2	35.00	3.881	0.381	0.145	0.055
1975	4800	9	7.78	3.681	0.182	0.033	0.006
1976	6550	3	23.33	3.816	0.317	0.100	0.032
1977	835	69	1.01	2.922	-0.578	0.334	-0.193
1978	4800	10	7.00	3.681	0.182	0.033	0.006
1979	1650	65	1.08	3.217	-0.282	0.080	-0.022
SUMS:				241.473		2.247	-0.097
MEAN:				3.500			
STD DEV:				0.182			
SKEW COEF:				-0.245			

DISCUSSION AND SUMMARY

**Klickitat** River data (Table 1) were plotted on log-normal paper to relate river flow data to the Log-Pearson Type III analysis (Figure 1). There was an excellent **correlation** between the flow data and the Log-Pearson Type III curve (Figure 10).

The **predicted 100-year** flow of **7,900 cfs** would be reasonable for hatchery **design** if there were no flood flow data **existing** which exceeded **this** amount. However, a peak flow of **9,870 cfs** was reported for Water Year **1934** (Table 1) and this data point was **substantially** higher than **predicted** by the Log-Pearson Type III analysis (Figure 1).

It is **recommended** that a flood flow of **10,000 cfs** be used for design of the **Klickitat** Hatchery. This flow is larger than the **100-year** flood predicted by the Log-Pearson Type III analysis, and is also **slightly** larger than the maximum recorded flood during a **10-year period** of record for the **Klickitat** River.

*Paul Tappel*

---

Paul Tappel  
Civil Engineer

cc: Jay Kidder

(L7508C)




FIGURE 1: FLOOD FREQUENCY CURVE FOR THE KLICKITAT RIVER NEAR GLENWOOD, WASHINGTON.

R. W. BECK AND ASSOCIATES	PROJECT _____		
	FILE NO. _____		
	COMP. <u>JK</u>	CHK. _____	REV. _____
	DATE <u>6/4/07</u>	DATE _____	DATE _____
PAGE <u>8</u> OF <u>2</u> PAGES			

THE PREVIOUS DATE 8/1/07 AND THE FLOOD FLOW ANALYSIS CONCLUDES THAT THE 100, 50, 10, AND 2 YEAR FLOOD FLOWS:

100 YR	-	7,900 CFS
50 YR	-	7,200 CFS
10 YR	-	5,400 CFS
2 YR	-	3,200 CFS

THE FLOOD FLOW, THE PREVIOUS ANALYSIS - 477 CFS  $Q_{max} = 2Q_{100}$ , OR  $Q_{max} = 4 Q_{100}$  WHERE  $A = FS$ , IS VERY CONSERVATIVE.

THE NORMAL DEPTH OF  $U_n = 13.5'$

IS CONSERVATIVE AND RESULTS IN ABOUT A 10% CHANGE IN STAGE ALL ACROSS THE PROJECT SITE. ENGINEERS AND ARCHITECTS MUST CONSIDER THE FOLLOWING:

100 YR FLOOD,  $Q_{100} = 7100$  CFS  
 100 YR FLOOD STAGE TO BE  $U_n = 13.5'$  @ SECTION 1A AND A 10.0' INCREASE IN DEPTH OF THE KLICKITAT RIVER

**APPENDIX D**

**U. S. BUREAU OF RECLAMATION  
RAW WATER QUALITY DATA**

STORET RETRIEVAL DATE 49/11/02

PGM=ALLPARM

KLI112  
 45 21 54.0 121 10 20.0 3  
 KLUCKITAT RIVER 1 MI ABV PISCOE CK CONFLUENCE  
 53077 WASHINGTON YAKIMA  
 PACIFIC NORTHWEST 130400  
 YAKIMA RIVER  
 1110USER 890506 1707J106  
 0000 FEET DEPTH 988 METERS ELEVATION

ZTTPZINENTZSTELAN

INITIAL DATE		89/04/26		89/06/21		INITIAL DATE		89/04/26		89/06/21	
INITIAL TIME		0000		1045		INITIAL TIME		0000		1045	
MEDIUM		WATER		WATER		MEDIUM		WATER		WATER	
00010	WATER	TEMP	5.0	6.9	01045	IRON	FE,TOT	UG/L			120
00011	WATER	TEMP	41.05	44.41	01051	LEAD	PB,TOT	UG/L			20
00021	STREAM	FLOW	200J	160J	01055	MANGNESE	MN	UG/L			10.0
00072	TURB	TRYSUMTR	2.0	1.00	01061	NICKEL	NI,TOTAL	UG/L			100
00094	CONDUCTIVY	FIELD	70		01077	SILVER	AG,TOT	UG/L			2.00
00095	CONDUCTIVY	AT 25C		53	01092	ZINC	ZN,TOT	UG/L			100
00300	DU		10.9	11.7	01105	ALUMINUM	AL,TOT	UG/L			3
00301	DU	SATUR	65.25	75.94	01147	SELENIUM	SE,TOT	UG/L			100
00335	COU	LOWLEVEL	4.0	4.0	46570	CAL HARD	CA MG	MG/L	237		205
00400	PH			7.21	70501	DISS SOL	SOL	MG/L	50		4
00405	PH	LAB	7.4		71700	MERCURY	HG,TOTAL	UG/L			120
00440	HCO3 ION	HCO3	30	26							
00445	CO3 ION	CO3	0	0							
00520	RESIDUE	TOT NFLT	8	2							
00605	NH3+NH4-	N DISS	.010	.0100							
00512	NH-IONZD	NH3-N	.000033	.000025							
00519	NH-IONZD	NH3-NH3	.000033	.000025							
00625	TOT NITR	N	.100	.100							
00551	NITRATES	N-DISS	.010	.1K							
00665	PHOS-TOT		.026	.025							
00671	PHOS-DIS	ORTAD	.009	.008							
00915	CALCIUM	CA,DISS	6.4	5.6							
00925	MAGNESIUM	MG,DISS	1.6	1.3							
00930	SODIUM	NA,DISS	2.30	2.07							
00921	SODIUM	ABSTION	.2	.2							
00925	POTASSIUM	K,DISS	.86	.78							
00940	CHLORIDE	TOTAL	.4	.4							
00946	SULFATE	SO4-DISS	1.9	2.4							
00950	FLUORIDE	F,DISS		.10K							
00955	SILICA	DISOLVED	21.0	18.4							
01002	ARSENIC	AS,TOT		5U							
01007	BARIUM	BA,TOT		5U							
01027	CADMIUM	CD,TOT		.5U							
01034	CHROMIUM	CR,TOT		2U							
01042	COPPER	CU,TOT		5U							

D-2

KLI104

46 02 23.0 121 11 00.0 3

KLICKITAT RIVER AT WDF FISH HATCHERY S4 6N 13E

53039 WASHINGTON KLICKITAT

PACIFIC NORTHWEST 131090

COLUMBIA RIVER BELOW YAKIMA RIVER

1119548 890127 17070106027 0002.840 01

0000 FEET D.PTH 387 METERS ELEVATION

7176AZ44ENTZSTREAN

-----				-----						
INITIAL DATE				8/24/20	8/26/21	INITIAL DATE				
INITIAL TIME				0000	1455	0000	1455			
MEDIUM				WATER	WATER	WATER	WATER			
00010	WATER	TEMP	CENT	8.9	13.4	01051	LEAD	PB,TOT	UG/L	0.0
00011	WATER	TEMP	FRAIN	48.04	56.15	01055	MANGANESE	PI	UG/L	10.0
00061	SPLASH	FLOW	INST-CFS		350J	01067	NICKEL	NI,TOTAL	UG/L	100
00075	TURB	TRIBUTMTR	HACH FTU	3.0	2.0	01077	SILVER	AG,TOT	UG/L	2.0J
00084	CONDUCTIV	FIELD	MICROMHO	72	58	01092	ZINC	ZN,TOT	UG/L	100
00300	DU		MG/L	11.3	10.6	01105	ALUMINIUM	AL,TOT	UG/L	0
00301	DU	SATUR	PERCENT	97.44	100.00	01147	SELENIUM	SE,TOT	UG/L	100
00335	DU	LOWLEVEL	MG/L	6.0	3.0	46570	CAL HARD	CA HG	MG/L	213
00400	PH		SU		7.32	70301	DISS SIL	SU	UG/L	15
00405	PH	LAG	SU	7.7		71201	COBALT	MG,TOTAL	UG/L	0.0
00440	HC03 ION	HC03	MG/L	30	32					
00445	CO3 ION	CO3	MG/L	0	0					
00530	RESIDUE	TOT NFLT	MG/L	15	12					
00568	NH3+NH4-	N DISS	MG/L	.0100	.0100					
00512	NH-1NH2O	NH3-N	MG/L	.000074	.000044					
00519	NH-1NH2O	NH3-NH3	MG/L	.000084	.000054					
00625	TOT KjEL	N	MG/L	.110	.100					
00651	NO2&NO3	N-DISS	MG/L	.010	.1K					
00665	PHOS-TOT		MG/L P	.036	.049					
00671	PHOS-DIS	ORTHO	MG/L P	.016	.021					
00715	CALCIUM	CA,DISS	MG/L	5.2	4.8					
00725	MAGNESIUM	MG,DISS	MG/L	1.9	2.1					
00720	SODIUM	NA,DISS	MG/L	2.76	2.99					
00731	SODIUM	ADSETIUM	RATIO	.3	.2					
00735	POTASSIUM	K,DISS	MG/L	1.10	1.17					
00740	CHLORIDE	TOTAL	MG/L	.5	.4					
00745	SULFATE	SO4-DISS	MG/L	1.9	2.4					
00750	FLUORIDE	F,DISS	MG/L		.10K					
00955	SILICA	DISOLVED	MG/L	24.6	25.1					
01002	ARSENIC	AS,TOT	UG/L		50					
01007	BARIUM	BA,TOT	UG/L		50					
01027	CADMIUM	CD,TOT	UG/L		.50					
01034	CHROMIUM	CR,TOT	UG/L		20					
01042	COPPER	CU,TOT	UG/L		50					
01045	IRON	FE,TOT	UG/L		130					

D-3

KLI902  
 46 01 06.0 121 09 21.0 3  
 CASCADE SPRINGS NR KCLICKITAT R AT RM 40  
 53039 WASHINGTON KCLICKITAT  
 PACIFIC NORTHWEST 131000  
 COLUMBIA RIVER BELOW YAKIMA RIVER  
 1119USBR 880827 17070106027 0000.340 OFF  
 0000 FEET DEPTH 357 METERS ELEVATION

/TTPA/MSNT/SPRING

INITIAL DATE				89/06/20
INITIAL TIME				1245
MEDIUM				WATER
00010	WATER	TEMP	CENT	7.3
00011	WATER	TEMP	FAHN	45.14
00025	BAROMTRC	PRESSURE	MM O F HG	738
00076	TURB	TURBIDMTR	HACH FTU	1.00
00094	CNOUCTVY	FIELD	MICROMHO	70
00300	DD		MG/L	11.9
00301	DD	SATUR	PERCENT	101.9
00335	CO2	LOWLEVEL	MG/L	1.00
00400	PH		SU	7.62
00405	CO2		MG/L	1.8
00410	T ALA	CACO3	MG/L	38
00440	HCO3 I O N	HCO3	MG/L	46
00445	CO3 I O N	CO3	MG/L	0
00530	RESIDUE	TOT NFLT	MG/L	10
00556	OIL-GRSE	FREON-CR	MG/L	1.000
00608	NH3+NH4-	N DISS	MG/L	.0100
00612	UN-IONZD	NH3-N	MG/L	.000054
00613	UN-IONZD	NH3-NH3	MG/L	.000064
00625	TOT KJEL	N	MG/L	.030
00631	NU2GN03	N-DISS	MG/L	.2
00665	PHOS-TOT		MG/L P	.046
00671	PHOS-DIS	ORTHO	MG/L P	.037
00913	CALCIUM	CA,DISS	MG/L	5.8
00925	MGNSIUM	MG,DISS	MG/L	3.3
00930	SODIUM	NA,DISS	MG/L	3.68
00931	SODIUM	ADSBTIUM	RATIO	.3
00935	PTSSIUM	K,DISS	MG/L	1.96
00940	CHLORIDE	TOTAL	MG/L	.4
00946	SULFATE	S04-DISS	MG/L	.5
00950	FLUORIDE	F,DISS	MG/L	.10K
00955	SILICA	DISOLVED	MG/L	35.7
01002	ARSENIC	AS,TOT	UG/L	50
01007	BARIUM	BA,TOT	UG/L	50
01027	CADMIUM	CD,TOT	UG/L	.50
01034	CHROMIUM	CR,TOT	UG/L	20

INITIAL DATE				89/06/20
INITIAL TIME				1245
MEDIUM				WATER
01042	COPPER	CU,TOT	UG/L	50
01045	IRON	FE,TOT	UG/L	10
01051	LEAD	PB,TOT	UG/L	2K
01055	MANGNESE	MN	UG/L	5.0
01067	NICKEL	NI,TOTAL	UG/L	100
01077	SILVER	AG,TOT	UG/L	2.00
01092	ZINC	ZN,TOT	UG/L	100
01105	ALUMINUM	AL,TOT	UG/L	10
01147	SELENIUM	SE,TOT	UC/L	100
46570	CAL HARD	CA MG	MG/L	288
50064	CHLORINE	FREE AVL	MG/L	.010
70301	DISS SOL	SUN	MG/L	75
71875	H2S		MG/L	.010
71900	MERCURY	HG,TOTAL	UC/L	.20
73004	NIT + A R	GAS SATR	Z SAT	100.0
74041	WQF	SAMPLE	UPDATED	890914

D-4

KLI908  
 46 01 42.0 121 09 50.0 4  
 KIDDER SPRINGS NR KCLICKITAT R AT RM 41  
 53039 WASHINGTON KCLICKITAT  
 PACIFIC NORTHWEST 131000  
 COLUMBIA RIVER BELOW YAKIMA RIVER  
 1119USBR 890701 17070106  
 0000 FEET DEPTH

/TTPA/AMBNT/SPRING

INITIAL DATE			89/06/20
INITIAL TIME			1135
MEDIUM			WATER
00010	WATER	TEMP	7.3
00011	WATER	TEMP	45.18
00025	BAROMTRC	PRESSURE	739
00076	TURB	TRSDMTR	1.00
00094	CNDUCTVY	FIELD	72
00300	DO	MC/L	11.8
00301	DO	SATUR	100.9
00335	COO	LOWLEVEL	1.00
00400	PM	SU	7.03
00405	CO2	MG/L	6.7
00410	T ALK	MG/L	36
00440	MC031 O N	HCO3	44
00445	CO3 ION	CO3	0
00530	RESIDUE	TOT NFLT	1U
00556	OIL-GRSE	FREON-CR	1.00U
00608	NH3+NH4-	N DISS	.010U
00612	UN-IONZD	NH3-N	.000018
00619	UN-IONZD	NH3-NH3	.000028
00625	TOT KJEL	N	.020
00631	NO2&NO3	N-DISS	.1
00665	PHOS-TOT	MG/L P	.060
00671	PHOS-DIS	MG/L P	.035
00915	CALCIUM	CA,DISS	5.6
00925	MGNSIUM	MG,DISS	3.2
00930	SODIUM	NA,DISS	3.68
00931	SODIUM	ADSBTION	RATIO
00935	PTSSIUM	K,DISS	1.96
00940	CHLORIDE	TOTAL	.4
00946	SULFATE	SO4-DISS	.5
00950	FLUORIDE	F,DISS	MC/L
00955	SILICA	DISOLVED	MG/L
01002	ARSENIC	AS,TOT	UC/L
01007	JARIUM	BA,TOT	UG/L
01027	CADMIUM	CD,TOT	UC/L
01034	CHROMIUM	CR,TOT	UC/L

D-5

INITIAL DATE			89/06/20
INITIAL TIME			1135
MEDIUM			WATER
01042	COPPER	CU,TOT	UC/L
01045	IRON	FE,TOT	UC/L
01051	LEAD	PB,TOT	UC/L
01055	MANGNESE	MN	UG/L
01067	NICKEL	NI,TOTAL	UG/L
01077	SILVER	AG,TOT	UG/L
01092	ZINC	ZN,TOT	UG/L
01105	ALUMINUM	AL,TOT	UG/L
01147	SELENIUM	SE,TOT	UG/L
46570	CAL HARD	CA MG	MG/L
50064	CHLORINE	FREE AVL	MG/L
70301	DISS SOL	SUM	MG/L
71875	H2S		MG/L
71900	MERCURY	HG,TOTAL	UC/L
73004	NIT + AR	GAS SATR	% SAT
74041	WQF	SAMPLE	UPDATED

100.0  
890914

**APPENDIX E**  
**HATCHERY EQUIPMENT LIST**

HATCHERY EQUIPMENT LIST BY FUNCTION

Function and Equipment	Estimated cost
<b>A. TRANSPORTATION, FISH AND PERSONNEL</b>	
1. Fish Plant Truck, <b>2-1/2</b> Ton with <b>Fish</b> Tank .....	\$ 85,000
2. <b>Pickup</b> Truck, <b>1/2</b> Ton, <b>4WD</b> .....	12,000
3. Pickup Truck, 1 Ton with Fish Tank, <b>4WD</b> .....	18,000
4. <b>CB Mobile</b> Units .....	240
5. Boat <b>Suitable</b> for Need and Trailer .....	4,500
6. Tractor/Hoe, Broom, Loader and Mower .....	15,660
7. <b>CB</b> Base Station .....	150
8. <b>CB</b> Antenna .....	76
Subtotal .....	\$135,626
<b>B. MAINTENANCE OF GROUNDS - FACILITIES</b>	
1. Sludge Pump and <b>3-Inch-Diameter</b> Hose .....	1,944
2. Ladders, Step and <b>Extension</b> .....	252
3. Push Brooms .....	15
4. Power Broom for Snow <b>Blowing</b> .....	774
5. Plumbing Snake .....	200
Subtotal .....	\$ 3,185
<b>MAINTENANCE OF GROUNDS - EQUIPMENT</b>	
1. Hydraulic Jack, <b>12</b> Ton .....	206
2. Battery Charger, 6 and <b>12</b> Volts, <b>10</b> Amp .....	52
3. Booster Cables, <b>12</b> Volt x <b>25 ft</b> long .....	41
4. Grease Gun .....	22
5. Auto Creeper .....	23
6. <b>Oil</b> and Gasoline Containers .....	102
7. Funnels (Various <b>Sizes</b> ) .....	16
Subtotal .....	\$ 462
<b>MAINTENANCE OF GROUNDS - GENERAL</b>	
1. <b>Woodworking</b> Hand Tools .....	499
2. Metalworking Hand Tools .....	200
3. <b>Welding</b> Equipment and Clothing .....	200
4. Portable Emergency Generator .....	550
5. Portable Emergency Lighting .....	66
6. Gas Welder .....	290
7. Arc Welder .....	300
8. Wood Vise .....	90
9. Drill Press and <b>Vise</b> .....	145

HATCHERY EQUIPMENT LIST BY FUNCTION

Function and Equipment	Estimated cost
MAINTENANCE OF GROUNDS - GENERAL (cont.)	
10. Band Saw .....	\$ 145
11. Face Shield .....	19
12. Metal Vise with Cinch .....	80
13. Table Saw .....	400
14. Flammable Storage Cabinet .....	427
15. Shotgun and Gun Safe .....	298
16. Small Hand and Power Tool Cabinets/Lock .....	350
17. Sawdust Vacuum .....	187
18. Electric Air Compressor .....	687
19. Portable Electric Circle Saw .....	100
20. Radial Arm Saw .....	480
21. Miter <b>Box/Back</b> Saw .....	100
22. Hand Truck, <b>400</b> lb. Capacity .....	91
23. Bench Grinder, <b>3/4</b> HP .....	150
24. Electric Drill and Bits .....	140
25. Solder Gun Kit .....	30
26. Heavy Duty Staple Gun Set .....	60
27. Pop Rivet Gun Set .....	40
28. Hand Saws .....	60
29. Hack Saw .....	8
30. Come-A-Long .....	34
31. Hand Truck .....	91
32. Pipe Cutter .....	30
33. Wrecking <b>Prybar</b> (Small and Large) .....	30
34. Cloth and Metal Measuring Tapes .....	45
35. Wire and Paint Brushes .....	25
36. Tap and Die Set .....	130
37. Power Sanders .....	150
38. Pipe Threader .....	170
39. Rubber Mallet .....	10
40. Hammers, Sledges and Axes .....	150
41. <b>Pickaroon</b> .....	20
42. Bolt Cutter .....	20
43. Extension Cord with Trouble <b>Lite</b> .....	31
44. Garbage Cans .....	132
45. Miscellaneous .....	<u>1,500</u>
Subtotal .....	<b>\$ 8,760</b>

HATCHERY EQUIPMENT LIST BY FUNCTION

Function and Equipment	Estimated cost
<b>MAINTENANCE OF GROUNDS - GROUNDS</b>	
1. Shovels, Snow and Gardening .....	\$ 40
2. Lawn Mower - Gas .....	331
3. Wheelbarrow - Industrial .....	140
4. Garden and Leaf Rake and Hoe .....	30
5. Brush and Limb Trimmers .....	20
6. Garden Hose, Spray Nozzles and <b>Sprinklers</b> .....	<u>186</u>
Subtotal .....	\$ 747
 <b>C. HATCHERY BUILDING - OFFICE</b>	
1. Personal Computer/Printer .....	2,500
2. Calculator <b>with</b> Tape .....	89
3. Desks .....	510
4. <b>Chairs</b> .....	312
5. <b>Filing</b> Cabinets .....	126
6. Waste Baskets .....	42
7. Table .....	200
8. Book Case and Credenzas .....	275
9. Clock .....	60
10. Stapler, Tape, Pens, etc. ....	<u>100</u>
Subtotal .....	\$ 4,214
 <b>HATCHERY BUILDING - LAB</b>	
1. Laboratory Stools .....	\$ 88
2. Glassware .....	200
3. Chemicals .....	200
4. <b>Microscope, 100X</b> .....	2,200
5. <b>Dissecting</b> Mi croscope .....	620
6. Balance Scales .....	240
7. Water Pollution <b>Kit</b> .....	269
8. Maximum-Minimum Thermometers .....	48
9. Calibrating Thermometers .....	95
10. <b>Dissecting</b> Tools .....	30
11. Propane Torch <b>with</b> Holder .....	50
12. Bench Top Autoclave .....	100
13. <b>Stir</b> Hot plates .....	<u>60</u>
Subtotal .....	\$ 4,200

HATCHERY EQUIPMENT LIST BY FUNCTION

Function and <b>Equipment</b>	Estimated cost
<b>HATCHERY BUILDING - CREW ROOM</b>	
1. Microwave Oven .....	\$ 250
2. Rooms, Mops and Dust Pans .....	20
3. Small Dinette Set .....	260
4. Refrigerator .....	350
5. cots .....	130
6. Lockers .....	400
7. Large Bulletin Board .....	<u>54</u>
Subtotal .....	<b>\$ 1,464</b>
 <b>D. SPAWNING - HOLDING POND</b>	
1. Egg Pails and Stands .....	\$ 208
2. Work Table .....	120
3. Portable <b>12</b> Cubic Foot Temporary Holding Tank .....	1,186
4. Adult Dip Nets .....	150
5. Adult Fish Crowder or Seine .....	300
6. Spawning Knives .....	80
7. Insulated Chest Coolers .....	120
8. <b>25-ft</b> House Trailer for Security During Spawning .....	10,000
9. Spawning Clothing, Gloves and Boots .....	234
10. Boom Hoist for Weighing Fish .....	671
11. Gloves, Boots .....	160
12. Lake <b>Merwin</b> Trap .....	<u>500</u>
Subtotal .....	<b>\$ 15,729</b>
 <b>E. INCUBATION</b>	
1. Egg Weighing Scoop .....	\$ 5
2. Egg Tongs .....	15
3. Burlap Bags .....	<u>15</u>
Subtotal .....	<b>\$ 35</b>

HATCHERY EQUIPMENT LIST BY FUNCTION

Function and Equipment	Estimated cost
<b>F. REARING - POND</b>	
1. Screen and Pond Brushes .....	\$ 128
2. Fish Weighing Scale/Holder .....	454
3. Hand Cart .....	257
4. Dip Nets - Small Fish .....	50
5. Seine - Small Fish .....	90
6. Rack and Screen Rakes .....	18
7. <b>Pump/Standpipe</b> for Filling Fish Hauling Tanks .....	435
8. Pond Crowders .....	1,200
9. Grader Boxes .....	390
10. Poles and Rakes .....	<u>66</u>
Subtotal .....	<b>\$ 3,088</b>
<b>REARING - FEED ROOM</b>	
1. Feed Weighing Scales .....	\$ 355
2. Hand Cart .....	257
3. Feed Buckets (5 gal.) .....	12
4. Feed Room Scoops .....	17
5. Feed Hopper .....	<u>300</u>
Subtotal .....	<b>\$ 941</b>
<b>REARING - GENERAL</b>	
1. Wash Down Pump/Suction and Discharge Hose .....	\$ 1,944
2. Portable High Pressure Washer Pump with Accessories .....	<u>2,000</u>
Subtotal .....	<b>\$ 3,944</b>
<b>G. SAFETY-FIRST AID - GENERAL</b>	
1. First Aid Kits (Shop & Trucks) .....	\$ 124
2. Stretcher/Wool Blanket .....	185
3. Safety Goggles .....	12
4. Respirator Mask/Filters .....	17
5. Air Splint Set .....	93
6. Hard Hats .....	36
7. Hazard Signs (Keep Out, Danger, etc.) .....	200
8. Fire Pump/Hose Nozzle .....	2,000
9. Fire Extinguishers (Buildings & Trucks) .....	300
10. Life Vests .....	60
11. Ear Cover - Noise Suppression .....	60
12. Bulletin Board .....	<u>54</u>
Subtotal .....	<b>\$ 3,141</b>
TOTAL FOR ALL EQUIPMENT .....	<b>\$185,536</b>
SAY .....	<b>\$186,000</b>
EQUIPMENT COST WITHOUT 2-1/2 TON TRUCK .....	<b>\$101,000</b>